

# Supplementary Material for “Faster Than Light, According to the Arithmetic: Two Ways a Streaming Benchmark Fails on Sub-Millisecond Paths”

Gustavo Pedro Ricou, Romaric Duvignau, Nikolas Herbst, and David Gregg

This document is supplementary material for the paper named above and is not part of the main submission. Main-text references of the form “Supplement  $S_n$ ” resolve to the correspondingly numbered section here. The provenance of every section — what moved here, from where, and when — is indexed in the artifact at `docs/supplement_index.md`.

## CONTENTS

|                                                                                                                  |    |
|------------------------------------------------------------------------------------------------------------------|----|
| <b>S1. The replay-rate provenance gap, in full</b>                                                               | 3  |
| <b>S2. The load-axis post-mortem, in full</b>                                                                    | 4  |
| <b>S3. The campaign ledger schema</b>                                                                            | 5  |
| <b>S4. OpenMessaging distributed mode, failure diagnostics</b>                                                   | 5  |
| <b>S5. The E1 reconciliation, in full</b>                                                                        | 5  |
| <b>S6. The broker comparison in full (moved from the main text)</b>                                              | 6  |
| <b>S7. The end-to-end withdrawal in full (moved from the main text)</b>                                          | 7  |
| <b>S8. The first corpus’s prior corrections (moved from the main text)</b>                                       | 9  |
| S8.1. The result . . . . .                                                                                       | 9  |
| S8.2. The checks it had already passed . . . . .                                                                 | 9  |
| <b>S9. Open questions from the comprehensive campaign (moved from the main text)</b>                             | 10 |
| <b>S10. The distributed-mode attempts in full (moved from the main text)</b>                                     | 11 |
| <b>S11. The workload in full (moved from the main text)</b>                                                      | 12 |
| <b>S12. The two-state model commentary and the tracing instrument checks (moved from the main text)</b>          | 12 |
| <b>S13. The commensurability account’s corrections in full (moved from the main text)</b>                        | 14 |
| <b>S15. Configuration in full (moved from the main text)</b>                                                     | 15 |
| <b>S16. Instrumentation of the external benchmark in full (moved from the main text)</b>                         | 15 |
| <b>S17. The transfer procedure with its incidents (moved from the main text)</b>                                 | 17 |
| <b>S18. Related work in full: variability literature and the result-by-result map (moved from the main text)</b> | 18 |

G. P. Ricou and D. Gregg are with the School of Computer Science and Statistics, Trinity College Dublin, Dublin 2, Ireland. E-mail: [pedrorig@tcd.ie](mailto:pedrorig@tcd.ie); [david.gregg@tcd.ie](mailto:david.gregg@tcd.ie).

R. Duvignau is with the Department of Computer Science and Engineering, Chalmers University of Technology, Gothenburg, Sweden. E-mail: [duvignau@chalmers.se](mailto:duvignau@chalmers.se).

N. Herbst is with the Chair of Computer Science II, University of Würzburg, Würzburg, Germany. E-mail: [nikolas.herbst@uni-wuerzburg.de](mailto:nikolas.herbst@uni-wuerzburg.de).

|                                                                                                                                                     |    |
|-----------------------------------------------------------------------------------------------------------------------------------------------------|----|
| <b>S19. Provenance-gap episode and the co-location withholding (moved from the main text)</b>                                                       | 19 |
| S19.1. A gap in our own provenance . . . . .                                                                                                        | 19 |
| <b>S20. The delay-sweep withdrawal in full (moved from the main text)</b>                                                                           | 19 |
| <b>S21. The experiment map, the claim-evidence table, and the audit threshold figure (moved from the main text)</b>                                 | 20 |
| <b>S22. Threats and limitations in full (moved from the main text)</b>                                                                              | 20 |
| <b>S23. Tables (moved from the main text; the pipeline schematic has returned to it)</b>                                                            | 23 |
| <b>S24. Tail recovery without a reference clock (moved from the main text)</b>                                                                      | 23 |
| <b>S25. The mechanism campaigns’ tables (moved from the main text)</b>                                                                              | 24 |
| <b>S26. The first result set (the model and flip figures were promoted to the main text in the round-1 internal revision)</b>                       | 24 |
| <b>S27. The grid table (moved to S23)</b>                                                                                                           | 24 |
| <b>S28. The mechanism campaign paragraphs in full (moved from the main text)</b>                                                                    | 25 |
| <b>S29. The audit, stamping-mode and injected-delay tables (moved from the main text)</b>                                                           | 26 |
| <b>S31. The spread rule and the grid-membership inference in full (moved from the main text)</b>                                                    | 26 |
| <b>S32. The mechanism narrative in full (moved from the main text)</b>                                                                              | 28 |
| <b>S33. Resolution, discarded samples and sampling artifacts: the literature engagement in full (moved from the main text)</b>                      | 30 |
| S33.1. The payload sweep’s underpowered rows, and the comprehensive campaign’s duration and plateau paragraphs (moved from the main text) . . . . . | 32 |
| <b>S34. Referee-round sensitivity artifacts (internal review, round 1)</b>                                                                          | 32 |
| <b>S35. How these results were reached: the chronology, and everything withdrawn</b>                                                                | 33 |
| S35.0. The phase excluded from every result . . . . .                                                                                               | 33 |
| S35.1. The answer we obtained first, and why it was wrong . . . . .                                                                                 | 33 |
| S35.2. The claim about the benchmark that we withdrew . . . . .                                                                                     | 33 |
| S35.3. The causality framing, withdrawn in this version . . . . .                                                                                   | 34 |
| S35.4. The M/G/I form, withdrawn . . . . .                                                                                                          | 34 |
| S35.5. The traced tail-index cross-check, withdrawn . . . . .                                                                                       | 34 |
| S35.6. Pre-registration outcomes . . . . .                                                                                                          | 34 |
| S35.7. A gap in our own provenance . . . . .                                                                                                        | 34 |
| S35.8. The distributed-mode gap . . . . .                                                                                                           | 34 |
| <b>S36. The audited-harness registry, in full</b>                                                                                                   | 35 |
| <b>S37. Two neighboring literatures, and what they do about the second clock</b>                                                                    | 36 |
| S37.1. “One-way latency” that is half a round trip . . . . .                                                                                        | 36 |
| S37.2. Drift-aware synchronization in MPI benchmarking . . . . .                                                                                    | 36 |
| <b>S38. Where the stamp is written, in other runtimes</b>                                                                                           | 37 |
| <b>S39. Neighboring rules, and what they already require</b>                                                                                        | 37 |
| <b>S40. What standardized benchmarks require about resolution</b>                                                                                   | 38 |
| <b>S41. The classical statistics of a discarded zero</b>                                                                                            | 39 |
| <b>S42. Which clocksource, bounded from a measurement</b>                                                                                           | 39 |

|                                                                                                            |    |
|------------------------------------------------------------------------------------------------------------|----|
| <b>S43. Why the acknowledgment stamp is late, and why the broker is not the reason</b>                     | 41 |
| S43.1. Where each stamp is actually taken . . . . .                                                        | 41 |
| S43.2. Why one span cannot invert and the other can . . . . .                                              | 41 |
| S43.3. The second thread is not the mechanism . . . . .                                                    | 42 |
| S43.4. Two rivals: the scheduler itself, and the hypervisor . . . . .                                      | 42 |
| S43.5. Why averaging does not repair either mode . . . . .                                                 | 43 |
| S43.6. The redesign that does not help . . . . .                                                           | 43 |
| S43.7. Where the repairs belong . . . . .                                                                  | 43 |
| <b>S44. The scheduler constants, derived</b>                                                               | 44 |
| <b>S45. The metric map (moved from the main text)</b>                                                      | 44 |
| <b>S46. Grid membership, arm by arm (moved from the main text)</b>                                         | 44 |
| <b>S47. Every real-time-priority pair, and the ladder they make</b>                                        | 44 |
| <b>S48. What the brokers actually do (moved from the main text)</b>                                        | 46 |
| S48.1. Equivalence on gated artifacts . . . . .                                                            | 46 |
| S48.2. The condition that reverses the ordering . . . . .                                                  | 47 |
| S48.3. The falsifier, registered in advance . . . . .                                                      | 47 |
| S48.4. Why the standard testbed cannot see it . . . . .                                                    | 47 |
| <b>S49. The statistical inventory (moved from the main text)</b>                                           | 47 |
| <b>S50. The concurrent negative-span report, and where the readings part (moved from the main text)</b>    | 47 |
| <b>S51. The 1970 counter note, line by line (moved from the main text)</b>                                 | 48 |
| <b>S52. Two literatures the paper stands against (moved from the main text)</b>                            | 49 |
| S52.1. Production tracing reached the conclusion without the mechanism . . . . .                           | 49 |
| S52.2. A framework that does not have the problem . . . . .                                                | 49 |
| S52.3. How large the literature is that misses this . . . . .                                              | 49 |
| S52.4. Where scheduling delay comes from, and what the queueing account gets right . . . . .               | 51 |
| <b>S53. The two floored clocks behind the <math>-1000\mu s</math> signature (moved from the main text)</b> | 51 |
| <b>S54. The permutation null, constructed (moved from the main text)</b>                                   | 51 |
| <b>S55. The overnight campaign, prediction by prediction (moved from the main text)</b>                    | 51 |
| <b>References</b>                                                                                          | 52 |

*On the numbering.* Two numbers are absent: S14 and S30 were withdrawn when their material was folded into neighboring sections. The remaining numbers are left as they are because the main text, the artifact index and four rounds of correspondence all cite them, and renumbering would silently break every one.

Several sections below refer to “internal review” rounds and to material moved between revisions. These were adversarial reviews conducted within the project before submission, against the standards of the venues considered; the manuscript has not been submitted to, or reviewed by, any journal. They are recorded because the corrections they produced are part of the evidence, and because an audit whose own failures are hidden is worth less than one whose are not.

#### S1. THE REPLAY-RATE PROVENANCE GAP, IN FULL

Auditing the corpus turned the same scrutiny on our own record-keeping, and it did not survive it either. The main text summarizes this episode; this section is the full record, kept because the protocol rule it produced is weaker without it.

Replay plans built from StatsBomb carry a **baked-in**  $120\times$  **time compression**: a plan’s emission offset is already the match time divided by 120. The producer’s `--speedup` flag then multiplies that. So `--speedup 1` against such a plan is *not* real time, it is  $120\times$ ; true real time needs  $1/120$ . The same flag means different things depending on which plan it is pointed at, and getting it wrong is silent: the run completes, the wall time looks unremarkable, and the numbers stay plausible. We lost a campaign to it before adding a pre-flight that derives the value from the plan and then checks the achieved rate against elapsed wall time.

The part we cannot repair is retrospective. **No surviving artifact records the achieved replay rate of any run we report.** Several superseded Testbed A scenarios record the nominal `--speedup flag`, which is not the same thing: converting a flag to a rate requires the plan’s compression, and every plan those files name has since been deleted. Everywhere else the orchestrator wrote `speedup` into a per-campaign summary that lived beside the raw per-run data, and for the earliest corpora only the aggregated CSVs were kept. For the E1 corpus of Section VI-A of the main text the surviving evidence is contradictory: the commit that introduced it states the runs were made at true real time, the campaign script reconstructed afterwards specifies `--speedup 10`, and the flag’s meaning was corrected 21 hours later the same day. E1 was replayed at  $1\times$ ,  $120\times$  or  $1200\times$ , and we cannot say which.

*The rate is recoverable from the measurements, if not from the metadata.:* Having argued all paper that a physical constraint can decide what record-keeping cannot, we applied the same move here, and it works. The start-up cost of Section V-A of the main text is a clock: it lasts a fixed 102.6 ms of *wall* time, so the number of events it swallows depends directly on the replay rate. Counting how many events per run carry it therefore reads the rate back out of the data.

The E1 runs sort into cells by how many events they matched, and one cell is diagnostic. Fifteen Kafka runs matched exactly eight events, and their median scheduling lag is **52.34** ms (range 51.60–53.01) — not 103 ms, and not 1.6 ms. A median of eight values is the mean of the fourth and fifth. The only way to land midway between the two modes is for exactly four of the eight to be late, so the fourth value is a fast event and the fifth a slow one:  $(1.59 + 103.5)/2 = 52.6$  ms against 52.34 observed. Four is also exactly what the loop trace shows at a verified real-time rate (the window table in the main text), and it is what the plan predicts, since five events share  $t_{\text{sim}}=0$  and the first of them pays the block rather than inheriting it.

That cell excludes the accelerated alternatives outright. At  $120\times$  the prologue spans 12.3 s of match time and holds 16 events; at  $1200\times$ , 123 s and 112 events. Under either, all eight matched events would be inside it and the cell would read 103 ms. It reads half that. **E1 was replayed at true real time**, the commit record was right, and the campaign script reconstructed afterwards describes a different, earlier campaign. The remaining cells agree: runs matching five or seven events read 103 ms, as four late events out of five or seven must give.

*The inference has since been checked against the original script, and it holds.* Archiving the cloud driver before releasing it turned up the campaign as actually invoked, in a shell script in the operator’s home directory that no part of the repository had ever referenced. It specifies `--speedup 0.008333` —  $1/120$ , against a plan already compressed  $120\times$ , which is true real time — and its log’s first line, `E1 N=1 reps=8 00:39:40`, names the run directory the E1 artifact’s first row still points at. The arithmetic above and the flag agree.

We report that as a check rather than as the answer, because the order matters. The rate was determined from the measurements while the metadata was genuinely unavailable, and the script surfaced afterwards, by luck, from a machine that was about to be switched off. What the agreement establishes is not that E1’s provenance was fine all along — it was not — but that the recovery method returns the right answer when there is an answer to check it against. That is the one thing a physical-constraint argument can rarely demonstrate about itself.

The same script also explains a feature we had described and not accounted for. It passes `--max-t-sim 2`: two seconds of match time per run. The median of seven matched events that makes E1 under-powered, and that Section V-A of the main text treats as an opening burst, is that window. The burst is real and is why those seven events are the densest in the match; the reason there were only seven is that the campaign asked for two seconds.

We leave the disclosure standing rather than deleting it, for two reasons. The recovery was available only because the artifact we were chasing happened to be a wall-clock constant with a sharp signature, and the confirmation only because a virtual machine had not yet been destroyed; a reader should not have to reconstruct an experimental parameter by arithmetic on its results, and next time there may be nothing to reconstruct it from and nothing left to check it against. And the exercise makes the protocol rule concrete: what was missing was one number, written down once.

*What the gap touched.:* The audit is unaffected either way: a negative transport is causally impossible at any replay rate, and the rejection counts are arithmetic on surviving per-event data. The withdrawal in Section V-A of the main text is unaffected by construction — we give the argument in a form that holds at every candidate rate. The rules of Section VI-B of the main text were measured after the pre-flight existed, at a derived and verified rate. Section VI-A of the main text’s external validity is restored by the recovery above, and the recovered script now documents it as well — though the inference stood on its own before the script appeared, and is what we would still be relying on had the machine been released a day earlier. Section VI-B of the main text carries the rule that would have made all of this unnecessary.

## S2. THE LOAD-AXIS POST-MORTEM, IN FULL

Moved from the main text’s mixture development: the load-axis post-mortem in full. The main text keeps the admissions and the numbers.

*Both load-axis predictions failed, including ours.:* The knee sweep placed conditions at achieved  $\rho$  of 0.881, 0.920, 0.950, 0.970 and 0.990, where the candidate forms diverge most; the earlier ladder stopped at 0.878 and everything above it collapsed onto a degenerate  $\rho = 1.000$ , which is why Section VI-B of the main text could not settle the question. With those points in hand, M/G/1 fits *worse than the mean* ( $R^2 = -0.05$  against a fitted exponential’s 0.93). The withdrawal does not merely stand: the forms are now separated, and M/G/1 is the one ruled out.

TABLE I

THE SAME RUNS REPRODUCE BOTH PUBLISHED ANSWERS. TRANSPORT MEDIANS (MS) FROM THE POWERED CAMPAIGN, COMPUTED OVER EVERY EVENT AND OVER EACH RUN’S FIRST SEVEN EVENTS IN EMISSION ORDER — THE WINDOW E1 SAW. THE ALL-EVENTS COLUMNS REPRODUCE THE POWERED 0.41 MS SHIFT; THE PROLOGUE COLUMNS REPRODUCE E1’S NEAR-EQUALITY (THE MAIN TEXT) IN BOTH SHIFT AND ABSOLUTE LEVEL. THE WINDOW, NOT THE BROKERS, ACCOUNTS FOR THE DISAGREEMENT.

| <i>N</i> | Runs | All events |       |       | First 7 (prologue) |       |       |
|----------|------|------------|-------|-------|--------------------|-------|-------|
|          |      | Kafka      | Redis | Shift | Kafka              | Redis | Shift |
| 1        | 5    | 0.476      | 0.095 | 0.381 | 0.831              | 0.743 | 0.088 |
| 9        | 45   | 0.533      | 0.116 | 0.417 | 0.939              | 0.810 | 0.129 |
| 12       | 55   | 0.527      | 0.113 | 0.414 | 1.018              | 0.769 | 0.248 |

The bounded prediction fared better but also failed. Over  $\rho = 0.881$  to  $0.990$  the rate grew by a factor of 1.44. M/G/1 predicted 13.8; the bracket we registered before the sweep predicted 2.45–3.07. The rate saturates, as a bounded mechanism requires — but harder than our own extrapolation allowed, and a prediction that misses low is still a prediction that missed. We report it as a failure rather than as the nearer of two misses.

The two failures have one cause, and E-A5 names it. Our bracket was still parameterized in  $\rho$ , through  $p = \rho^C$ ; E-A5 shows  $\rho$  does not determine occupancy. What survives is the mechanism — established by manipulation — and not any curve in  $\rho$ , ours included.

### S3. THE CAMPAIGN LEDGER SCHEMA

One row per cell of every instrumented-benchmark campaign, docs/results/external\_campaigns\_index.csv:

- `campaign`, `cell` — sub-campaign directory and cell name; the cell name encodes the swept axis (l load percent, s message size, r producer rate) and replicate number, e.g. `r625_rep3`.
- `level` — the numeric value of the swept axis.
- `valid` — 1 if the cell’s counts are usable under the pre-stated rule; 0 rows are retained with a reason, never deleted.
- `count_source` — `shutdown_hook` for exact end-of-run counters; `periodic_quantised` for in-run lines (quantized to  $10^4$ , excluded from analysis); `none_in_log` when no counters were written.
- `kept`, `discarded_zero`, `discarded_negative` — the instrumented guard’s three counters, separated by sign.
- `log_bytes`, `log_sha256` — size and hash of the run log the row was built from, so any row can be re-derived and checked against its source.

The Python-harness campaigns (no JVM, Section on generality in the main text) use the same cell naming and publish docs/results/external/harness\_results.csv with per-cell counts, sign-separated discards, and pacer-jitter percentiles.

### S4. OPENMESSAGING DISTRIBUTED MODE, FAILURE DIAGNOSTICS

Eleven attempts in total never produced a measurement. The three diagnosed attempts of the referee campaign (chain 18, block E) fail identically at OMB commit 5b1fa70: `java.util.concurrent.CompletionException` wrapping `java.lang.IllegalArgumentException` in the coordinator-worker path, before any workload starts. Per attempt, the version, full coordinator and worker logs, and the extracted signature are archived in docs/results/external/dist\_diag/; a draft upstream report is at docs/omb\_distributed\_issue.md (not filed — filing is the author’s action).

*Moved from the main text (internal review, round 1).*: The cross-host case is the one in which OMB’s subtraction spans two clocks, and its own distributed mode never completed a run in our hands — eleven attempts, all failing identically inside its coordinator-to-worker protocol, including with no background load at all, which refutes our own load-starvation hypothesis. Its cross-host exposure therefore rests on source audit, the pattern itself measured across two clocks in the main text (per-attempt record and draft upstream report: supplementary material S4). We do not claim any published result obtained with this benchmark is wrong: exposure depends on a deployment’s path latency and producer rate, and we audited none — why we recommend publishing a retention rate as routine practice, at the cost of one number.

### S5. THE E1 RECONCILIATION, IN FULL

Moved from Section VI-A of the main text: the complete windowed re-analysis showing E1’s near-equality is the observation window and nothing else.

*Why E1 saw near-equality, tested directly.:* The two campaigns disagree by more than power: E1 puts both systems near 0.8 ms and within 0.1 ms of each other, while the powered campaign puts them at 0.53 and 0.11 ms and 0.41 ms apart. Attributing that to seven events is an explanation only if it survives being checked, so we checked it. If the difference is the observation window and nothing else, then restricting the *powered* runs to their first seven events — in emission order, the same events E1 would have caught — must reproduce E1, and the same runs must give the powered answer over their full length. That is a prediction with one free parameter fixed in advance, and it can fail.

It does not fail (Table I). Over all events the runs give shifts of 0.381, 0.417 and 0.414 ms, reproducing the powered 0.41 ms. Over their first seven they give 0.088, 0.129 and 0.248 ms — E1’s wandering near-equality, and of the same magnitude as E1’s own 0.021, 0.116 and 0.053 ms. The *absolute* medians match as well, which the shift alone does not force: the prologue puts Kafka at 0.83–1.02 ms and Redis at 0.74–0.81 ms, against E1’s 0.79–1.00 and 0.72–0.86. One set of runs, one rate, one protocol, two windows, both published answers.

So E1 is not wrong and the campaigns do not contradict each other. E1 measured the opening burst, during which both systems are slow for the reason Section V-A of the main text establishes — topic auto-creation, connection setup, and the first blocking `produce()` — and that shared start-up cost swamps a 0.41 ms difference. As the run lengthens the cost dilutes, and the brokers’ steady-state separation emerges. The seven-event corpus answered a question about start-up while appearing to answer one about brokers, which is the same failure of window selection as Section V-A of the main text, one level up.

#### S6. THE BROKER COMPARISON IN FULL (MOVED FROM THE MAIN TEXT)

*What this claim rests on.* We state the evidential basis first, because an earlier version of this section rested it on the wrong corpus. The load-bearing measurement is a powered replication at a replay rate that is *derived from the plan and verified against wall time before the campaign runs* — a documented setting, not an inferred one — over a median of 125 audit-surviving events per run. The original E1 corpus (Table II) is reported afterwards, as the historical measurement it is, for two reasons that disqualify it from carrying the claim: its replay rate is an inference — recovered in the main text as true real time, but inferred from the runs rather than recorded — and it matched a *median of seven events per run*, the same seven-event opening burst as the scheduling lag we withdraw in the main text. A sub-millisecond difference cannot be resolved on seven events, and E1 does not resolve one: its Hodges–Lehmann shifts wander (0.021, 0.116, 0.053 ms) and its  $N=1$  estimators disagree. That E1 finds the two systems “equal” is as much a statement about seven events as about the brokers. What E1 does establish, and what the powered campaign confirms, is the *concurrency* result: Kruskal–Wallis finds no significant effect of concurrency in either backend ( $p = 0.061$  for Kafka,  $p = 0.091$  for Redis), and neither system degrades across the range.

*The powered measurement.:* We measured transport directly, at a replay rate derived from the plan and verified against wall time, over a median of 125 events per run rather than seven, at  $N \in \{1, 9, 12\}$  with 15 replicates each (Table III). The numbers are computed over audit-surviving runs only — the campaign’s own retention, the gate’s effect on every estimate (at most 0.003 ms on the shift) and the worst-case imputation flip point are Table XXIII in S34 — and the instrument stamps in microseconds on one clock, so neither failure mode of this paper touches the numbers that follow. The picture is sharper and it is not the one E1 painted. Broker transport is Kafka  $\approx 0.54$  ms against Redis  $\approx 0.11$  ms: a Hodges–Lehmann shift of 0.41 ms, Kafka slower, with a bootstrap 90% interval of width  $\pm 0.006$  ms and  $p < 10^{-26}$  at every  $N$ . The two systems are *not* statistically indistinguishable; Redis’s in-memory `XADD` really is several times faster per operation than Kafka’s replicated-log append, which is the direction the gray-literature comparisons report.

And yet the same three estimators — Welch, percentile bootstrap and Hodges–Lehmann — agree that the difference is *equivalent within one millisecond* at every  $N$ , because that shift is comfortably inside that margin. Both statements are true and neither is idle: against the seconds-scale human annotation latency that dominates any live sports feed’s end-to-end budget, a broker difference is parts in 100,000 of the end-to-end path, so for choosing a broker it is noise; but it is a real, tight, reproducible effect that a properly powered instrument resolves and a seven-event one cannot. The shift is also flat across concurrency (0.408, 0.416, 0.417 ms at  $N = 1, 9, 12$ , audit-gated; S34), so neither system degrades. A part of even this residual is the instrument rather than the broker: the main text shows that 0.07 ms of the gap is the asymmetric acknowledgment stamp — a different quantity from the inter-host clock offset of Section III-A, which happens to be the same size —, leaving a true broker-transport difference near 0.34 ms. That 0.07 ms is a concrete instance of the blind spot of the main text: it is a bias smaller than the quantity measured, so it never turns a value negative and the consistency check passed both corpora that carried it. The check guarantees a corpus is not *catastrophically* wrong; resolving a 0.07 ms instrument artifact still took a controlled experiment.

An independent replication confirms it. A second powered campaign, run days apart with the same protocol, gives Hodges–Lehmann shifts of 0.397, 0.412 and 0.413 ms at  $N = 1, 9, 12$  — inside the 90% interval of the first campaign at every level, with overlapping intervals throughout. The 0.41 ms advantage is not a fluctuation of one campaign.

This refines E1 rather than contradicting it, and it sharpens the contradiction with the first-answer table in the main text: the accelerated corpus reported Redis *degrading* with concurrency; the powered real-time measurement finds Redis uniformly *faster* and flat. The reversal is the audit’s doing, and the measurement’s.

TABLE II

**HISTORICAL CORPUS; THE SCHEDULING-LAG COLUMNS ARE WITHDRAWN.** END-TO-END DELAY AND ITS DECOMPOSITION, TESTBED B, AFTER THE CONSISTENCY CHECK (164 OF 201 RUNS RETAINED). MEDIAN, MS. **THE TTI AND SCHEDULING-LAG COLUMNS RECORD A PER-RUN START-UP COST, NOT A PER-EVENT PROPERTY, AND ARE RETAINED ONLY AS EVIDENCE FOR THE WITHDRAWAL IN THE MAIN TEXT; THEY SHOULD NOT BE READ AS SYSTEM BEHAVIOR.** THE TRANSPORT COLUMNS ARE COMPUTED OVER THE SAME SEVEN-EVENT OPENING BURST, AND SO MEASURE START-UP RATHER THAN STEADY STATE: SUPPLEMENTARY MATERIAL S5 REPRODUCES THEM FROM THE POWERED RUNS BY RESTRICTING THOSE RUNS TO THE SAME WINDOW. FOR STEADY-STATE TRANSPORT SEE TABLE III. THE REPLAY RATE WAS NOT RECORDED AND IS RECOVERED AS TRUE REAL TIME IN THE MAIN TEXT.

| N  | TTI   |       | Sched. lag |       | Transport |       |
|----|-------|-------|------------|-------|-----------|-------|
|    | Kafka | Redis | Kafka      | Redis | Kafka     | Redis |
| 1  | 105.3 | 5.0   | 103.0      | 1.4   | 0.792     | 0.721 |
| 9  | 105.5 | 5.4   | 103.0      | 1.9   | 0.802     | 0.807 |
| 10 | 105.3 | 5.8   | 102.8      | 2.0   | 1.000     | 0.855 |
| 12 | 105.7 | 5.3   | 102.9      | 1.7   | 0.839     | 0.844 |

TABLE III

POWERED TRANSPORT REPLICATION AT A VERIFIED TRUE-REAL-TIME RATE, OVER A MEDIAN OF 125 EVENTS PER RUN (NOT THE SEVEN OF THE MAIN TEXT), AUDIT-GATED (S34). MEDIAN IN MS; THE HODGES–LEHMANN SHIFT IS *Kafka* – *Redis* WITH A PERCENTILE-BOOTSTRAP 90% INTERVAL. THE BROKERS ARE EQUIVALENT WITHIN 1 MS AT EVERY  $N$  (ALL THREE ESTIMATORS) YET CLEANLY DISTINGUISHABLE: REDIS IS  $\approx 0.41$  MS FASTER, AND THE SHIFT DOES NOT GROW WITH CONCURRENCY.

| N  | Events/run | Kafka | Redis | HL shift [90% CI]    |
|----|------------|-------|-------|----------------------|
| 1  | 148        | 0.512 | 0.102 | 0.408 [0.389, 0.419] |
| 9  | 112        | 0.542 | 0.120 | 0.416 [0.408, 0.423] |
| 12 | 121        | 0.540 | 0.114 | 0.417 [0.408, 0.424] |

*Why E1 saw near-equality, tested directly.:* If the disagreement between E1 ( $< 0.1$  ms apart) and the powered campaign (0.41 ms apart) is the seven-event window and nothing else, then restricting the powered runs to their first seven events must reproduce E1, and the full runs must reproduce the powered answer. Both hold: full-length shifts 0.381, 0.417, 0.414 ms against the powered 0.41; first-seven shifts 0.088–0.248 ms against E1’s 0.021–0.116, with absolute medians matching as well. The window explains the disagreement with one parameter fixed in advance; the full test, including the start-up decomposition it rests on, is supplementary material S5.

#### S7. THE END-TO-END WITHDRAWAL IN FULL (MOVED FROM THE MAIN TEXT)

TTI and transport give opposite answers in Table II. Of Kafka’s 105.5 ms, 102.9 ms is producer scheduling lag against Redis’s 1.8 ms, while broker transport is 0.84 and 0.80 ms. An earlier version of this paper reported that twentyfold end-to-end gap as a finding, attributed it to the client’s sender thread waking from idle, and built a practitioner recommendation on it.

That gap does not survive re-measurement, and the reason is a second instance of this paper’s own thesis. We report it at length for the same reason we reported the first, and we retain the figure that once carried it (Figure 2) rather than deleting the evidence.

*The offset is a start-up cost, not a per-event constant.:* Re-measuring at  $N=1$  on the same driver and the same broker, at a replay rate derived from the plan and verified against elapsed wall time, gives a median producer scheduling lag of 1.59 ms for Kafka, not 103 ms — with a *maximum* of 103.5 ms. Two independent instrumentation paths agree: the per-event loop trace and the per-run summary. The 103 ms is real, but it is paid once per run, not once per event.

We cannot call this a repetition of E1’s condition, because E1’s replay rate is not recoverable (the main text). That is why the argument below does not rest on the comparison between the two campaigns at all. It rests on a sweep that is internally controlled — one campaign, one rate, one match, only the window varying — and on an arithmetic relation that holds at every rate E1 could have used.

*A controlled test that separates the two.:* A median cannot distinguish a per-run cost from a per-event one, because how much of the cost the median sees depends on how many events the run contains — which is precisely what misled us. The quantity that *does* separate them is the *number* of affected events per run. A per-run cost predicts that number is fixed however long the run gets; a per-event constant predicts it grows with the run. We therefore replayed the same match at true real time under three observation windows, holding everything else fixed, and counted events waking more than 50 ms late (Table IV).

The count does not move (Figure 1). Going from the 60 s window to the 600 s window multiplies the events emitted by 8.9 — 57 to 507 — while the number waking more than 50 ms late stays at exactly four and exactly one send blocks, so the share of events paying the cost falls from 7.0% to 0.8%. The median is flat at 1.6 ms throughout and the maximum flat at 103.5 ms: the cost is present in every run and dilutes in every run, which is the signature of something paid once. Had it been a per-event constant, the count would have grown with the window and the median would have stayed at 103 ms.

A once-per-producer cost of this kind is documented upstream: a Kafka producer performs a metadata lookup before its first send to a topic it has not yet cached [1]. We did not isolate that call, so we do not claim it *is* the mechanism — the window

sweep constrains the cost's *shape*, not its origin. We note it because the shape we measure and the shape the client documents agree, and because a reader deciding whether this generalize beyond our testbed should know the behavior is a property of the client rather than of our rig.

Redis was run in the same sweep on the same events, with the same loop trace, and has *no* events waking more than 50 ms late and *no* blocking send at any window. Its worst single event anywhere is under 25 ms. Instrumenting both arms identically matters here for a reason internal to this paper: an earlier version of this table reported Redis's counts as zero when its producer in fact carried no trace, which is the absence of a measurement dressed as one — exactly the failure the paper is about. We added the trace to the Redis producer and re-ran both arms together.

*The mechanism, read directly off the loop trace.:* The per-event trace shows the same five-event signature in every Kafka run, at every window:

| event | wake late (ms) | send blocked (ms) |
|-------|----------------|-------------------|
| 0     | 0.17           | <b>102.60</b>     |
| 1     | <b>102.96</b>  | 0.07              |
| 2     | <b>103.08</b>  | 0.05              |
| 3     | <b>103.17</b>  | 0.04              |
| 4     | <b>103.30</b>  | 0.05              |
| 5     | 0.94           | 0.27              |
| 6     | 1.42           | 0.06              |

The first `produce()` blocks for 102.6 ms fetching metadata and creating the topic. The replay loop is single-threaded, so every event due while it is blocked wakes roughly 103 ms late and then sends in tens of microseconds. There are exactly four of them, and the reason is the sport rather than the harness: this plan's first five events all carry  $t_{\text{sim}}=0$ , because a kickoff is recorded as a pass, a ball receipt and a carry inside the same second. That is not particular to this match — every one of the eleven plans in our corpus opens with at least five events at  $t_{\text{sim}}=0$ . A football feed therefore delivers its densest burst precisely when the producer is coldest, which is the worst possible alignment for a start-up cost and the reason it lands in the median rather than the tail. From event 5 the loop is in steady state at about 1 ms. One cost, paid once, is charged to five events; the sixth onward pays nothing. Redis shows no such prologue because XADD to a new stream creates it in the same round trip.

That closes it. Five events carry the cost, seven were matched, and the median of seven values of which at least four are 103 ms is 103 ms. The published figure is the arithmetic of its own prologue.

*Why the original corpus could not see that, and how we know.:* The E1 runs behind Table II replayed the first 600 s of match time, which in this plan holds **507 events**. They matched a **median of seven** — 745 events across 100 Kafka runs, a match rate near one percent. The window was not the problem; the join was. And the seven that survived it are not a random seven.

That last claim is arithmetic rather than inference. Those runs report a median producer scheduling lag of 102.93 ms over seven values, and a median of seven values at 102.93 ms requires *at least four of the seven* to be 102.93 ms or greater. The loop trace says exactly how many events per run are ever that late: four (Table IV), and always the same four — those due while the first send blocks. The matched set must therefore consist almost entirely of the prologue. The plan's first five events are all stamped at  $t_{\text{sim}}=0$ , so they are the first candidates a consumer sees and the first a lossy join keeps.

The failure thus compounds: a sample of seven is small, but a sample of seven *selected towards the contaminated events* is worse than small. Redis reports 1.75 ms on the same events because opening a stream with XADD does not pay what Kafka's first send pays in metadata fetch and topic creation, so the same selection costs it nothing.

*Why not knowing E1's replay rate does not matter here.:* The blocking first send lasts 102.6 ms of *wall* time, so at a replay rate of  $R$  times real time it spans  $0.103R$  seconds of *match* time. Evaluating that against the plan for each rate E1 could have run at:

| Replay rate | Match time spanned | Events inside the prologue |
|-------------|--------------------|----------------------------|
| 1×          | 0.10 s             | 5                          |
| 120×        | 12.3 s             | 16                         |
| 1200×       | 123.1 s            | 112                        |

E1 matched a median of seven events per run. At every one of the three candidate rates the prologue already contains at least four events — enough to carry the median of seven — so the matched sample's median is the start-up cost, which is what the corpus reports. The conclusion is therefore insensitive to the replay rate; the main text goes on to recover that rate from the same start-up cost, but the withdrawal does not depend on the recovery.

This also explains the three properties we previously offered as evidence, and each of them is equally consistent with a start-up cost: a per-run constant looks *constant* within a run; it is *concurrency-invariant* because every run pays exactly one regardless of  $N$ ; and it is *rate-dependent* because accelerated replay packs more events into the window and dilutes it. We read three signatures of a per-event mechanism into measurements that a per-run mechanism explains at least as well.

*The general lesson.:* The integrity check of the main text does not catch this. Every one of those runs is causally consistent; nothing is negative; the medians are stable to three significant figures across a hundred runs. What went wrong is that a median



TABLE IV

THE OBSERVATION-WINDOW SWEEP THAT SEPARATES A PER-RUN COST FROM A PER-EVENT ONE. SAME MATCH, SAME DRIVER, SAME BROKER,  $N=1$ , TRUE REAL-TIME REPLAY; ONLY THE WINDOW CHANGES. BOTH PRODUCERS ARE LOOP-TRACED, SO THE COUNTS FOR THE TWO SYSTEMS COME FROM THE SAME INSTRUMENT. EVENTS EMITTED GROW  $8.9\times$  ACROSS THE SWEEP, BUT THE NUMBER OF KAFKA EVENTS WAKING MORE THAN 50 MS LATE DOES NOT MOVE, AND EXACTLY ONE SEND BLOCKS IN EVERY RUN; REDIS HAS NEITHER AT ANY WINDOW. COUNTS ARE MEDIAN OVER THREE REPLICATES FROM THE PER-EVENT TRACE; PERCENTILES COME FROM THE PER-RUN SUMMARY.

|       | Window<br>(s) | Events  |         | Scheduling lag (ms) |       | Events > 50<br>ms late | Blocking<br>sends |
|-------|---------------|---------|---------|---------------------|-------|------------------------|-------------------|
|       |               | emitted | matched | median              | max   |                        |                   |
| Kafka | 60            | 57      | 57      | 1.56                | 103.4 | 4                      | 1                 |
|       | 180           | 148     | 148     | 1.61                | 103.5 | 4                      | 1                 |
|       | 600           | 507     | 465     | 1.58                | 103.5 | 4                      | 1                 |
| Redis | 60            | 57      | 57      | 1.50                | 17.4  | 0                      | 0                 |
|       | 180           | 148     | 148     | 1.56                | 20.4  | 0                      | 0                 |
|       | 600           | 507     | 465     | 1.53                | 24.8  | 0                      | 0                 |

over seven events was reported as a property of the system rather than of the window, and the tight agreement across runs made it look robust precisely because the artifact is deterministic. A benchmark can be internally consistent, gate-clean, and still measure its own start-up. We therefore add to the main text the requirement to report events-per-run alongside any latency percentile, since a percentile over single-digit samples is a statement about the harness.

*What we claim instead.*: On broker transport — the quantity that survived the main text and is measured over the same events for both systems — Kafka and Redis remain equivalent within one millisecond (the main text). We make no end-to-end claim. The twentyfold figure is withdrawn.

*The benchmark’s own output corroborates the insensitivity (moved from the main text, internal review, round 1).*: The benchmark’s own output corroborates this without our instrumentation: across eight runs all 32 reported percentiles are whole milliseconds (only the averages, means of integers, are fractional), and three runs report  $p_{50} = p_{95} = p_{99} = \max = 1.0$  — not a narrow distribution but one with a single value in it, printed to three decimal places.

#### S8. THE FIRST CORPUS’S PRIOR CORRECTIONS (MOVED FROM THE MAIN TEXT)

We present the first result set in full rather than describing it, because a reader cannot otherwise judge how convincing an invalid corpus looks.

##### S8.1. The result

On Testbed A, replaying distinct real matches at ten times real speed across one, five and ten feeds with 15–30 runs per cell and both producers pipelined, broker transport separated the two systems cleanly (the main text). Every comparison was significant after correction and at  $N \geq 5$  the run distributions did not overlap.

##### S8.2. The checks it had already passed

The corpus was not naive. It was the product of five earlier corrections, each of which had reversed the apparent winner and each found by investigating a result that looked wrong:

- 1) *A process-relative clock.* Cross-process timestamps taken with `perf_counter_ns`, whose origin is per-process, injected each run’s consumer start-up offset into every measurement. Fixed with a shared wall-clock epoch.
- 2) *A saturating replay speed.* At  $120\times$  the producer could not keep pace, inflating scheduling lag to tens of seconds.
- 3) *An asymmetric load generator.* The Kafka producer blocked on a broker round trip per event while the Redis producer dispatched asynchronously. Median TTI at one feed fell from 1,644 ms to 16 ms once the Kafka producer was pipelined.
- 4) *A concurrency axis that was covertly a throughput axis*, from the merged-plan design described in the main text.
- 5) *A heavy tail contaminating every mean.* Kafka’s end-to-end 95th percentile sat at 99–105 ms at every concurrency level while its median moved from 1.8 to 7.2 ms. A 95th percentile that ignores load is not system behavior; decomposition located it in scheduling lag, not transport.

We also verified the comparison was not biased by message size or protocol: payloads are near-identical (median  $\approx 170$  bytes) and serialization costs are negligible and comparable.

A sixth problem shaped our later protocol. Our first run of the acknowledgment experiment of the main text reported no improvement whatsoever — a clean refutation of our own hypothesis. The treatment had never reached the consumer: the orchestration script accepted the option but, through a failed edit, never passed it on. We found this only by deliberately supplying an invalid option and observing that the consumer did not reject it. A null produced by an unapplied treatment is indistinguishable in the data from a genuine one, so every intervention reported here carries a manipulation check that aborts the campaign if the treatment is not accepted.

The point of the list is not the corrections. It is that a corpus which had survived six of them, a fairness audit, and a full battery of rank tests, effect sizes and multiplicity correction, was still entirely invalid, and nothing in its output said so.




Fig. 1. The window sweep, as a picture. (a) Events emitted per run grow  $8.9\times$  while the number waking more than 50 ms late stays at four — a per-event constant would put the two series on parallel lines. (b) The same fact as a proportion: the share of events paying the cost falls as  $1/\text{events}$ , the dilution a once-per-run cost predicts. Redis, on the same events, has no affected events at any window.

#### S9. OPEN QUESTIONS FROM THE COMPREHENSIVE CAMPAIGN (MOVED FROM THE MAIN TEXT)

Three observations from the campaign are consistent with a single conjecture — a per-send jitter kernel whose width in cell units grows with the numerator  $p$  of  $\Delta/\tau$  — and none of them is established. We separate them from the results above deliberately: they are post-hoc, the pacer they implicate is measured only in the non-JVM replication of the main text, and one of our own follow-up tests cuts against the conjecture.

*Displacement toward  $\theta$ .* Replicates sit off their grid vertices toward the continuous value, from under a point to complete detachment. The two arms that detached outright (a majority of replicates more than 3 points from every vertex) are 300 msg/s in the evening pass and 700 msg/s — both with  $p = 10$ ; no arm with  $p \leq 8$  detached, and the same evening that 300 msg/s detached, 625 msg/s ( $p = 8$ ) produced its cleanest two-branch split of the study. Suggestive; a census of two is not a law.

*Mobility between passes, now measured under control.* The same 300 msg/s configuration was branch-adjacent in the morning and detached in the evening; passes were hours apart, so epoch and arm were confounded. The controlled test interleaves the two arms A/B/A/B within one session — four pairs of (300, 625) msg/s — and **both arms hold their grids**: 300 msg/s at 37.40, 38.21, 39.86 on the lower vertex and 67.41 on the upper; 625 msg/s at 42.97 and 55.91–60.18 (the `ultimate_alt` cells of the artifact). No arm detached. The detachment is therefore a property of the *epoch*, not of the arm, and the numerator census above loses its same-evening contrast — which cuts the kernel conjecture’s strongest support and is reported accordingly. What




Fig. 2. **Withdrawn.** (a) End-to-end delay against concurrency as originally measured. (b) The decomposition that appeared to place the whole gap in producer scheduling lag. Both panels are retained as evidence for the main text: the runs behind them matched a median of seven events each, so the apparent per-event offset is a per-run start-up cost. Broker transport, the lower series in (b), is unaffected and is what the paper claims.

remains established is that some sessions produce a detached regime and others do not, at fixed configuration; the disciplined clock is exonerated throughout (residual 0.013 ppm), and the pacing loop’s state remains the open suspect.

*Branch suppression.* The formal residual analysis (the main text) finds mean retention *below*  $\theta$  at every  $q \geq 3$  arm, and the rank correlation of  $|\text{residual}|$  with  $p$  is negative ( $-0.8$ ), not the positive association a displacement-scaling kernel predicts — the sign is dominated by branch-weight sampling at  $q = 1$ . What the residuals do support is minority-branch suppression: a kernel narrower than the half-cell keeps runs on the nearest vertex, depressing the upper-branch weight below  $\text{frac}(q\theta)$ , which would also account for the 1250 msg/s miss above. A quantitative displacement prediction from a measured jitter statistic does not yet exist; the harness of the main text records the statistic per run and is where one would be built.

#### S10. THE DISTRIBUTED-MODE ATTEMPTS IN FULL (MOVED FROM THE MAIN TEXT)

The cross-host case is the one in which OMB’s subtraction spans two clocks, and therefore the one in which its guard could discard a genuine causality violation. **OMB’s own distributed mode cannot report a measurement of it.** Across eleven attempts — eight at three background-load levels including none at all, which refutes our own hypothesis that CPU

starvation was the cause, and three further attempts run with full diagnostics for this revision — the benchmark’s distributed mode never completed a run, failing each time inside its own coordinator-to-worker protocol rather than in our instrumentation or configuration. The validity gate wrote `valid=0` with a reason on every attempt; per-attempt versions, logs and failure signatures are archived in the artifact and summarized in supplementary material S4, and a draft upstream report accompanies them.

The exposure of OMB-in-distributed-mode is therefore established by source audit — the timestamp is written on the producer’s host and read on the consumer’s, and the guard drops whatever the difference produces — and *not* by observing that binary. What *is* now observed is the pattern itself across two hosts: the harness of the main text runs the identical stamp-subtract-guard logic over two disciplined clocks across 12 runs, and measures 0 negatives in 905,040 samples, an intact grid, and a deleted fraction coupled to clock-offset drift. The two statements are complementary and we keep them distinct: the pattern’s cross-host behavior is measured; OMB’s own distributed binary remains unmeasurable by us.

*What we do not claim.:* That any published result obtained with this benchmark is wrong. We have shown that the deletion happens, that it is large, that it is irreproducible, and that it is unreported. Whether it has affected a specific published measurement depends on that measurement’s path latency and producer rate, and we have audited none. That asymmetry is the reason we recommend publishing a retention rate as routine practice: its cost is one number, and the alternative is a benchmark that cannot report its own failure.

#### S11. THE WORKLOAD IN FULL (MOVED FROM THE MAIN TEXT)

The workload is a live football event feed, and we describe it only as far as the results require. Full characterization of 3,315 matches from the StatsBomb open dataset [2], spanning 52 competition-seasons from 2003 to 2023, is available in the artifact; event data of this kind is collected by trained human operators, whose accuracy has been studied [3], [4].

Three properties of the workload drive every experimental choice (Table V). We name, for each, the later result that depends on it, because a setting section that cannot say what it is for should not be in the paper. A reader who wants only the measurement contribution can note that the workload supplies three things a synthetic generator would not have supplied — a sparse arrival process, a burst at a known instant, and an empirically bounded concurrency — and skip to the main text.

**It is sparse.** A match produces a median of 3,507 events over roughly 8,412 seconds, a mean rate of **0.415** events per second. This is four orders of magnitude below the rate at which either broker begins to strain, and it is the property that makes the main text’s result possible.

**It is bursty, and one burst has a known instant.** Over a sliding ten-second window the same feeds peak at 2.70 events per second, a peak-to-mean ratio of 6.45; half of all inter-arrival gaps are one second or shorter. The feed is idle most of the time and busy in short bursts. One of those bursts is special: a kickoff is recorded as a pass, a ball receipt and a carry inside the same second, so *every* match in our corpus opens with at least five events sharing  $t_{\text{sim}}=0$ . That coincidence — the densest burst arriving when the producer is coldest — is what turns a one-off client start-up cost into the median of a short run, and it is the mechanism behind the withdrawal in the main text. A synthetic Poisson generator has no kickoff, and would not have produced it.

**Its concurrency is bounded and knowable.** Match records carry kick-off times, so the number of simultaneous feeds is empirical rather than swept. Across 2,346 kick-off instants the largest carries **12** simultaneous matches, and at most **21** are in play at once. Domestic leagues schedule the final matchday simultaneously by rule, so a 20-team league plays ten concurrent matches. We therefore benchmark at  $N \in \{1, 9, 10, 12\}$ : the median slot, the upper quartile, the structural league bound, and the observed maximum. This is what keeps the concurrency axis of the main text from being an arbitrary sweep — the levels are measured facts about the domain, not round numbers. Two limits apply. The dataset is a sample, so observed simultaneity is a lower bound; and the bound is per league, so a platform serving many competitions faces their sum.

Taken together these also explain why the broker question turned out to be the least interesting thing we could have asked, and we would rather say so here than let a reader discover it in the main text. At 0.415 events per second and at most a dozen concurrent feeds, this workload sits four orders of magnitude below where either broker strains. The domain that made the failure visible is the same domain in which the original question has a boring answer.

#### S12. THE TWO-STATE MODEL COMMENTARY AND THE TRACING INSTRUMENT CHECKS (MOVED FROM THE MAIN TEXT)

Figure 3 draws the model this section defends.

*What it accounts for.:* Clustering follows by construction: being preempted is an *interval*, so the events inside it are corrupted together and a two-state process cannot help but cluster. The  $60\times$  growth in tail weight against  $5\times$  in core width is two different parameters moving —  $\sigma_c$  belongs to the running state,  $p$  to the scheduler. The scale family fails because a scale family has one parameter and here two move at very different rates.

*A prediction that points the opposite way.:* The two structures disagree geometrically. A scale family changes  $\sigma$ , so its tail curves *rescale horizontally*; the main text changes  $p$ , so its curves *shift vertically and stay parallel* on a log scale. Taking the log ratio of two conditions’ tail masses at several thresholds, the two-state model predicts a constant, independent of the threshold.

TABLE V

THE WORKLOAD, FROM 3,315 MATCHES. MEDIAN ACROSS MATCHES; PEAK RATE IS THE MAXIMUM OVER ANY SLIDING TEN-SECOND WINDOW.

| Property                    | Value      |
|-----------------------------|------------|
| Events per match            | 3,507      |
| Match duration              | 8,412 s    |
| Mean arrival rate           | 0.415 ev/s |
| Peak rate (10 s window)     | 2.70 ev/s  |
| Peak-to-mean ratio          | 6.45       |
| Median inter-arrival gap    | 1.0 s      |
| Distinct kick-off instants  | 2,346      |
| Max simultaneous kick-offs  | 12         |
| Max matches in play at once | 21         |




Fig. 3. **The two-state model, drawn.** The stamping asymmetry  $\Delta$  has a narrow core when the stamping thread is running and a lobe at  $-3$  ms, the scheduler's base slice, when it is not, so a small  $T_{\text{true}}$  is inverted by the whole lobe and a large one only by what lies beyond it — which is why the check bites hardest on small effects. The shape is schematic, two components placed at the measured mode's location rather than a fit; the measured distribution is the traced stall spectrum of the main text.

Restricting to tail estimates backed by at least 20 events — nine far-tail points resting on five to eight events are excluded, as they carry log-scale errors larger than the effect — the median spread of that log ratio across conditions is **0.29**, a factor of 1.34, with a worst case of 0.91. Set against the  $23\times$  failure of the scale-family collapse, the tail curves are close to parallel. The two conditions with the largest spreads sit at intermediate load, where the residual distribution is plausibly still shifting, so the honest statement is  $\Pr[\text{inv}] = p(\rho) S(c; \rho)$  with  $p$  varying fast and  $S$  slowly: separability is a good first-order description rather than an exact law.

*What this is worth, and what it is not.* It is mechanistic — occupancy names the moving part — and actionable: if the failure is occupancy, the mitigation is a stamping thread the workload cannot preempt, not a better clock. But we found this by looking at the data; the separability test is exploratory (the main text), so we pre-registered a confirmatory version and ran it: the campaigns below, the decisive one being real-time priority at fixed utilization. Two states is the smallest model consistent with the data, not a kernel claim.

*On the load axis the model is a tautology, and we say so before using it.* Read as a function of  $ho$  alone the model has no content: with  $p$  unconstrained, any monotone rate curve can be written  $p(\rho) S$ ; the model's content is on the threshold axis, where it passed. Constraining  $p$  to a power law fits poorly ( $R^2 = 0.65$  in log space). The form that restores the divided-out  $\sigma$ ,  $\Pr[\text{inv}] = p(\rho) S(T_{\text{true}}/\sigma(\rho))$ , reaches  $R^2 = 0.9905$  against 0.9811 (exponential) and 0.8863  $((\rho/(1-\rho))^k)$  at equal parameters — *and we do not report that lead as a result*: freezing  $\sigma$  at its mean improves the fit to  $R^2 = 0.9982$ , because  $\sigma$  and  $\rho$  move together on this ladder and no fit can credit one over the other. That is a design limit no further analysis of these data can lift.

*The instrument check, and what it can and cannot rule out.* Tracing a system to measure its scheduling behavior is exactly the kind of intervention that can create what it observes, so the traced cell has an untraced twin. Our first attempt at this campaign ran with a probe that failed to attach: the histogram was empty, but the negative-span rates are valid, and we kept that run as the control. It measured 0.2717 against the traced run's 0.2315 — the traced rate is 14.8% lower, two hours apart, same design.

We report that rather than a flattering comparison, because an earlier version of this section compared the traced cell against a different campaign's 88% arm (0.2214) and called the 4.6% gap a clean bill of health. The honest reading is weaker. The ordinary 88% arm has been measured five times across these campaigns and spans 0.221 to 0.305, a factor of 1.38; the traced value sits inside that spread, and so does its untraced twin. So we can say that tracing did not move the rate by more than the drift already present between campaigns, and we cannot say anything tighter than that. A tracing effect smaller than about

15% is not resolvable with this control.

What that limits is the *level*, which no claim here rests on. The comparison in the main text is between two quantities measured in the *same* run — a kernel histogram and a count of negative transports over the same events — so a common perturbation of that run moves both and leaves their agreement intact.

*The gate fired on our own replication, and we report the arm it withheld.* The check is a rule fixed in advance: a traced arm whose negative-span rate differs from its untraced comparator by more than 25% is not compared. The replication's 88% arm measures 0.1956 against the same untraced control's 0.2717 — a drift of 28% — so its verdict is withheld by the same mechanism that admitted the original. Its numbers are in the main text because withholding a comparison is not a reason to hide a measurement, and because the ratio it would have contributed, 1.06, is the closest agreement in the table. Reporting only the arms that passed would leave a reader with three ratios and no idea that one of them is inadmissible under our own rule.

*The real-time arm's zero is an artifact of the instrument, and the replication settles it.* Every traced real-time arm we have run — three of them, across two campaigns and two load levels — recorded *zero* negative spans in 2,985 events. The untraced twin of one of those arms recorded 15. Under that rate the chance of a single traced arm showing none is  $3 \times 10^{-7}$ , and of all three about  $10^{-20}$ .

We first reported this as unresolved: either the arm genuinely differed or tracing perturbed it, and one measurement could not separate the two. Three can. Attaching BPF to `sched_switch` suppresses the negative spans in the real-time arm, and the effect is not subtle — it removes all of them. The direction is consistent with the ordinary arm, where the two traced measurements are the lower two of the six we have at 88%, though there the drift between campaigns is wide enough that the same conclusion cannot be drawn.

This is the paper's own thesis arriving uninvited. We attached an instrument to measure why an instrument was failing, and the second instrument changed the thing it came to observe — in the arm where the quantity was smallest, which is exactly where the main text says a measurement is most exposed. It costs us nothing here, because no claim rests on the real-time arm's level, and it is worth stating plainly rather than leaving in a footnote: a kernel tracer is not a free observer.

### S13. THE COMMENSURABILITY ACCOUNT'S CORRECTIONS IN FULL (MOVED FROM THE MAIN TEXT)

*We report the correction because the first version was weaker and we published it to ourselves.* Treating  $100/q$  as a point prediction made the even denominators look like failures, and we introduced an exclusion for them — an arm cannot test a grid the continuous value sits on, so  $q = 2$  and  $q = 4$  were set aside. That exclusion was defensible and pre-registered: it was derived from the  $q = 4$  result and committed at 14:09Z on 2026-07-27, and the first cell of the first odd- $q$  arm was measured at 15:06Z, so the odd denominators were run *because* the rule said they would separate. It was also unnecessary. Under the main text an on-grid arm is a prediction of a flat arm, so  $q = 2$  and  $q = 4$  are evidence *for* the account rather than cases to be excused. We had reached for a law that excluded its exceptions when one that explains them was available.

What exposed it was checking whether the exclusion survived re-estimating one of its own inputs. The continuous value is not constant across rate — it runs 51.2% at 333 msg/s down to 47.5% at 889, a trend of 4.15 points against a replicate noise of 1.55 — and under a rate-local estimate  $q = 4$  ceased to be degenerate and became a failure. A classification that flips on that choice is not a classification. Measuring position against the cell half-width instead of a fixed noise floor removes the sensitivity: every call in the main text is the same under either estimate.

*A second prediction of ours failed, and no reading of it rescues the number.* We recorded, before running it, that  $q = 5$  would put 2 of 5 phases across a boundary and so retain about 40%. The ten replicates gave a median of 51.04% — inside the incommensurate range and 11.0 points from what we wrote down. The error was again naming one branch of a two-branch prediction: with  $T_{\text{true}}/\tau$  at a half, 2 or 3 phases cross depending on where a run's initial phase falls, so a replicate is predicted at 40% or 60% and the average of many is near 50. The values — 40.71, 41.07, 41.96, 42.11, 46.58, 55.50, 57.02, 58.60, 59.05 and 60.04 — are bimodal about exactly those two branches, five on each, which is what the account requires and what no continuous account produces. The miss grew when the arm did: at five replicates the median stood 6.6 points from the registered value and at 10 it stands 11.0, because the upper branch was under-sampled in the smaller set. The grid held; the point we picked on it did not.

*Where the account is approximate, stated rather than trimmed.* Two observations sit outside it, and a third did until the arm was filled. One replicate at 500 msg/s sits at 18.0, which a run confined to a single phase cannot produce. We read this as the limit of the idealization: a nominal rate is  $q = 1$  only if the pacing is exact for the whole run, and over three minutes a drift of a few parts per million walks the phase across a boundary part-way through. The grid that governs retention is the one the pacing realizes, not the one the nominal rate implies. Second,  $q = 2$ 's spread of 17.61 rests on a single replicate at 68.03; the other four span 3.10 points, which is the incommensurate noise level and exactly what an on-grid arm should show. We report the spread over all five rather than the four that agree.

The one that resolved is worth recording, because it is an argument for one of our own rules. The  $q = 1$  arm at 250 msg/s was listed here as a departure from the account when it had three replicates and spread little more than half its cell. At five it spreads 98.73 of 100, which is the full cell width the model predicts, and the anomaly is gone. It was never a departure; it

TABLE VI

EVERY CONFIGURATION THAT CAN MOVE A LATENCY NUMBER, AND WHY IT HOLDS THAT VALUE. SETTINGS MARKED *learned* WERE DISCOVERED BY A DEFECT THEY CAUSED, NOT CHOSEN IN ADVANCE.

| Setting               | Value    | Why                                                                                                                                                                                     |
|-----------------------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <i>Kafka producer</i> |          |                                                                                                                                                                                         |
| acks                  | all      | Durability semantics matched to Redis’s synchronous XADD; weaker acknowledgment would compare different guarantees.                                                                     |
| linger.ms             | 0        | No artificial batching delay; the workload is sparse, so any linger would dominate the quantity measured.                                                                               |
| max-inflight          | 64       | <i>Learned.</i> At the default 1 the client blocks on a round trip per event, making the comparison one of harnesses rather than brokers (the main text).                               |
| compression           | none     | Football events are small JSON; compression would add CPU to the path being timed for no representative benefit.                                                                        |
| ack-stamp             | callback | Default, and deliberately asymmetric with Redis; the main text measures what the asymmetry costs by also running <i>inline</i> .                                                        |
| <i>Redis producer</i> |          |                                                                                                                                                                                         |
| send workers          | pool     | Non-blocking dispatch so the emission loop keeps schedule; send and acknowledgment are stamped in the worker, preserving a valid transport span.                                        |
| <i>Consumers</i>      |          |                                                                                                                                                                                         |
| Redis ack-batch       | 200      | <i>Learned.</i> Acknowledging per message adds one network round trip per message, which at 20 ms of delay is the difference between 103 ms and 4,138 ms (the main text).               |
| Redis count           | 200      | Read batch; matched to the acknowledgment batch so neither dominates.                                                                                                                   |
| Kafka poll-timeout    | 1000 ms  | Client already amortizes fetches; no per-record round trip exists to remove.                                                                                                            |
| <i>Replay</i>         |          |                                                                                                                                                                                         |
| speed-up              | derived  | <i>Learned.</i> Plans carry a baked-in 120× compression, so the flag is not the rate; it is derived from the plan and verified against wall time before every campaign (the main text). |
| window                | 60–600 s | Swept deliberately: the number of events a run contains is itself a variable, and the main text is the reason.                                                                          |

was an arm reported before it had enough replicates to show what it was doing — which is exactly what Section VI-B asks benchmark authors to count before they quote.

#### S15. CONFIGURATION IN FULL (MOVED FROM THE MAIN TEXT)

Table VI states every setting that can move a latency number, with the reason it holds its value.

Mohammad [5] finds that published Kafka comparisons are frequently not comparable because client configuration and acknowledgment semantics differ silently between the systems being compared. We therefore state every setting that can move a latency number, with the reason it holds the value it does (Table VI). Two of these were not chosen but *learned*: the pipelining setting and the acknowledgment-batching setting each cost us a result before we understood them, and both are the subject of the main text.

The general principle is that the two clients must be equalized on *semantics*, not on parameter names. Kafka and Redis expose different knobs, and matching them syntactically is what produces the asymmetries this paper is about. Concretely, Kafka’s producer buffers and pipelines by default while our Redis producer dispatches to a worker pool; leaving *max-inflight* at 1 makes the Kafka client wait for a broker round trip per event while the Redis client does not, which is not a broker difference but a harness difference.

#### S16. INSTRUMENTATION OF THE EXTERNAL BENCHMARK IN FULL (MOVED FROM THE MAIN TEXT)

*Two silent losses that were bugs (moved from the main text).*: The positivity guard is not the first time this harness has discarded latency data with nothing in its output to show it. A serialization defect found in 2023 truncated the histogram on long runs and lost most of the samples [6]; a second defect — distinct, though the two interact in the repair’s own account — reset each client’s histogram on read during a retry, and was found only during “a statistical analysis on some results that looked strange” [7]. Both were repaired. They are recorded here because they establish the contrast the main text draws: those were bugs, and the guard is not one — it was added deliberately, for a stated and locally sound reason, and it is still there.

The second failure mode is measured in the OpenMessaging Benchmark rather than in our harness, so the instrument is a patch to somebody else’s code and its design needs stating.

*What the patch does, and what it deliberately does not.:* At the named commit, a sample is admitted to the histogram only by `if (endToEndLatencyMicros > 0)`. We add counters in the existing `else` branch and change nothing else: not the latency computation, not the guard’s condition, not any reported statistic. The benchmark’s own output is therefore exactly what it would have been unpatched, which is the property that lets us set its published summary beside the retention behind it. The diff is in the artifact.

*The counters must distinguish sign, and an earlier version did not.:* Both a causality violation and a sub-millisecond delivery fail a  $> 0$  test. A single unsigned total cannot tell them apart, and we initially reported one, drawing a conclusion the sign-separated data later refuted (the main text). The counters are now four — zero, negative, most-negative, kept — and the distinction between them carries the finding.

*Counts must be exact, which required two corrections.:* The counters are declared `static`: an embedded run constructs several `WorkerStats` instances, and per-instance counters silently split the totals between them. Totals are printed once by a JVM shutdown hook rather than read from periodic progress lines, because those fire every 10,000 discards and reading the last one quantizes the answer to a multiple of 10,000 — three runs with genuinely different totals all reported 50,000 that way. Every cell records which source its counts came from, and cells whose counts are quantized are excluded from every analysis by rule rather than by inspection.

*A validity gate that refuses to report a number.:* A benchmark that fails to run discards nothing, and a zero from such a run looks exactly like a measured zero. Our first distributed attempt wrote `discarded=0` after the worker died on a classpath fault, and that vacuous zero reached a draft of this paper as a genuine negative result. The campaign now validates before writing: the run must have produced publish-rate output and no failure lines, and if it did not, the row is written `valid=0` with the reason and no count. The gate has since refused eight distributed attempts (the main text), and its refusals are in the artifact alongside its acceptances.

*Denominators.:* OMB warms up for one minute by default, resets its histograms at that boundary, and reports percentiles over the test phase alone; our counters are never reset and would otherwise span both. We make the setting explicit and report a matched sweep with warmup disabled. It changes the sample count per cell from  $\approx 120,000$  to  $\approx 90,000$  and leaves the retention fraction unchanged, so the figures computed with warmup included stand.

*Campaign design.:* Retention at a fixed configuration proved not to have a stable central value (the main text), which dictates the design: every claim is made over whole distributions of replicates rather than over a summary of them, and the axes are swept one at a time with everything else held fixed — background load, message size, producer rate, and the warmup setting — because the variable that turned out to matter was one we did not initially think to hold fixed.

*Every run is indexed, including the failures.:* Each cell is one row in a ledger built by reading the cell’s own log rather than a receipt written afterwards, recording configuration, counts, whether the counts are exact, and the size and SHA-256 of the log they came from. This is not bookkeeping for its own sake: it recovered a valid cell whose script died between finishing the benchmark and writing its result row — a cell that is the median of its load level — and it exposed a fabricated negative sample that our own indexer had produced by mapping an older result schema positionally. A campaign that silently drops its failures is a selection of the runs that worked, which is the failure this paper is about, one level up.

*The full record, stated once.:* The external campaign totals 223 instrumented runs in twelve named sub-campaigns: four load sweeps, a resolution sweep, a payload sweep at an incommensurate rate, a bimodality series ( $n=18$  at one configuration), two rate-phase sweeps, the rate-independence control, a 63-cell comprehensive campaign (arms to  $n \geq 5$ , three new denominators, a payload $\times$ grid manipulation, a duration sweep, and a two-rate probe of the continuous value), and a distributed-mode series that never completed a run and is reported as exactly that. Six predictions for the comprehensive campaign were registered with falsifiers before it launched, and each interim reading was committed to the version-controlled record before the block that followed; three registered predictions failed and are reported beside the one that passed. From 22:02 UTC on the final night a once-per-minute log of the driver’s clock discipline (residual frequency, skew, offset) runs alongside every cell, so each run joins to the clock state during it.

*Verification of the manuscript itself.:* Every quantity this paper states from the campaign is recomputed from the committed ledger by an automated suite (2,000-plus checks, branch coverage of the analysis code at or above 95%), including every row of Tables the main text—the main text and every checkable sentence of the main text; run counts and discard totals are generated into the text from the ledger rather than typed, after an earlier draft was found quoting a count stale in nine places at once. The rendered PDF is checked separately from the source, which has caught defects the compiler passes. The suite is mutation-tested: corrupting a table value, or a value and its derived classification together, fails a check.

*Moved from the main text (internal review, round 1).:* A validity gate refuses to report a number from a run that did not demonstrably produce output — a benchmark that fails to run discards nothing, its zero looking exactly like a measured zero; the gate has refused eight distributed attempts, refusals archived beside its acceptances. Warmup is disabled and reported with a matched sweep (retention unchanged; samples  $\approx 120,000 \rightarrow \approx 90,000$ ), axes are swept one at a time, and every run, failures included, is one ledger row recording configuration, sign-separated counts, and the log’s size and SHA-256. Two counting defects we found and fixed, and what the ledger’s indexing exposed, are supplementary material S16.



## S17. THE TRANSFER PROCEDURE WITH ITS INCIDENTS (MOVED FROM THE MAIN TEXT)

The check is worth reporting only if it transfers, so we state it as a procedure rather than as a description of what we happened to do. It applies to any latency computed as a difference of timestamps taken in different processes, threads or hosts — which covers most end-to-end measurements in this literature.

- 1) **Identify every span whose endpoints are stamped by different execution contexts.** In our pipeline exactly one of the three components qualifies: scheduling lag and the output interval are stamped within a single process, broker transport is not. Spans stamped within one context cannot violate causality and need no check.
- 2) **Record the raw per-event values, not summaries.** The failure is invisible in aggregate — that is its defining property — so a pipeline that writes only percentiles has already discarded the evidence. This is the one requirement that may demand a change to an existing harness.
- 3) **Count the fraction of events in which the span is negative, per run and per component.**
- 4) **Reject by a stated rule, before looking at results.** We reject a run when any component exceeds 1% inverted or has a negative median. The threshold is a judgment and should be reported with its sensitivity (the main text); what matters more is that it is fixed in advance and applied to every condition, including those whose results look reasonable. Applying it only to suspicious results reproduces the error it exists to prevent.
- 5) **Report the retention rate alongside the results,** the way a survey reports its response rate. A benchmark that discards nothing has either an unusually clean instrument or an unexamined one, and a reader cannot tell which without the number. Count *both* causes separately: a sample rejected for being negative is an instrument failure, and a sample rejected for computing to zero is a resolution failure. A single unsigned total cannot distinguish them, and we drew a wrong conclusion from one that could not (the main text).
- 6) **Compare the timestamp's resolution against the latency you expect to measure, and publish both.** This is the ratio that governs the second failure mode, and neither number alone conveys it. A millisecond-grained clock on a path the experimenter believes is sub-millisecond is a stated problem, not a latent one.
- 7) **Read your own reported percentiles for quantization. This costs nothing and needs no patch.** If every percentile a benchmark prints is a whole multiple of its clock's quantum, the measurement has no resolution below that quantum and the distribution is an artifact of the grid. In the benchmark we audited, all 32 percentile values across eight runs were whole milliseconds, and three runs reported  $p_{50} = p_{95} = p_{99} = \max = 1.0$  — a distribution with one value in it, printed to three decimal places, in output anybody could have read. We found it only after instrumenting the source, which was unnecessary.
- 8) **Put your send interval over the timestamp quantum, reduce the fraction, and look at the denominator.** A fixed interval that visits few phases within the quantum puts nearly every sample in a run at one of them, which makes the surviving fraction bimodal and irreproducible rather than merely small (in the main text). The diagnostic is arithmetic on two numbers you already know, but it is the reduced denominator  $q$  that matters, not whether the interval looks round: 500 msg/s gives  $q = 1$  and spread 99.52 points, and 300 msg/s gives  $q = 3$  and spread 31.23, while 889 msg/s — which sits 0.00014 away from  $9/8$  — gives a denominator in the hundreds and is stable to 1.7. A small  $q$  is the hazard; proximity to a simple fraction is not. The remedy is to dither the send instant, which works without having to get the arithmetic right.
- 9) **Report events-per-run alongside every latency percentile.** This is the check that would have caught our second withdrawal (the main text) and the sign check would not: a median over seven events is a statement about the harness, not the system, and it looks its most convincing when the artifact is deterministic enough to repeat across a hundred runs. Any percentile computed over single-digit samples should be labeled as such.
- 10) **Record the achieved rate, per run, next to the results — not the flag that was meant to produce it.** A replay harness has a nominal rate and an achieved one, and they part company silently. Ours parted company by a factor of 120 because the plans carried a compression the flag did not know about (the main text). Derive the setting from the workload rather than assuming it, verify the achieved rate against elapsed wall time before the campaign rather than after, and write the verified figure into an artifact that outlives the raw data. We had to reconstruct the rate of our own earliest corpus by arithmetic on its results, which happened to be possible and will not always be.
- 11) **Before attributing an offset to every event, vary the run length and count.** Lengthen the observation window by a known factor and count how many events exceed the offset, rather than re-computing the average. A per-run cost holds that count fixed while the run grows; a per-event one grows it in proportion. The two are indistinguishable in any percentile, which is why we report the count. In our sweep the count stayed at four while events per run grew several times over (supplementary material S7).
- 12) **Where retention differs between arms, bound the selection it introduces.** Unequal rejection is itself a bias, and the main text gives the worst-case imputation we use.

The cost is one pass over data the harness already produces. In our implementation the rule is under two hundred lines and runs in seconds over 2,266 runs, which is why we argue it belongs in routine practice rather than in a dedicated study.

*When it matters most.*: Equation 6 of the main text tells a reader where to be careful without repeating our experiments: risk rises as the measured quantity approaches the instrument’s own scheduling jitter, and as utilization approaches saturation. A benchmark measuring milliseconds on a loaded machine is in the dangerous region; one measuring seconds, or running well below saturation, is not. That is a rule of thumb, and the main text says what would be needed to make it quantitative.

*Moved from the main text (internal review, round 1).*: The check transfers to any latency computed across execution contexts — most end-to-end measurements in this literature. The load-bearing rules: (1) identify every span whose endpoints are stamped by different execution contexts, and check those; (4) reject by a rule stated before looking at results, and report its sensitivity; (5) report the retention rate beside the results, counting rejection causes separately (negative = instrument failure; computes-to-zero = resolution failure); (8) put the send interval over the timestamp quantum, reduce the fraction, and read the denominator — small  $q$  is the hazard, dithering removes it; (10) record the achieved rate, per run, verified against elapsed wall time, next to the results — not the flag meant to produce it; (12) where retention differs between arms, bound the selection. Rules (2), (3), (6), (7), (9) and (11) are stated, each with the incident that taught it, in supplementary material S17. The cost is one pass over data the harness already produces; our implementation is under two hundred lines and runs in seconds over 2,266 runs, which is why we argue it belongs in routine practice rather than in a dedicated study.

#### S18. RELATED WORK IN FULL: VARIABILITY LITERATURE AND THE RESULT-BY-RESULT MAP (MOVED FROM THE MAIN TEXT)

*Run-to-run instability has a supporting literature, and it is on our side.*: The irreproducibility we measure — three-replicate medians reproducing at one load level in five, and the distribution *family* itself moving between passes of an identical configuration (the main text) — sits in a line of work showing that benchmark variability is structural, not noise. Mytkowicz et al. [8] showed that factors as innocuous as link order and environment-variable size flip published conclusions; Georges et al. [9] that JVM results without confidence intervals routinely mislead; Barrett et al. [10] that virtual machines frequently never reach the steady state their benchmarks assume, so the distribution being sampled is itself non-stationary — the closest published analogue of our regime mobility. Maricq et al. [11] found hundreds of trials necessary for stable comparisons on real hardware, and Kalibera and Jones [12] supply the replication framework. Against this stands common practice rather than any contrary finding: the surveyed norm of a handful of repetitions [13], [14] presumes a stable distribution that our phase-locked configurations demonstrably lack. We add the mechanism: at these configurations the instability is not variance around a value but a two-point support whose weights move, so no replicate count converges (the main text).

*Result by result.*: For each headline result, the nearest support and the nearest constraint we can find:

- *Deletion law and grid structure* (in the main text). Supported mathematically by equidistribution and dither theory [15], [16], [17], and practiced in profiling since randomized sampling clocks were introduced to break exactly this kind of synchronization [18]; no empirical study reports a benchmark’s retained fraction, so the nearest contradiction is implicit — every published OMB-derived latency figure [19] assumes retention near 100%, an assumption our 0.36%–100% range refutes for sub-tick paths.
- *Summary insensitivity* (the main text). Supported in spirit by Ousterhout’s injunction to measure beneath the summary [20] and by reporting standards that require sample counts [14]; contradicted by no study, but silently contradicted by every report of a latency percentile without the count behind it.
- *Irreproducibility and regime mobility* (the main text, the main text). Supported by [8], [9], [10], [11]; constrained by the same literature’s remedy — more replicates — which our two-point supports show cannot converge here.
- *Scheduling-stall negative spans* (in the main text). Supported by the tail-latency and scheduler literature [21], [22], [23] and by the concurrent negative-span reports [24]; qualified by Sharma et al.’s skew-threshold reading, which our zero-skew negative spans show is unsafe under load.
- *The sign audit* (the main text). Ten million discarded samples, not one negative. Nothing in the literature contradicts a count; what it refuted was our own prior claim, which is the point of publishing it.

Li et al. [21] decompose the tail latency of three Linux servers into hardware, operating-system and application-level sources, and report the finding that matters most for us: measured tails are *substantially worse* than a queueing model alone predicts, with the excess traced to interference from background processes, request re-ordering under constrained concurrency, interrupt routing, power management and NUMA effects. A single-parameter queueing description is therefore a leading-order account, not a complete one — which is precisely what the main text measures directly on the instrument rather than on the system under test. Their background-interference mechanism also predicts the temporal signature we observe: a core blocked by another task delays not one event but every event arriving in that interval, so the resulting failures should appear in consecutive bursts. The main text tests that prediction and finds exactly this clustering.

Our contribution here is therefore not the observation that scheduling delay is heavy-tailed, which is established, but that this shape propagates into the *measurement* of an unrelated quantity, and that load moves the tail’s weight far faster than the core’s width (the main text). The practical consequence is specific: a benchmark can sit at a utilization where its measurements look tight — the core is narrow — while the tail that actually corrupts them is already growing.

TABLE VII

WHY THE DELAY SWEEP IS NOT AN EFFECT-SIZE MANIPULATION. INJECTED ONE-WAY DELAY AT THE BROKER, VERIFIED PRESENT AT THE INTERFACE, AT A VERIFIED TRUE REAL-TIME RATE. TTI TRACKS THE INJECTION; BROKER TRANSPORT DOES NOT MOVE, BECAUSE THE SAME DELAY IS ADDED TO BOTH ARRIVALS WHOSE DIFFERENCE DEFINES IT.

| Injected delay | TTI median | Transport median | Transport IQR |
|----------------|------------|------------------|---------------|
| 0 ms           | 3.72 ms    | 0.535 ms         | 0.162 ms      |
| 1 ms           | 4.67 ms    | 0.508 ms         | 0.166 ms      |
| 5 ms           | 8.66 ms    | 0.494 ms         | 0.159 ms      |
| 20 ms          | 23.61 ms   | 0.480 ms         | 0.150 ms      |

*Moved from the main text (internal review, round 1).*: That presumption is not ours: Lozi et al. [23] document Linux scheduler bugs under which cores stay idle *for seconds* while runnable threads queue elsewhere, invisible to conventional testing because throughput stays healthy. Under exact work conservation a stamping thread would never wait while a core was free, and the geometry contrast of the table in supplementary material S25 would have to be flat; it is not, and it converges only where no core is free to migrate to.

Li et al. [21] decompose Linux tail latency into hardware, OS and application sources, report measured tails *substantially worse* than a queueing model alone predicts — precisely the excess our instrument measures — and their background-interference mechanism predicts the temporal signature we observe, consecutive corrupted events, tested and found in the main text (full engagement: supplementary material S18).

#### S19. PROVENANCE-GAP EPISODE AND THE CO-LOCATION WITHHOLDING (MOVED FROM THE MAIN TEXT)

##### S19.1. A gap in our own provenance

Auditing the corpus turned the same scrutiny on our own record-keeping, and it did not survive it either: no surviving artifact records the achieved replay rate of the earliest corpus. Replay plans carry a baked-in  $120\times$  compression that the producer’s flag then multiplies, so the candidate rates are  $1\times$ ,  $120\times$  and  $1200\times$ , and the records that exist disagree. The rate was recovered from a physical constraint: the client’s start-up cost is a wall-clock constant, so the number of events it swallows encodes the rate, and one diagnostic cell whose median reads 52.34 ms (range 51.60–53.01 across fifteen runs) — midway between the two modes at 1.6 and 103.5 ms — fixes it at four late events and hence at true real time. What the gap touches is bounded: the audit is unaffected, since causal impossibility holds at any rate; the withdrawal of the main text is stated in a form that holds at every candidate rate; and the main text’s external validity is restored by the recovery. The full episode — recovery arithmetic, per-claim exposure, the disagreeing records — is supplementary material S1. The rule it produced — write the number down — is in the main text.

*A manipulation that did not manipulate, and what it cost.*: We also withhold a co-location campaign (E-A8). The intent was to shorten  $T_{\text{true}}$  by removing the network hop — the opposite of the payload sweep, and a useful check that the  $T_{\text{true}}$  result is not an artifact of how we lengthened it. It did not work. Moving the broker onto the driver made transport *longer* at idle,  $0.512 \rightarrow 0.573$  ms, because it traded network latency for CPU contention on the same cores; under 88% load it moved transport by  $1.03\times$ , which is no manipulation at all. The negative-span rates duly failed to separate (intervals overlapping in both cells). Reporting those rates as a null would misdescribe the experiment: nothing was manipulated, so nothing was tested. We record it because the pattern is itself informative. Two of our three attempts on this axis failed for structurally similar reasons — netem delayed both paths and canceled in the difference, co-location traded one delay for another — which suggests  $T_{\text{true}}$  is a quantity that resists manipulation in a shared-resource system, because every route to shortening it lengthens something else. The payload sweep worked because padding adds serialization without contending for the scheduler, and we were fortunate that it does.

#### S20. THE DELAY-SWEEP WITHDRAWAL IN FULL (MOVED FROM THE MAIN TEXT)

*We withdraw the intermediate points, and the reason is worth more than they were.* An earlier version supported H1 additionally with a netem delay sweep, reporting a rank correlation across injected delays of 0 to 50 ms. We then re-ran that sweep at a verified real-time rate with a manipulation check, and the check failed — not because the treatment was too weak, but because it does not act on the quantity at all. Injecting delay at the broker moves end-to-end TTI almost exactly as commanded ( $3.72 \rightarrow 23.61$  ms across  $0 \rightarrow 20$  ms) while broker transport stays flat ( $0.535 \rightarrow 0.482$  ms; Table VII).

The cause is that the delay is **common-mode**. It delays the acknowledgment travelling broker-to-producer and the record travelling broker-to-consumer by the same amount, and transport is the *difference* of stamps taken at those two arrivals, so the injected delay cancels exactly. A manipulation can be applied correctly, verified present at the interface, and still not touch the quantity under study — which is the same lesson as the rest of this paper, arriving this time in our own experimental design rather than in our instrument. The original sweep’s correlation was therefore never an effect-size relationship, and we report the sweep only as the negative result it is.

| Campaign                         | Manipulated                            | Held fixed                  | What it settles                                                     |
|----------------------------------|----------------------------------------|-----------------------------|---------------------------------------------------------------------|
| E1<br>concurrency                | feeds $N$ :<br>1, 9, 10, 12            | rate, host,<br>plan set     | the original question:<br>does broker choice matter?                |
| E-B<br>delay sweep               | injected delay<br>0-50 ms              | load, feeds                 | H1 effect size<br>(direction only; confounded)                      |
| E-A / E-A3<br>load sweep         | background load<br>0-12                | rate, feeds,<br>plan        | H2 utilization, H10 mixture,<br>$F_{\Delta}$ recovery               |
| E-A2<br>process count            | processes at<br>fixed rate             | aggregate<br>event rate     | H4 oversubscription                                                 |
| E-C3 / E-C4<br>stamping          | ack stamp:<br>callback vs inline       | load, in-flight,<br>backend | H3 asymmetry<br>(replicated)                                        |
| window<br>sweep                  | observation window<br>60-600 s         | rate, host,<br>match        | start-up cost vs<br>per-event constant                              |
| transport<br>(x2)                | feeds, powered                         | verified<br>real-time rate  | broker transport,<br>equivalence + shift                            |
| E-A5/A5b/A7<br>stamping priority | SCHED_FIFO on<br>the stamping threads  | utilization,<br>to 0.003    | scheduling, not utilization<br>(8 pairs, 7-80x)                     |
| E-A6 / E-A6b<br>load geometry    | cores free vs<br>all duty-cycled       | achieved<br>utilization     | utilization is not the variable<br>(2.07x, 2.05x, at $\rho$ 0.7531) |
| E-A9<br>run-queue trace          | nothing:<br>observation only           | load,<br>priority arm       | $P(\text{stall} > T_{\text{true}})$ predicts<br>the rate, unfitted  |
| E-A10<br>transport sweep         | payload size;<br>$T_{\text{true}}$ 77x | load, hosts,<br>code path   | other side of the inequality;<br>tail index 0.34                    |
| E-A8<br>co-location              | broker on<br>the driver                | utilization,<br>to 0.003    | nothing: transport did not<br>move, so it is withheld               |
| OMB<br>external                  | instrumented<br>discard counter        | our broker,<br>under load   | the exposure is<br>not ours alone                                   |

*Every claim in the discussion traces to one row. No row both generates and tests the same hypothesis, and a row that settled nothing says so.*

Fig. 4. The experiment map. Each campaign manipulates one variable, holds the others fixed, and settles one claim. The delay sweep is marked confounded because injecting delay also inflates variance (the main text), so we use it for direction only.

## S21. THE EXPERIMENT MAP, THE CLAIM-EVIDENCE TABLE, AND THE AUDIT THRESHOLD FIGURE (MOVED FROM THE MAIN TEXT)

Figure 4 is the experiment map; Table VIII is the claim-evidence table; Figure 5 shows the threshold's consequences.

## S22. THREATS AND LIMITATIONS IN FULL (MOVED FROM THE MAIN TEXT)

### Threats to validity (full)

*Construct validity: the check may not measure what we claim.:* A negative span is proof that *something* is wrong, but our attribution of it to scheduler delay in reaching the clock is an inference. Two rival explanations are available. Clock skew is ruled out directly for Testbed A, where both processes read the same operating-system clock; it is not ruled out on Testbed B, where producer and consumer may sit on different hosts, and there we rely on the co-located conditions failing at rates comparable to the distributed ones.

Coarse kernel timestamp granularity would also produce negative spans, and that rival makes a different prediction we can test. Quantization acts on each event independently, so its negative spans would be scattered at random through a run; a descheduling event, by contrast, makes a *consecutive run* of events wake late together. A Wald–Wolfowitz runs test on the

TABLE VIII

WHAT EACH CLAIM RESTS ON. E1 IS THE ONLY CORPUS WHERE RETENTION IS A LIVE CONCERN; THE CAMPAIGNS AFTER IT RETAIN EVERY RUN, SO THE BREAKDOWN-POINT ARGUMENT OF THE MAIN TEXT IS NEEDED FOR ONE ROW ONLY.

| Claim (section)                         | Campaign              | Runs per cell            |
|-----------------------------------------|-----------------------|--------------------------|
| Audit rejection rates (main text)       | all corpora           | 2,266 runs total         |
| H1 effect size (main text)              | co-located vs network | 15 per delay level       |
| H2 utilization shape (main text)        | E-A, E-A3             | 25 per load level        |
| H4 process count (main text)            | E-A2                  | 15 per level             |
| H3 asymmetry (main text)                | E-C3, replicated E-C4 | 10, then 15 per arm      |
| Mixture structure (main text)           | E-A3, nine levels     | 25 per level             |
| Scheduling, not utilization (main text) | E-A5, E-A5b, E-A7     | 25 per arm               |
| Load geometry (main text)               | E-A6, both geometries | 25 per arm               |
| Traced run-queue tail (main text)       | E-A9                  | 25 per arm               |
| $T_{\text{true}}$ sweep (main text)     | E-A10, four payloads  | 25 per level             |
| Broker transport (main text)            | powered, replicated   | 15, then 8 per cell      |
| Start-up withdrawal (main text)         | window sweep, twice   | 3 per window             |
| <i>Historical: E1</i> (main text)       | E1                    | 8–35, 52.8–100% retained |

sequence of span signs separates the two: independence gives  $z \approx 0$ , clustering  $z \ll 0$ . Across conditions the negative spans are strongly clustered — median  $z = -6.9$  at the co-located floor,  $-6.8$  idle,  $-5.1$  saturated — and the clustering is present even with no background load, so it is intrinsic to the stamping path rather than induced by contention. This is the signature of a shared scheduling delay, not of independent quantization, and the main text additionally reports the measured timer granularity on both platforms. We regard the Testbed A attribution as well supported and the Testbed B attribution as probable rather than established.

*Internal validity: the audit selects.:* The check rejects unequally between arms, so the surviving corpus is not a random sample of the measured one. This is the most serious internal threat, and the main text addresses it with a worst-case bound rather than an argument. That bound holds only while retention exceeds one half, and our tightest cell sits 2.8 points above that line; a slightly worse campaign would have left the equivalence claim undefendable.

*Internal validity: the surviving comparison is small.:* After rejection, per-cell samples run from 8 to 35. The  $N=1$  cell cannot support inference and we treat it as descriptive; conclusions rest on the levels with 19 or more runs.

*External validity: one workload, two systems, two platforms.:* We demonstrate the failure on a sparse bursty feed, two brokers and two operating systems. The model of the main text predicts it wherever cross-process spans are measured near the instrument’s own jitter under load, but we have not shown that. Sharma et al. [24] report the same symptom in an unrelated domain, which is suggestive but is not our evidence.

*Construct validity: a percentile is not automatically a property of the system.:* The 103 ms producer offset reproduced across both testbeds, four concurrency levels and 164 runs, and we took that breadth as evidence it was a property of the system. It was a property of the window (the main text). Reproducibility across runs distinguishes a deterministic effect from a noisy one; it does not distinguish a system effect from a harness effect, and we treated it as though it did. Every percentile in this paper is now reported with the events per run behind it.

*Construct validity: the injected-delay sweep is not a clean effect-size manipulation.:* H1’s quantitative slope (the main text) is estimated from a `tc netem` delay sweep, on the assumption that injecting  $d$  ms of delay simply raises  $T_{\text{true}}$  by  $d$ . It does not: on our bursty feed, a per-delivery delay builds a queue, so the measured transport *variance* climbs from 10 ms<sup>2</sup> at zero delay to 9,200 ms<sup>2</sup> at 50 ms — a clean offset would leave it unchanged. The delay sweep therefore confounds  $T_{\text{true}}$  with backlog-driven jitter, and we do not lean on its fitted slope. H1’s robust evidence is the comparison it does not confound: the co-located arm, where  $T_{\text{true}} \approx 0.5$  ms, fails wholesale, while the network arm, where  $T_{\text{true}}$  is tens of seconds, passes 15/15 on the same hardware (the main text). Testing the fine-grained slope cleanly needs an instrument that lengthens  $T_{\text{true}}$  without perturbing the scheduler, which `netem` is not. The payload sweep of the main text is that instrument by another route: padding adds serialization and transfer time without contending for the run queue, and it moves  $T_{\text{true}}$  by  $77\times$  against `netem`’s confounded range. It is not a perfect constant offset either — serialization pushes utilization slightly *up*, which works against the observed direction rather than for it — but it is clean enough to carry the claim `netem` could not, which is why the  $T_{\text{true}}$  result rests on it and not on this sweep.

*The mechanism is established; the quantity is not predicted.:* The clearest limit on this work is what it still cannot do. We can say what causes a negative span, manipulate it on both sides, and predict the rate to within a third in the three arms where we traced the scheduler directly. We cannot write down the rate a benchmark will suffer at a given load on a given machine. Two attempts failed and are reported above: the queueing form fits worse than the mean once the sweep reaches the range where forms diverge, and our own registered bracket missed a  $1.44\times$  growth by predicting  $2.45\text{--}3.07\times$ . Both failed for the same reason — both were parameterized in  $\rho$ , and  $\rho$  is not the variable. The flight factor  $G(T_{\text{true}})$  of Equation 6 is the nearest thing we have to a quantitative law, and it carries no load term at all: it predicts how the rate scales with  $T_{\text{true}}$ , not




Fig. 5. The audit on Testbed A. (a) Per-run negative-span rates: 104 runs are clean and the rest spread over three decades, so there is no natural threshold. (b) Share of runs rejected against the threshold. The choice matters for the run count and not for any conclusion.

what the rate is. So the practical guidance this paper supports is a check to run, not a number to look up. A reader wanting to know whether their own measurement is exposed must measure it, which is precisely why we argue the check should be routine rather than the model be trusted.

*Conclusion validity: multiplicity and pre-specification.*: Holm families are declared over the design actually executed rather than chosen afterwards, and equivalence margins were fixed before testing. The threshold in the check was fixed before the final campaign but *after* earlier campaigns had run, which is weaker than pre-registration; the sensitivity analysis of the main text exists partly to compensate.

#### Limitations (full)

*The surviving evidence is narrower than the design.* The audit removed the throughput sweep, the connection sweep above ten, the cluster arm, the durability quantification and all of Testbed A. We cannot characterize behavior at the concurrency a multi-tenant platform would see.

*EI's replay rate is inferred, not documented.* The main text recovers it from the data and the recovery is, we think, correct, but it is an inference from a 52.34 ms median in one cell rather than a setting anyone recorded. A reader who does not accept the inference should read the main text as establishing that both arms met the same rate, which is all the between-system comparison needs.

*The E1 reconciliation is an explanation, not a re-run of E1.* Supplementary material S5 shows that restricting the powered runs to their opening seven events reproduces E1’s figures in both shift and absolute level, which is why we no longer treat the two campaigns as contradictory. But it demonstrates that the window is *sufficient* to produce the disagreement, not that it is the only difference between the campaigns: E1 ran on a corpus whose replay rate we infer rather than read, and we cannot rule out that some other difference contributes as well. What we can say is that no additional cause needs to be invoked.

*The mechanism is established for our client, not for Kafka in general.* The blocking first `produce()` is visible in the loop trace of every run (the main text), so for this client the attribution is direct rather than inferred. Whether a different client, or a pre-created topic, or a broker configured against auto-creation would pay the same cost, we did not test. The practitioner advice in the main text is written to be safe either way.

*The occupancy result is a mechanism, not a load model.* The main text shows by manipulation that the negative-span rate follows stamping-thread occupancy rather than utilization, and that is the strongest causal claim in this paper. It is not a formula. We can say the rate falls fifty-fold when the stamping thread stops being preempted; we cannot say what the rate will be at a given load, and both attempts to write one — the queueing form and our own bounded bracket — failed against the sweep. A practitioner should read this as “keep the stamping thread runnable and measure what you get”, not as a curve to substitute into a budget.

*The external evidence is single-host, and the cross-host case is unmeasured.* The 223-run campaign of the main text ran in embedded mode, so both stamps came from one JVM on one host. That is sufficient for the resolution failure, which needs no second clock — the quantum is a property of the timestamp, not of the network — but it means the cross-host channel is established by source audit and not by observation. We attempted a distributed run eight times, at three background-load levels including none at all, and the benchmark’s own coordinator-to-worker protocol failed on every one; the load-starvation hypothesis we formed after the first failures is refuted by the unloaded attempts failing identically. That difficulty is worth recording rather than hiding, and it cuts both ways: a failure mode this hard to instrument is one a practitioner is unlikely to find by accident, and a distributed mode that does not complete a run in repeated attempts by readers of its source is itself a fact about the state of the tooling.

We are also explicit that the clock bound on this testbed does *not* rule the channel out. `chrony` reports inter-host offsets near 0.1 ms, which is comfortably sub-tick — but the bound it places on its own error, root dispersion plus half the root delay, is 4 to 7 ms per host across the 4 hosts captured, and the two worst of those bounds sum to 12 ms against a 1 ms timestamp. An operator checking whether cross-host subtraction is safe reads the offset line and concludes it cannot happen; the figure that bounds the disagreement is two orders of magnitude larger and three lines further down the same output. The channel is therefore open on this testbed, and we could not measure it.

*H3 is measured at one operating point.* The symmetric-stamping comparison (the main text) was run at one in-flight request and one load level, because inline stamping requires the single in-flight setting. The direction and the one-sidedness of the effect are what the model predicts, but we do not characterize how the 0.07 ms offset scales with load or pipelining.

*The five-feed acknowledgment null is unexplained,* as set out in the main text.

*One workload.* The arrival-rate result should generalize to any sparse bursty feed, but we demonstrate it on one.

## S23. TABLES (MOVED FROM THE MAIN TEXT; THE PIPELINE SCHEMATIC HAS RETURNED TO IT)

Table IX is the per-arm ledger behind Section IV-B’s grid claim: one row per send rate, with the arithmetic denominator  $q$ , the replicate count, and the spread those replicates actually showed. The main text keeps the inference drawn from it and the set view of the same arms; this is the record they are drawn from, and every cell in it is recomputed from the committed campaign index by the test suite rather than proofread. Table X keeps the individual replicate retentions for three arms, which the ledger reduces to a single spread: it is the same evidence at finer grain, and it is where the 0.47-to-99.99 range behind the  $q = 1$  corner can actually be seen.

Two further tables hold evidence the main text spends a line on each. Table XI sweeps payload at an incommensurate rate, where samples stay dephased and implied latency can be read off directly. Table XII is the load sweep behind the queueing form we withdrew; it is kept because a fit we abandoned should stay inspectable by anyone who wants to disagree with the abandonment. A third answers the question Section VI-A raises about unequal audit loss: Table XIII bounds the selection effect that loss could have introduced into the broker equivalence, by imputing every rejected Redis run at the largest value its own cell allows. Its margin is the one that equivalence is stated against.

## S24. TAIL RECOVERY WITHOUT A REFERENCE CLOCK (MOVED FROM THE MAIN TEXT)

*Recovering the tail without a reference clock, and where it reproduces.:* Because negative-span rate at a threshold is a quantile of  $\Delta$ ’s tail, the tail can be read off negative span counts alone — an instrument-quality estimate needing no reference clock. The honest test of it is not internal consistency but reproduction: do the recovered tail quantiles agree between two independent campaigns at matched utilization? Below saturation they do — 12 of 17 matched quantiles overlap at 90%, and every one of the deep pre-knee quantiles does. The failures are all at  $\rho = 1$ , where the coordinate is degenerate — eight, ten and twelve background workers all read as full utilization while representing different degrees of overload — so the two campaigns

TABLE IX

**REPLICATE SPREAD AGAINST THE PHASE DENOMINATOR  $q$**  (MOVED FROM SECTION IV-B), AT FIXED PAYLOAD, LOAD, DURATION AND HOST.  $Pos.$  IS THE DISTANCE FROM THE MEASURED CONTINUOUS VALUE TO THE NEAREST GRID POINT, AGAINST THE CELL HALF-WIDTH: 0 SITS ON A GRID POINT, 1 MIDWAY BETWEEN TWO. POSITION IS SCALE-FREE, SO EVERY CALL IS UNCHANGED WHETHER THE CONTINUOUS VALUE IS ESTIMATED POOLED OR PER RATE. *Predicts* IS *full* WHERE THE POSITION EXCEEDS A HALF; *shows* IS *full* WHERE THE MEASURED SPREAD EXCEEDS HALF THE CELL WIDTH. BOTH ARE RECOMPUTED FROM THE GEOMETRY AT BUILD TIME, SO THE LAST TWO COLUMNS CAN BE READ AGAINST EACH OTHER: 10 OF THE 12 COMMENSURATE ROWS AGREE, AND THE TWO THAT DO NOT ARE 700 AND 1250 MSG/S, DAGGERED AND SET IN BOLD HERE AND DISCUSSED IN SUPPLEMENTARY MATERIAL S31. BOTH ARE RESOLVED IN THE MODEL'S FAVOR BY THE REPLACEMENT STATISTIC OF TABLE XXV, WHICH DOES NOT USE SPREAD. INCOMMENSURATE ARMS HAVE NO CELL AND THEREFORE NO CLASS: THEIR *predicts* ENTRY IS THE NOISE FLOOR RATHER THAN A PREDICTION, AND THEIR MEASURED SPREADS — ABOUT THREE POINTS — ARE THAT FLOOR, NOT A DISAGREEMENT. ROWS ARE ORDERED BY  $q$ , WHICH IS WHAT DECIDES THE PREDICTION. EVERY INCOMMENSURATE RATIO SHOWN IS ALREADY IN LOWEST TERMS.

| rate                                                     | $\Delta/\tau$ | $q$ | $n$ | width | pos. | predicts    | spread | shows       |
|----------------------------------------------------------|---------------|-----|-----|-------|------|-------------|--------|-------------|
| 1000/s                                                   | 1/1           | 1   | 5   | 100.0 | 0.98 | full        | 99.4   | full        |
| 500/s                                                    | 2/1           | 1   | 5   | 100.0 | 0.98 | full        | 99.5   | full        |
| 250/s                                                    | 4/1           | 1   | 5   | 100.0 | 0.98 | full        | 98.7   | full        |
| 400/s                                                    | 5/2           | 2   | 5   | 50.0  | 0.04 | flat        | 17.6   | flat        |
| 600/s                                                    | 5/3           | 3   | 6   | 33.3  | 0.95 | full        | 32.7   | full        |
| 300/s                                                    | 10/3          | 3   | 10  | 33.3  | 0.95 | full        | 31.2   | full        |
| 800/s                                                    | 5/4           | 4   | 5   | 25.0  | 0.07 | flat        | 7.2    | flat        |
| 1250/s <sup>†</sup>                                      | 4/5           | 5   | 5   | 20.0  | 0.91 | full        | 7.6    | <b>flat</b> |
| 625/s                                                    | 8/5           | 5   | 10  | 20.0  | 0.91 | full        | 19.3   | full        |
| 875/s                                                    | 8/7           | 7   | 5   | 14.3  | 0.87 | full        | 10.7   | full        |
| 700/s <sup>†</sup>                                       | 10/7          | 7   | 5   | 14.3  | 0.87 | full        | 6.5    | <b>flat</b> |
| 900/s                                                    | 10/9          | 9   | 5   | 11.1  | 0.84 | full        | 6.9    | full        |
| <i>incommensurate — phase set effectively continuous</i> |               |     |     |       |      |             |        |             |
| 333/s                                                    | 1000/333      | >64 | 5   | —     | —    | $\approx 0$ | 4.5    | —           |
| 383/s                                                    | 1000/383      | >64 | 5   | —     | —    | $\approx 0$ | 2.8    | —           |
| 457/s                                                    | 1000/457      | >64 | 5   | —     | —    | $\approx 0$ | 2.1    | —           |
| 611/s                                                    | 1000/611      | >64 | 5   | —     | —    | $\approx 0$ | 3.1    | —           |
| 889/s                                                    | 1000/889      | >64 | 5   | —     | —    | $\approx 0$ | 1.7    | —           |
| 1053/s                                                   | 1000/1053     | >64 | 4   | —     | —    | $\approx 0$ | 3.0    | —           |
| 1219/s                                                   | 1000/1219     | >64 | 4   | —     | —    | $\approx 0$ | 4.5    | —           |

TABLE X

RETENTION AGAINST THE PRODUCER'S SEND INTERVAL, WITH MESSAGE SIZE, BACKGROUND LOAD, DURATION AND HOST HELD FIXED. ONLY THE COMMENSURATE RATE IS UNSTABLE, AND THE TWO INCOMMENSURATE RATES AGREE WITH EACH OTHER DESPITE INTERVALS DIFFERING BY 19%. PREDICTIONS WERE RECORDED BEFORE THE RUNS.

| Rate  | Interval | Multiple of tick? | Retention per replicate           | Spread |
|-------|----------|-------------------|-----------------------------------|--------|
| 500/s | 2.000 ms | <b>exact</b>      | 0.47, 1.51, 1.55, 18.02, 99.99    | 99.5   |
| 457/s | 2.188 ms | no                | 48.77, 49.50, 49.69, 50.51, 50.87 | 2.1    |
| 383/s | 2.611 ms | no                | 50.28, 51.09, 51.45, 51.77, 53.13 | 2.8    |

are not in fact at matched load there. The recovered curve reproduces wherever utilization is a meaningful coordinate and stops when it stops being one, which is the correct boundary for the method rather than a defect in it.

#### S25. THE MECHANISM CAMPAIGNS' TABLES (MOVED FROM THE MAIN TEXT)

Table XIV is the mixture across nine load levels; Table XV the occupancy manipulation; Table XVI the load-geometry comparison with its replication; Table XVII the payload sweep; and Table XVIII the kernel-trace comparison, including the withheld arm.

#### S26. THE FIRST RESULT SET (THE MODEL AND FLIP FIGURES WERE PROMOTED TO THE MAIN TEXT IN THE ROUND-1 INTERNAL REVISION)

Table XIX is the first, rejected result set in full.

#### S27. THE GRID TABLE (MOVED TO S23)

The table of replicate spread against the phase denominator  $q$  is Table IX, in supplementary material S23 with the other tables that left the main text.

It was in the main text for one revision, at the request of the reviewer of v2.5, and left again when the page budget tightened. This section held it before that and said so afterwards, which was true for one revision and then was not: the table went to S23 and this section went on pointing at a main text that no longer had it, while S31 went on pointing here. Round 45 followed the chain and found nothing at the end of it.



TABLE XI

RETENTION AGAINST PAYLOAD AT 457 MSG/S, INCOMMENSURATE WITH THE MILLISECOND GRID SO SAMPLES STAY DEPHASED. IMPLIED  $T_{\text{true}}$  INVERTS THE MAIN TEXT. THE FINAL COLUMN IS THE INCREMENT IN IMPLIED LATENCY PER BYTE OF ADDED PAYLOAD, RELATIVE TO THE 200 B BASELINE; THE TWO SMALLEST STEPS ARE NOISE-DOMINATED AND MARKED.

| Payload | Retention (3 reps)  | Median | Implied $T_{\text{true}}$ | $\Delta T/\text{byte}$ |
|---------|---------------------|--------|---------------------------|------------------------|
| 200 B   | 51.08, 52.03, 52.88 | 52.03% | 0.520 ms                  | baseline               |
| 1 KB    | 50.11, 50.32, 51.47 | 50.32% | 0.503 ms                  | $-2.600^\dagger$       |
| 2 KB    | 52.13, 54.62, 54.77 | 54.62% | 0.546 ms                  | $1.752^\dagger$        |
| 4 KB    | 51.86, 54.17, 56.24 | 54.17% | 0.542 ms                  | $0.686^\dagger$        |
| 8 KB    | 54.92, 55.22, 57.89 | 55.22% | 0.552 ms                  | $0.499^\dagger$        |
| 32 KB   | 68.01, 68.44, 69.40 | 68.44% | 0.684 ms                  | <b>0.630</b>           |
| 64 KB   | 84.21, 85.36, 86.82 | 85.36% | 0.854 ms                  | <b>0.638</b>           |

$^\dagger$  added serialization under 0.07 ms, comparable to the 0.02–0.04 ms replicate noise, so the ratio is scatter over a small denominator. The two unmarked levels have a signal-to-noise ratio near 20 and carry the result.

TABLE XII

H2: NEGATIVE-SPAN RATE AGAINST ACHIEVED CPU UTILIZATION, NO CORE PINNING, BACKGROUND LOAD SWEEPED FROM IDLE TO OVERSUBSCRIPTION. THE WITHDRAWN QUEUEING FORM FITS AT  $R^2 = 0.945$  AGAINST 0.640 FOR A STRAIGHT LINE.

| Utilization $\rho$ | Negative span rate |
|--------------------|--------------------|
| 0.003              | 0.007              |
| 0.253              | 0.009              |
| 0.504              | 0.022              |
| 0.628              | 0.047              |
| 0.753              | 0.132              |
| 0.878              | 0.207              |
| 1.000              | 0.208              |
| 1.000              | 0.221              |
| 1.000              | 0.264              |

Following it also found what the broken signpost had been hiding. The table was gated column by column against the campaign index on every run and had never drifted, but the ledger it was drawn from — `phase_quantisation.csv` — was built before `chain17`’s `ultimate` campaign was added to the rate arms and was never rebuilt, and the check that should have caught that was recomputing against a hard-coded copy of the same stale campaign list. Two routes agreed because both were stale in the same way. The table is now generated from the rebuilt ledger, and the campaign list is imported rather than copied, so the second route can no longer inherit the first one’s mistake.

## S28. THE MECHANISM CAMPAIGN PARAGRAPHS IN FULL (MOVED FROM THE MAIN TEXT)

*The experiment that settles it.:* Move one of the two and hold the other fixed: raising the stamping processes to real-time priority makes them preempt the background load rather than queue behind it, so occupancy falls sharply while utilization does not move — and unlike our delay injection, which canceled in the subtraction (the main text), priority acts on the stamping threads themselves, where the model locates the failure. An occupancy mechanism predicts collapse toward the running-state floor; any account in which the rate is a function of  $\rho$  predicts no change, because  $\rho$  is unchanged by construction. The result is unambiguous (Section S25): utilization held to 0.001 (the pre-registered manipulation check passes), and the negative-span rate fell from 0.132 to 0.0034 at  $\rho = 0.75$  and from 0.305 to 0.0057 at  $\rho = 0.88$  — factors of 39 and 54, disjoint Wilson intervals, both residual rates on the floor the model names in advance,  $C_0 \approx 0.004$ .

*Utilization is not the variable, shown at identical utilization.:* Two loads can reach the same  $\rho$  by different means:  $k$  cores flat out leaves  $C - k$  genuinely free, while duty-cycling every core leaves none. If the mechanism is whether the stamping thread can find a core, the second should be worse at equal  $\rho$  — and it is (Section S25): at  $k = 6$  both arms sit at  $\rho = 0.7531$ , identical to four decimals, same machine, same hour, and the negative-span rates differ by  $2.07\times$  ( $z = 10.3$  over 2985 matched events per cell, disjoint Wilson intervals). A function of  $\rho$  returns one value for one input. The gap narrows at  $k = 7$  ( $1.06\times$ ) — the mechanism showing itself: one free core out of eight is nearly as useless as none. *A full replication (E-A6b) corrects us on one point:* it reproduces the load-bearing cell almost exactly ( $\rho = 0.7531$  in all four arms;  $2.05\times$  against  $2.07\times$ ), reproduces  $k = 5$  in direction but not size, and at  $k = 7$  resolves a small difference ( $1.19\times$ ,  $z = 3.46$ ) where the original could not — so we withdraw an earlier draft’s reading of that convergence as a null. Both campaigns agree on the shape: twofold at  $k = 6$ , near-parity at  $k = 7$ .

*The other side of the inequality, and it moves the rate the wrong way.:* The mechanism predicts that a *slower* path is a *more reliable* measurement, because the same stalls have a longer interval to outrun. Padding the payload lengthens  $T_{\text{true}}$  without touching the scheduler (Section S25): transport rose  $76.9\times$  while the negative-span rate *fell*  $4.1\times$ , monotonically, with

TABLE XIII

BOUNDING THE UNEQUAL-RETENTION SELECTION EFFECT. “WORST CASE” IMPUTES EVERY REJECTED REDIS RUN AT THE LARGEST VALUE OBSERVED IN THAT CELL. MARGIN 1 MS.

| $N$ | Redis retained | Shift (ms) | Worst case | Equivalent |
|-----|----------------|------------|------------|------------|
| 1   | 8/8            | +0.081     | +0.081     | yes        |
| 9   | 20/27          | +0.021     | −0.051     | yes        |
| 10  | 17/30          | +0.116     | −0.485     | yes        |
| 12  | 19/36          | +0.053     | −0.227     | yes        |

TABLE XIV

THE MIXTURE, MEASURED ACROSS NINE LOAD LEVELS (25 RUNS EACH, PRE-REGISTERED). THE CORE WIDTH  $\sigma_{\text{core}} = \text{IQR}/1.349$  GROWS  $5\times$  FROM IDLE TO THE KNEE; THE NEGATIVE-SPAN RATE — THE TAIL — GROWS  $60\times$ . NEGATIVE SPANS ARE TEMPORALLY CLUSTERED AT EVERY LOAD (RUNS-TEST  $z$ ). THE THREE  $\rho = 1$  ROWS ARE DISTINCT OVERSUBSCRIPTION LEVELS THAT THE UTILIZATION COORDINATE CANNOT SEPARATE.

| Utilization $\rho$ | Core $\sigma_{\text{core}}$ (ms) | Negative span rate | Clustering $z$ |
|--------------------|----------------------------------|--------------------|----------------|
| 0.003              | 0.126                            | 0.004              | −6.8           |
| 0.253              | 0.138                            | 0.004              | −6.8           |
| 0.504              | 0.180                            | 0.006              | −6.8           |
| 0.628              | 0.181                            | 0.024              | −6.9           |
| 0.753              | 0.238                            | 0.076              | −5.7           |
| 0.878              | 0.631                            | 0.224              | −4.9           |
| 1.000              | 1.224                            | 0.371              | −4.3           |
| 1.000              | 1.293                            | 0.317              | −4.7           |
| 1.000              | 1.710                            | 0.261              | −4.4           |

utilization held to a 0.012 spread — and pushed slightly *up* by serialization, against the observed fall, so the effect is measured against its own confound. The same numbers constrain the stall distribution sharply: a  $77\times$  larger threshold bought only a  $4.1\times$  lower rate, so the tail barely thins across two orders of magnitude — which is why mean-based counters could not see the effect and the direct trace was necessary.

#### S29. THE AUDIT, STAMPING-MODE AND INJECTED-DELAY TABLES (MOVED FROM THE MAIN TEXT)

Table XX is the consistency audit of every run; Table XXI the two stamping modes; Table XXII the injected one-way delay.

*Moved from the main text (internal review, round 1).*: Magnitudes of this size cannot be a per-event cost; the account we test is a round-trip-bound consumption pattern: our Redis consumer acknowledges each entry with XACK and waits — the idiomatic tutorial pattern — so a read of two hundred entries is followed by two hundred sequential round trips, free at 0.22 ms per trip and hopeless at 20 ms, where service rate falls below arrival rate and delay is set by backlog [25]; Kafka’s consumer serves from a prefetched buffer and commits on a timer, no per-record round trip to expose.

The falsification criterion was stated in advance: if amortizing the acknowledgments does not help, the account is wrong. At one feed under true real-time replay, batching them in groups of two hundred takes median TTI from 4,138 ms to 103 ms — a factor of **40.2**, replicated four times — and read-loop instrumentation corrects the shape: each XREADGROUP returns a full batch (median 106 messages in  $\sim 32$  ms), so the constraint is entirely in the acknowledgment path.

#### S31. THE SPREAD RULE AND THE GRID-MEMBERSHIP INFERENCE IN FULL (MOVED FROM THE MAIN TEXT)

Figure 6 is the confirmation the main text’s Section IV-C reports: the three payload arms against their  $q = 3$  grid, and the spread each one produces against the boundary the rule below puts at half a cell.

*What the replicate spread does, and does not, predict.*: It is tempting to write the prediction as “spread  $\approx 100/q$ ”, and we did; that is wrong in a way that matters, because  $100/q$  is the *cell width* — an upper bound, reached only when  $T_{\text{true}}/\tau$  sits midway between two grid points and replicates realize both. On a grid point, one point takes nearly every run and the spread collapses. One statement covers both:

$$\text{spread} \longrightarrow \begin{cases} 100/q & \text{when } T_{\text{true}}/\tau \text{ sits mid-cell,} \\ 0 & \text{when } T_{\text{true}}/\tau \text{ sits on a grid point.} \end{cases} \quad (1)$$

The measured continuous value is  $T_{\text{true}}/\tau = 0.495$ , a half to within replicate noise. A half lies on every even grid (1/2, 2/4, 4/8) and never on an odd one, so at this operating point the odd denominators are predicted to show their full cell width and the even ones to show almost none. That is a prediction about specific arms before they are run, not a description after.

TABLE XV

**OCCUPANCY, NOT UTILIZATION.** STAMPING PROCESSES AT ORDINARY PRIORITY VERSUS SCHED\_FIFO, WITH THE BACKGROUND LOAD UNCHANGED. UTILIZATION IS MEASURED IN BOTH ARMS, NOT ASSUMED: IT MATCHES TO 0.001, SO THE MANIPULATION MOVED OCCUPANCY ALONE. THE NEGATIVE-SPAN RATE FALLS BY A FACTOR OF 39–54 TO THE RUNNING-STATE FLOOR. UTILIZATION-ONLY MODELS PREDICT NO CHANGE.

| Load | Utilization $\rho$ |           | Negative span rate |           |        |
|------|--------------------|-----------|--------------------|-----------|--------|
|      | ordinary           | real-time | ordinary           | real-time | factor |
| 75%  | 0.7531             | 0.7525    | 0.1320             | 0.0034    | 39×    |
| 88%  | 0.8809             | 0.8812    | 0.3049             | 0.0057    | 54×    |

TABLE XVI

**SAME UTILIZATION, DIFFERENT RATE.** BOTH LOAD GEOMETRIES IN ONE CAMPAIGN. CONCENTRATED LOAD LEAVES  $C - k$  CORES FREE; SPREAD LOAD DUTY-CYCLES ALL OF THEM AND LEAVES NONE. AT  $k = 6$  THE TWO ARMS SIT AT THE SAME  $\rho$  TO FOUR DECIMALS — IN *both* CAMPAIGNS — AND THE RATES DIFFER TWOFOLD IN BOTH. EVERY CELL IS 2 985 MATCHED EVENTS OVER 25 RUNS;  $z$  IS A TWO-PROPORTION TEST BETWEEN THE ARMS OF THAT ROW. THE  $k = 7$  ROW IS WHERE THE TWO CAMPAIGNS DISAGREE: THE ORIGINAL CANNOT SEPARATE THE GEOMETRIES THERE, THE REPLICATION CAN, AND WE WITHDRAW THE STRONGER READING (TEXT).

| $k/C$ | E-A6 (original) |        |       | E-A6b (replication) |        |      | ratios       |
|-------|-----------------|--------|-------|---------------------|--------|------|--------------|
|       | conc.           | spread | $z$   | conc.               | spread | $z$  |              |
| 5/8   | 0.0201          | 0.0379 | 4.09  | 0.0111              | 0.0509 | 8.89 | 1.88×, 4.61× |
| 6/8   | 0.0824          | 0.1709 | 10.27 | 0.0600              | 0.1229 | 8.44 | 2.07×, 2.05× |
| 7/8   | 0.2281          | 0.2415 | 1.22  | 0.1973              | 0.2342 | 3.46 | 1.06×, 1.19× |

Achieved  $\rho$ ,  $k = 6$ : 0.7531 in all four arms.  $k = 5$ : 0.6284/0.6250 and 0.6284/0.6259.  $k = 7$ : 0.8778/0.8809 and 0.8778/0.8822.

*Most arms behave as their position predicts, and the two that do not are the reason this statistic was replaced.*: Table IX states each rate’s cell width, cell position, prediction and measured spread against Equation 1; the test needs no tolerance, since a spread above half the cell width separates full from flat. Of the 12 commensurate arms, 10 match. The predictions are ten full against two flat, so both classes are realized and the agreement is with a prediction that varies, not with a constant. The table’s last two columns are that comparison, one row at a time.

The two that miss are 700 and 1250 msg/s. Both are predicted full and measure flat, and we report them as failures of *this* statistic rather than of the model, for a reason that was stated before either was run and does not depend on how they came out. Spread is a range over replicates of a quantity with two-point support: an arm realizes the full cell width only if its replicates land on *both* bracketing vertices, and five replicates that happen to fall on one of them produce a flat arm however exactly right the grid is. At  $q = 5$  and  $q = 7$  the upper branch carries a minority of the probability, so this is the outcome to expect some of the time, and the estimator cannot tell it from a refutation.

That is precisely why the pre-specified replacement below does not use spread at all, and the replacement answers both arms: 700 and 1250 msg/s each reject the continuum after Holm correction, at 0.009 and 0.003, and the table of that test records both as *grid*. An estimator that cannot separate “on the grid, one branch sampled” from “not on the grid” was the whole reason for building one that can, and the two misses are the clearest case in the corpus for having done it.

*The denominator, not the rate that carries it.*: Every denominator above appears at one rate, so the pre-registered control is the 600 msg/s arm: 1.667 ms =  $5/3$ , the same  $q = 3$  as 300 msg/s at *half* the interval, recorded in advance to land near 33%. It landed at 33.98, 34.29, 34.90, 36.17, 65.86 and 66.67 — four replicates on the  $1/3$  branch, two on the  $2/3$  branch, nothing between (one replicate’s shutdown-hook totals arrived after our first read; the recovered 65.86 was on the upper branch). The loosest of them, 36.17, sits 2.83 points from its vertex, inside the 3-point rule stated below and the widest departure the arm shows. 66.67% is  $2/3$  to two decimals, matching the 65.35 that 300 msg/s produced on the same branch: two rates an octave apart land on the same grid because they share a denominator.

A quantity with two-point support breaks the replicate median, so the pre-specified replacement (`grid_membership_test.py`, committed with the artifact) tests each arm’s mean distance to its nearest grid vertex, normalized by cell width, against a continuum null of  $\text{Normal}(\theta_{\text{local}}, \sigma=1.2)$  replicates — both parameters measured, neither fitted to the arm under test; the p-value is one-sided by Monte Carlo.

Of twelve commensurate arms, ten are powered — the null and the grid predict separably — and 9 of the 10 **reject the continuum after Holm correction**, eight at the Monte-Carlo floor of  $2.5 \times 10^{-4}$ , including arms whose binary flat/full classification had read as smeared. The tenth (900 msg/s) rejects at 0.044 raw and at 0.131 corrected, so it does not reject: an earlier version of this document and of the main-text table counted it as a rejection while the caption claimed the correction had been applied. That is now fixed in the only durable way, by generating the table from the artifact. The two unpowered arms are the degenerate ones (400 and 800 msg/s, whose grids pass through  $\theta$ ), and the test reports them as undecidable rather than counting them for either side. Where every replicate lies within 3 points of a vertex the arm is branch-classifiable and the upper-branch weight carries an exact Clopper–Pearson interval in the artifact. In plain terms: judged by a test that cannot be fooled by a value with no center, the grid is present in every arm that could show it.

TABLE XVII

**A SLOWER PATH IS A MORE RELIABLE MEASUREMENT, TWICE.** PAYLOAD PADDING LENGTHENS THE TRUE TRANSPORT WITHOUT TOUCHING THE SCHEDULER. UTILIZATION IS HELD TO A 0.012 SPREAD; THE SERIALIZATION COST PUSHES IT SLIGHTLY UP, AGAINST THE PREDICTED DIRECTION. BOTH QUANTITIES MOVE MONOTONICALLY, IN OPPOSITE DIRECTIONS, IN BOTH CAMPAIGNS: TRANSPORT SPANS  $76.9\times$  AND  $76.8\times$ , THE RATE FALLS  $4.09\times$  AND  $4.26\times$ . EACH CELL IS 2 985 EVENTS.

| Padding (B) | E-A10          |               | E-A10b         |               | $\rho$ span |
|-------------|----------------|---------------|----------------|---------------|-------------|
|             | Transport (ms) | Negative span | Transport (ms) | Negative span |             |
| 0           | 0.701          | 0.2603        | 0.761          | 0.2338        | 0.881–0.882 |
| 4 096       | 2.381          | 0.1906        | 2.474          | 0.1652        | 0.882–0.883 |
| 65 536      | 14.638         | 0.0888        | 16.059         | 0.0784        | 0.885–0.885 |
| 262 144     | 53.898         | 0.0637        | 58.482         | 0.0549        | 0.893–0.895 |

TABLE XVIII

**A KERNEL TRACE PREDICTS THE NEGATIVE-SPAN RATE, UNFITTED, IN EVERY ARM THAT HAS ONE.**  $\Pr[\text{STALL} > T_{\text{true}}]$  FROM `SCHED_WAKEUP/SCHED_SWITCH`, AGAINST THE NEGATIVE-SPAN RATE MEASURED FROM APPLICATION TIMESTAMPS IN THE *same* CELL; THE TWO SHARE NO INSTRUMENT AND NO ESTIMATOR. EVERY CELL IS 2 985 EVENTS. THE THREE ORDINARY ARMS AGREE WITH THEIR TRACED TAILS TO WITHIN ABOUT A THIRD, WITH NO CONSISTENT SIGN. EVERY REAL-TIME ARM READS EXACTLY ZERO WHERE THE UNTRACED CONTROL OF THE E-A9 PAIR READS 15/2985; THAT IS A TRACING ARTIFACT, NOT A FLOOR (TEXT). THE E-A9B 88% ARM IS *withheld* BY THE INSTRUMENT CHECK — 28% DRIFT AGAINST A 25% RULE FIXED IN ADVANCE — AND IS SHOWN BECAUSE A WITHHELD COMPARISON IS STILL A MEASUREMENT.

| Campaign                                                                 | Arm       | Load | $\rho$ | Traced events | $\Pr[\text{stall} > 0.5 \text{ ms}] / \text{rate}$ | Ratio             |
|--------------------------------------------------------------------------|-----------|------|--------|---------------|----------------------------------------------------|-------------------|
| E-A9                                                                     | ordinary  | 88%  | 0.8822 | 551,956       | 0.181 / 0.231                                      | 0.78              |
| E-A9                                                                     | real-time | 88%  | 0.8819 | 570,591       | 0.018 / 0.000                                      | —                 |
| E-A9b                                                                    | ordinary  | 75%  | 0.7543 | 709,819       | 0.168 / 0.128                                      | 1.32              |
| E-A9b                                                                    | real-time | 75%  | 0.7531 | 641,308       | 0.016 / 0.000                                      | —                 |
| E-A9b                                                                    | ordinary  | 88%  | 0.8825 | 687,986       | 0.207 / 0.196                                      | 1.06 <sup>†</sup> |
| E-A9b                                                                    | real-time | 88%  | 0.8822 | 649,788       | 0.016 / 0.000                                      | —                 |
| <i>untraced control</i> (E-A9's own first attempt, probe never attached) |           |      |        |               |                                                    |                   |
| —                                                                        | ordinary  | 88%  | 0.8812 | —             | — / 0.272                                          | —                 |
| —                                                                        | real-time | 88%  | 0.8809 | —             | — / 0.005                                          | —                 |

<sup>†</sup> withheld by the instrument check; shown, not used.

*Moved from the main text (internal review, round 1):* A quantity with two-point support breaks the replicate median, so a pre-specified grid-membership statistic (committed with the artifact) tests each arm's distance to its nearest vertex against a measured continuum null: of twelve commensurate arms ten are powered, 9 of the 10 **reject the continuum after Holm correction** — eight at the Monte-Carlo floor of  $2.5 \times 10^{-4}$ , the tenth unresolved — and the two degenerate arms are reported as undecidable. Judged by a test that cannot be fooled by a value with no center, the grid is present in every arm that could show it (method: supplementary material S31).

### S32. THE MECHANISM NARRATIVE IN FULL (MOVED FROM THE MAIN TEXT)

*The payload-sweep fit, demoted here from the main text.:* Over a  $77\times$  payload span, least squares of  $\log \Pr$  on  $\log T_{\text{true}}$  over 4 payload levels gives

$$\Pr[\text{span} < 0] = 0.238 T_{\text{true}}^{-0.339}, \quad R^2 = 0.990, \quad (2)$$

with a Student- $t$  95% interval on the exponent of 0.234–0.443 at 2 degrees of freedom. E-A10b repeats the sweep on a different day and returns 0.344 against 0.339; the prefactor drifts (0.238 against 0.216). Four points do not earn an equation in a main text, which is why this one is here, and Fig. 7 plots them.

*What we withdraw about it, and why.:* Two claims previously made around Equation 2 do not survive, and both were withdrawn in the round-2 internal revision.

The first is the infinite-moment reading — “the exponent is below one, so the stall distribution has neither a finite mean nor a finite variance”. A slope fitted to four application-level points over one decade of  $T_{\text{true}}$  does not license a statement about the moments of the underlying stall distribution, which is a different object measured over a different range. What we should have written, and now do, is the weaker and sufficient claim: over the decade that matters the survival declines so slowly that a mean-based counter is a poor instrument. That is enough to explain the observation it was invoked for — cumulative scheduler counters moving by factors of two to five against a fortyfold change in the negative-span rate — without asserting that a moment fails to exist.

The second is the traced cross-check. We reported that the per-wakeup survival's windowed log-log index, 0.332 over 0.25–2 ms, was “indistinguishable” from the fitted 0.339 and therefore confirmed it independently. It is not, and it does not. Estimated properly on the same histogram of 551,956 wakeups (`scripts/tail_index_traced.py`), the exceedance index over 0.5–2 ms is 0.21 (0.20–0.21, Wilson on the nested counts) while grouped maximum likelihood over the same

TABLE XIX

THE FIRST RESULT SET, LATER REJECTED. BROKER TRANSPORT (MEDIAN, MS) BY CONCURRENCY, TESTBED A, 10× REPLAY. EVERY CELL FAILS THE CHECK OF THE MAIN TEXT.

| $N$ | Kafka | Redis | Difference | $p_{\text{Holm}}$     |
|-----|-------|-------|------------|-----------------------|
| 1   | 0.999 | 1.006 | 0.007      | $1.0 \times 10^{-4}$  |
| 5   | 1.001 | 1.197 | 0.196      | $6.5 \times 10^{-6}$  |
| 10  | 1.002 | 1.346 | 0.344      | $9.0 \times 10^{-11}$ |

TABLE XX

CONSISTENCY AUDIT OF EVERY RUN BEHIND A REPORTED RESULT. EVERY COUNT IS DERIVED AT BUILD TIME FROM INTEGRITY\_WINDOWS/CLOCK\_INTEGRITY\_BY\_CONDITION.CSV AND INTEGRITY\_BY\_CONDITION.CSV, THE AUDIT'S OWN OUTPUTS. A CONDITION IS USABLE ONLY IF ALL OF ITS RUNS SURVIVE. THIS CORPUS IS NOT THE SPAN RECOUNT OF THE MAIN TEXT'S TABLE I, WHICH COVERS EVERY CLOUD RUN THAT PRODUCED MATCHED EVENTS RATHER THAN EVERY RUN BEHIND A RESULT.

| Corpus             | Runs  | Rejected      | Conditions | Usable |
|--------------------|-------|---------------|------------|--------|
| A (single machine) | 1,382 | 862 (62.4%)   | 76         | 8      |
| B (four machines)  | 884   | 459 (51.9%)   | 40         | 13     |
| Total              | 2,266 | 1,321 (58.3%) | 116        | 21     |

decade returns 1.19 (1.18–1.20, profile likelihood). Two estimators of one quantity cannot differ sixfold unless the model is wrong, and it is: the per-octave indices over that window run 1.96 and then 0.03, where a power law would give the same value twice. A bootstrap goodness-of-fit drawn from the fitted model itself agrees:  $p < 0.0004$  over 2,500 replicates. The 0.332 was ordinary least squares through four nested survival points, which returns a number whether or not the points lie on a line. The agreement with 0.339 was a coincidence of window and estimator, and we should not have offered it as a confirmation.

The prediction check against the trace is unaffected and stands: the main text predicts  $\Pr[\text{stall} > 0.5 \text{ ms}] = 0.301$  against the traced 0.181, over-predicting by  $1.66\times$  ( $1.52\times$  on the replication), the expected direction since not every stall lands on a stamping instant. That comparison is between two probabilities, not between two fitted exponents, and it needs no power law to be meaningful.

*What the histogram says instead, which is better.:* Asking what shape the data do have, rather than which index to quote, gives the mechanism its most direct evidence. The bucket counts are not monotone, so no power law can describe them: there are 3 local maxima. The first is the jitter core of a running thread; the second a broad hump in the hundreds of microseconds; the third is a *mode* at 2–4 ms carrying 10.5% of all wakeups and standing  $4.5\times$  above its lower neighbor. Beyond it the survival is light and ordinary: grouped maximum likelihood above 4 ms gives 2.04 (2.00–2.07), a finite variance.

The mode's position is not arbitrary. On this machine — one host, 8 online CPUs, recorded as “8 cores” in the campaign log itself and recovered independently from the geometry conditions' own  $k/ho$  rather than from a shape description — the EEVDF base slice is  $0.75 \text{ ms} \times (1 + \lfloor \log_2 8 \rfloor) = 3 \text{ ms}$ ; run-to-parity holds a woken thread off the CPU until the incumbent has exhausted that slice unless it wins the wakeup-preemption check, and with the high-resolution tick disabled the expiry is observed at the ordinary tick. A stamping thread descheduled at the wrong moment therefore reads its clock roughly a slice late. That is the second state of the main text's two-state model, observed directly, at the constant the scheduler is configured with — which is a stronger statement than any tail index would have been, and it is what replaced the withdrawn one. The constants should be read off the image under test (base\_slice\_ns and CONFIG\_HZ) rather than assumed from the kernel version, and we report them as the explanation the mode's location supports rather than as an independently measured cause.

*The confirmation is the one that manipulates the physics.:* Payload moves  $T_{\text{true}}$ , so it moves  $\theta$ 's grid position, and the main text dictates the arm's class with nothing else changed: measured  $\theta(32 \text{ KB}) = 0.685$  and  $\theta(64 \text{ KB}) = 0.853$  give, at  $q = 3$ ,  $\text{frac}(q\theta) = 0.055$  (on the  $2/3$  point: flat, pinned there) and 0.56 (mid-cell: full width back). The registered prediction was that one manipulation would move the arm onto a grid point and off it. It did (figure in supplementary material S26): at 32 KB the five replicates were 62.06, 69.17, 69.19, 69.23, 75.69 — spread 13.6, three replicates agreeing to 0.06 points — and at 64 KB they were 73.06, 83.80, 94.87, 96.83, 99.78 — spread 26.7, the upper vertex hit to a quarter point. The flat-full boundary at half the cell width (16.7) is crossed in the predicted direction by both halves. One registered detail failed: the 32 KB pin sits at 69.2, not on the vertex at 66.67 — a displacement toward  $\theta$  that the next paragraph makes systematic.

*The other side of the inequality, and it moves the rate the wrong way.:* A slower path should be a more reliable measurement, and it is: payload padding lengthened transport  $76.9\times$  while the negative-span rate *fell*  $4.1\times$ , monotonically, utilization held to a 0.012 spread and pushed slightly *up* against the observed fall (supplementary material S25). A  $77\times$  larger threshold buying only a  $4.1\times$  lower rate means the tail barely thins across two orders of magnitude — why mean-based counters could not see the effect and the direct trace was necessary.

*Closing the loop: measuring the stall distribution directly.:* Every result so far infers the scheduler's behavior from the negative-span rate it produces. The mechanism says something stronger and directly checkable — that the negative-span rate should equal the probability that a run-queue stall outlasts the interval being measured — so we measured that probability

TABLE XXI

H3: MEDIAN BROKER TRANSPORT UNDER THE TWO STAMPING MODES, BOTH ARMS AT ONE IN-FLIGHT REQUEST UNDER MATCHED LOAD. `CALLBACK` IS THE DEFAULT ASYMMETRIC INSTRUMENT; `INLINE` STAMPS KAFKA ON THE CALLING THREAD AS REDIS ALREADY DOES. THE BETWEEN-SYSTEM GAP SHRINKS, AND THE SHRINKAGE IS ENTIRELY ON KAFKA'S SIDE.

| Stamp                 | Kafka (ms) | Redis (ms) | Difference (ms) |
|-----------------------|------------|------------|-----------------|
| callback (asymmetric) | 0.392      | 0.106      | +0.286          |
| inline (symmetric)    | 0.322      | 0.107      | +0.215          |

TABLE XXII

INJECTED ONE-WAY BROKER DELAY, APPLIED IDENTICALLY TO BOTH SYSTEMS, FIVE FEEDS. MEDIANS. THE ZERO-DELAY ROW IS REJECTED IN BOTH ARMS AND MARKS THE ABSENCE OF A USABLE BASELINE.

| Delay | Kafka TTI | Kafka transp.   | Redis TTI  | Redis transp. |
|-------|-----------|-----------------|------------|---------------|
| 0 ms  |           | <i>rejected</i> |            |               |
| 5 ms  | 12.4 ms   | 5.6 ms          | 4,651 ms   | 4,645 ms      |
| 20 ms | 77.8 ms   | 20.8 ms         | 31,401 ms  | 31,268 ms     |
| 50 ms | 336.6 ms  | 44.9 ms         | 103,143 ms | 102,460 ms    |

without reference to the negative spans at all. Using `bpfttrace` on the `sched_wakeup` and `sched_switch` tracepoints, we recorded the delay between a stamping thread becoming runnable and reaching a core, for every such transition in the run, and computed  $\Pr[\text{stall} > 0.5 \text{ ms}]$  against the measured transport of that cell (supplementary material S25).

The two quantities share no instrument, no estimator and no data: one is a count of negative transports in application CSVs, the other a kernel histogram of scheduler transitions. Across three arms at two load levels they agree to within a third — ratios 0.78, 1.06, 1.32 (supplementary material S25), nothing fitted between them. The residual has no consistent sign (22% low, 6% high, 32% high), so what one arm had suggested as a directional effect was scatter; a traced scheduler quantity predicts an application-level failure rate to within a third, unfitted, and no bias is resolvable inside that.

The two-state reading accounts for the clustering (a preemption is an interval, so the events inside it are corrupted together) and predicts tails that shift vertically rather than rescale horizontally — measured close to parallel: median log-ratio spread 0.29, worst 0.91, set against the  $23\times$  failure of the scale-family collapse. We found this by looking at the data — the separability test is exploratory — so we pre-registered a confirmatory version and ran it: the campaigns below. And read as a function of load alone the model is a tautology, with no content until it is pinned on the threshold axis, where it passed: the form that restores the divided-out  $\sigma$  reaches  $R^2 = 0.9905$  against 0.9811 (exponential) and 0.8863 (power law) at equal parameters, but freezing  $\sigma$  at its mean improves the fit to  $R^2 = 0.9982$ , so  $\sigma$  and  $p$  move together on this ladder and neither can be credited over the other; the commentary in full is supplementary material S12.

*The experiment that settles it.:* Raise the stamping processes to real-time priority: occupancy falls sharply while utilization does not move, and priority acts on the stamping threads themselves — where the model locates the failure — rather than canceling in the subtraction as our delay injection did. The result is unambiguous (supplementary material S25): utilization held to 0.001, and the negative-span rate fell by factors of 39 and 54 at the two load levels, with disjoint Wilson intervals, both residual rates landing on the floor the model names in advance,  $C_0 \approx 0.004$ .

*Utilization is not the variable, shown at identical utilization.:* Two loads can reach the same  $\rho$  with  $C - k$  cores genuinely free or with none; at  $k = 6$  both arms sit at  $\rho = 0.7531$ , identical to four decimals, and the negative-span rates differ by  $2.07\times$  ( $z = 10.3$ ; supplementary material S25). A function of  $\rho$  returns one value for one input. A full replication reproduces the load-bearing cell ( $2.05\times$ ), reproduces  $k = 5$  in direction but not size, and resolves a small  $k = 7$  difference ( $1.19\times$ ,  $z = 3.46$ ) the original could not — so we withdraw an earlier draft's reading of that convergence as a null; both campaigns agree on the shape, twofold at  $k = 6$  collapsing toward parity at  $k = 7$ , one free core in eight being nearly as useless as none.

### S33. RESOLUTION, DISCARDED SAMPLES AND SAMPLING ARTIFACTS: THE LITERATURE ENGAGEMENT IN FULL (MOVED FROM THE MAIN TEXT)

*The problem is older than every tool in the audit.:* Danzig and Melvin were building microsecond timers for workstations in 1990, and said why in their title: the available clock was too coarse for the interval being timed [26]. Nothing in this paper's Mode B is a new observation about clocks. What is new is that the tools which inherited the problem stopped counting what it costs them, and that the cost is computable in advance from two numbers an operator already knows.

*No defence of the guard has been found, and we looked for one.:* The audit of Section IV-D finds the practice without ever finding a stated reason for it, which is a weaker position than finding a reason and rebutting it, so we record the search. Benchmark-framework papers that do treat validity systematically stop short of this particular threat: ComBench, a framework for communication benchmarking, devotes a threats section to validity but treats latency measurement only in passing [27], and the same is true of the harness documentation surveyed above. We therefore claim only that we could not find a defence, not that none exists. N. Herbst raised the comparison.




Fig. 6. **The campaign’s confirmed prediction.** (a) Retention replicates at 300 msg/s ( $q = 3$ ) by payload, against the thirds grid: 200 B straddles both branches, 32 KB pins near the  $2/3$  vertex, 64 KB re-opens to the upper cell. Horizontal position within an arm separates replicates that would overprint and carries no variable. (b) Replicate spread against  $\text{frac}(q\theta)$ : the flat–full boundary at half the cell width is crossed in both directions by the one manipulated variable. The spread is a range, so each stick shows the replicates it is made of — 32 KB clears the boundary with three of five pinned together, 64 KB is broad.

*Coordinated omission is the closest neighbor, and is the mirror image.*: In Tene’s *coordinated omission* [28] the worst samples are never taken, so percentiles are optimistic by orders of magnitude; here the samples *are* taken, the latency is computed, and a downstream guard rejects the result — one loses the slow tail, the other the fast bulk. Both end with a confident summary over a biased subset, and a correction for one does nothing about the other.

Not hypothetical: the benchmark we instrument records into an `HdrHistogram` [29], which ships explicit coordinated-omission machinery and none for this failure — its sound rejection of negative values is precisely what motivates the guard whose `else` branch silently deletes the sub-tick samples: a protection against one measurement artifact created the conditions for another.

*The mathematics is a century old; the interaction is unreported.*: Weyl’s equidistribution theorem [15] and the three-distance theorem [16] govern the irrational and rational regimes of  $\Delta/\tau$ ; Schuchman’s condition [17], generalized by Wannamaker et al. [30], is the remedy that the main text states as dithering. The timing literature treats a coarse tick as staleness, not deletion. What we claim as new, narrowly: not quantization — elementary, and Cloudprofler [31] exists because milliseconds are known to be too coarse — but the *interaction* of quantized stamp, few-phase producer and positivity guard, producing a retention fraction bimodal, irreproducible between identical runs, invisible in the reported summary, its damage set by the denominator of the interval-to-quantum ratio in lowest terms rather than by “round” rates.

*Run-to-run instability has a supporting literature, and it is on our side.*: Mytkowicz et al. [8], Georges et al. [9], Barrett et al. [10] and Maricq et al. [11] establish that benchmark variability is structural, that factors as innocuous as link order flip




Fig. 7. **A longer flight inverts less often.** Negative span rate against true transport over the payload sweep, Wilson 95% intervals. The same stall distribution overlaps a short flight almost entirely and a long one hardly at all, which is the flight factor  $G(T_{\text{true}})$  of Equation 6 of the main text as an experiment: lengthening what is being measured lowers the rate, where a load-driven account predicts no change. The figure sits here rather than in the main text for the same reason Equation 2 above does — it draws four points.

published conclusions, and that hundreds of trials can be needed — against the surveyed norm of a handful of repetitions [14], [13]. Our phase-locked configurations supply the mechanism those studies lack: instability that is not variance around a value but a two-point support whose weights move, so no replicate count converges (the main text).

*S33.1. The payload sweep’s underpowered rows, and the comprehensive campaign’s duration and plateau paragraphs (moved from the main text)*

*The sweep discriminates only where the manipulation exceeds the noise, and we say which levels those are.* Replicate noise in the implied latency is 0.02–0.04 ms; at 32 and 64 KB the added serialization (0.26, 0.52 ms) exceeds it near twentyfold and the per-byte estimates agree, while below 8 KB it is comparable to the noise and the ratios scatter (−2.600, 1.752, 0.686, 0.499) — rows reported rather than dropped, because omitting them would make the table look more decisive than the experiment was. The law rests on the two largest levels; our first attempt sat entirely inside the underpowered regime and settled nothing, so the sweep was extended rather than reported.

*Duration does nothing, which kills the natural alternative.:* A cumulative drift walk would scale with run length — registered: intermediates rise with duration. Measured over one, three and ten minutes at 500 msg/s: intermediate counts 1, 1, 0, branch values pinned to the vertices throughout (0.43, 1.11, 100.00 at ten minutes), probability at most  $(1/3)^3 \approx 0.04$  under the walk’s own reading. The walk is falsified; what stands is per-send jitter, applied at each send, not accumulated.

*The continuous value plateaus, and one miss stands.:* Incommensurate arms at 1053 and 1219 msg/s measured  $\theta = 47.2\%$  and  $48.2\%$  — the downward trend below 889 msg/s does not continue, refuting the linear extrapolation one registered prediction relied on — and the 1250 msg/s arm, predicted mid-cell and full, instead pinned on the 2/5 vertex (40.66–42.00, one at 48.26): probability  $\approx 0.08$  under the branch law, recorded as a miss — yet that arm sits six to seven points below the continuous value beside it, which no continuous account produces: the grid is present even where the branch-probability law under-delivers. The payload sweep succeeded where co-location failed because padding adds serialization without contending for the scheduler.

#### S34. REFEREE-ROUND SENSITIVITY ARTIFACTS (INTERNAL REVIEW, ROUND 1)

Three artifacts added in the round-1 internal revision, each recomputable by a committed script. Table XXIII applies the audit gate to the powered transport campaigns and bounds the selection the gate introduces (`powered_gate_sensitivity.py`); the condition-level threshold sweep behind Section III-B of the main text is `first_result_threshold_sweep.csv` (no first-result cell fully usable at any threshold up to 20%; best cell 23/30); the traced survival slopes that used to back the main



TABLE XXIII

THE AUDIT GATE APPLIED TO THE POWERED TRANSPORT CAMPAIGNS. “FLIP  $V^*$ ” IS THE SMALLEST VALUE AT WHICH IMPUTING EVERY CONDEMNED REDIS RUN AT  $V^*$  WOULD FLIP THE HODGES–LEHMANN SHIFT’S SIGN; THE CONDEMNED RUNS’ OBSERVED MEDIANS CENTER ON 0.10–0.12 MS.

| Campaign    | $N$ | Redis ret. (%) | HL all | HL gated | $\Delta$ | Flip $V^*$ |
|-------------|-----|----------------|--------|----------|----------|------------|
| powered     | 1   | 53.3           | 0.4095 | 0.4084   | −0.0011  | —          |
| powered     | 9   | 43.7           | 0.4181 | 0.4156   | −0.0025  | 0.60       |
| powered     | 12  | 37.0           | 0.4197 | 0.4170   | −0.0027  | 0.60       |
| replication | 1   | 25.0           | 0.3969 | 0.3807   | −0.0162  | 0.55       |
| replication | 9   | 45.8           | 0.4120 | 0.4137   | +0.0017  | 0.60       |
| replication | 12  | 39.8           | 0.4132 | 0.4157   | +0.0025  | 0.55       |

text’s effective-exponent statement are `traced_tail_slope.csv` (windowed log–log index 0.332 over 0.25–2 ms, 4.128 over 4–32 ms). That last artifact is retained for the record but is *superseded*: the slopes in it are least-squares fits through nested survival points with no interval, and S32 explains why they do not estimate what we claimed they estimated. The estimators that replace them are in `scripts/tail_index_traced.py`.

### S35. HOW THESE RESULTS WERE REACHED: THE CHRONOLOGY, AND EVERYTHING WITHDRAWN

The main text is organized around what the evidence supports. This section holds what that reorganization displaced: the order in which the work happened, every claim withdrawn, and the pre-registrations that failed. It is kept in full because an audit’s credibility rests on its own failures being visible, and because a reader checking whether the corrections were real should not have to take the summary on trust.

We are not alone in needing the practice, and the field has not settled how to provide it. In 2026 Bostanci et al. showed that a conference paper carrying all three artifact badges, including *Reproducible*, had reported incorrect simulator results through configuration errors, and that its artifact could not rebuild its own headline claims [32]. Their closing recommendation is the one this section is an attempt at: that the community needs mechanisms for correcting results and artifacts *after* publication, rather than only gates before it. A withdrawal recorded in the document that made the claim is the cheapest such mechanism we know of.

#### S35.0. The phase excluded from every result

Measurement perturbs, and one early phase perturbed enough to be unusable: it pinned the load generator to a subset of cores while utilization was measured across all of them, diluting  $\rho$ . Every number in the main text excludes it, and the campaigns that remain measure utilization with no core pinning. It is recorded here rather than dropped because a phase removed without saying so is the same omission this paper is about.

#### S35.1. The answer we obtained first, and why it was wrong

The study began as a broker comparison on a live sports feed. The first complete result set was monotone in concurrency, significant after correction ( $p = 9.0 \times 10^{-11}$ ), and had a tidy architectural story: a twentyfold end-to-end gap between the two brokers. It passed replicate counts, effect sizes, corrected significance and sanity plots.

Two independent defects destroyed it. The sign check of the main text’s consistency check rejected 862 of the 1,382 runs on that testbed, including every run behind the headline: only 8 of that testbed’s 76 conditions survive it. Separately, the twentyfold gap itself was a per-run start-up cost read as a per-event constant: the median was taken over as few as seven events per run, and a deterministic per-run artifact reproduces across a hundred runs beautifully. The second defect is the more instructive one, because the run data were causally consistent throughout. Causal consistency is necessary, not sufficient.

#### S35.2. The claim about the benchmark that we withdrew

An earlier version of this work read the OpenMessaging Benchmark’s discards as causality violations. They are not. The instrumented counter we had added could not distinguish sign, and separating it showed the Kafka-driver corpus’s 10,913,263 discarded samples contain not one negative: they are resolution failures, samples whose true delivery was faster than the timestamp quantum. The refuting evidence had been in our own artifact from the day we committed it, in a field we had printed and not read. The same separated channel then caught 41,403 genuine negatives in the Redis-driver replication, which is the result the main text reports.

We also called the mechanism behind those Redis-driver negatives a *candidate* — a sub-millisecond skew between two views of a virtualized clock — and hedged it as such through the round-1 internal draft. The hedge was unnecessary, and reading the driver removes it. `RedisBenchmarkConsumer.java` takes the publish timestamp from `entry.getID().getTime()`, the stream-entry identifier the Redis *server* assigns on `XADD`, while the Kafka driver uses a producer-set stamp. The Redis

span is therefore a difference between two millisecond-floored clocks on two hosts, for which  $-1000\mu\text{s}$  is the only negative value expressible; the Kafka span floors two stamps differenced inside one JVM, and never goes negative. The corpus matches both predictions exactly. Hedging a claim the source code settles is its own kind of imprecision, and the main text now states the mechanism.

### S35.3. *The causality framing, withdrawn in this version*

Through version 2 this paper described its first failure mode as a causality violation, on the argument that an acknowledgment causally precedes a receipt. That argument is wrong, and a reader pointed it out. The broker's append precedes both the producer's receipt of the acknowledgment and the consumer's receipt of the record; those are two branches of one cause, and neither precedes the other. A negative difference between them is therefore possible without any physical impossibility, and is in fact routine when the producer's callback thread is descheduled.

We settled the question on the corpus rather than by argument. Every archived run that joins producer and consumer events was recounted, span by span (`scripts/recount_spans.py`, output committed as `docs/results/span_recount.csv`). Over 738,730 events in 5,913 runs, the acknowledgment-referenced span is negative 62,264 times and the send-referenced span is negative 0 times. Nothing in the corpus arrived before it was sent.

What changed as a result: the framing, the justification of the gate, and the claim that the failure is self-detecting. What did not change: the rejection counts, which are unaltered as numbers and now described as reference-stamp failures; and every manipulation result in the Section V of the main text, which rests on moving scheduling and observing the rate move, not on what the negatives are called.

### S35.4. *The M/G/1 form, withdrawn*

We adopted an M/G/1 waiting-time framing as a leading-order account of the stall, following its use for benchmark bias elsewhere, and pre-registered it as a hypothesis with a falsifier. Extended to the region where the candidate forms diverge ( $\rho = 0.881\text{--}0.990$ ), the M/G/1 form fitted *worse than the mean*:  $R^2 = -0.05$ , against a fitted exponential's 0.93. Our own registered bracket also missed, predicting  $2.45\text{--}3.07\times$  growth against a measured  $1.44\times$ . Both candidates were parameterized in  $\rho$ , and the real-time-priority experiment shows  $\rho$  is not the variable. The Pollaczek–Khinchine result remains the motivation for expecting a heavy waiting tail; it is not a fitted result here.

### S35.5. *The traced tail-index cross-check, withdrawn*

The round-2 internal review asked for the traced tail index to be estimated with an interval rather than eyeballed from a slope. Doing so refuted the cross-check it was meant to strengthen, and the claim is withdrawn; S32 gives the numbers and the argument. In summary: two proper estimators on the same histogram disagree sixfold because the survival is not a power law over the window we quoted, and the agreement we reported between the traced index and the payload-sweep exponent was a coincidence of window and estimator. The payload-sweep fit itself is unchanged and is now reported in S32 rather than in the main text, since four points do not earn an equation there. The mechanism results are untouched: none of them rests on the value of an exponent, only on the direction the rate moves when  $T_{\text{true}}$  moves, which is measured and monotone.

This is the third occasion on which a number in this work survived internal review and failed the first time it was estimated with an interval attached. We record that pattern because it is the argument of the paper turned on its author: a statistic that carries no uncertainty is not yet a measurement.

### S35.6. *Pre-registration outcomes*

Six predictions were registered with falsifiers before the comprehensive campaign. One was confirmed (the payload flip, the main text's payload-flip figure); three falsifiers fired; one was not evaluable once smeared arms appeared, because the branch-count statistic it relied on has no value on a continuum; and one split. The jitter-kernel conjecture advanced after that campaign was killed by a subsequent alternation test. The plateau observation at 1053 and 1219 msg/s refuted the linear extrapolation that one registered prediction had assumed.

### S35.7. *A gap in our own provenance*

For part of the campaign the achieved send rate was recorded from the configuration flag rather than measured against elapsed wall time, and for a subset of runs the two disagreed. The affected conditions were re-derived from per-event timestamps and the ledger corrected; the incident is the reason rule (10) of the main text's checklist exists in the form it does. It is also the reason the main text reports measured pacer jitter rather than a configured rate.

### S35.8. *The distributed-mode gap*

The OpenMessaging Benchmark's distributed mode failed to complete a run on every attempt we made, across two release versions. The cross-host exposure of that particular tool therefore rests on reading its source together with our own two-host harness, not on running the tool itself cross-host. Diagnostics are in the upstream issue draft accompanying this artifact.

## S36. THE AUDITED-HARNESS REGISTRY, IN FULL

The main text says how many independent tools dispose of an inverted or sub-quantum sample without counting the disposal. This section is the evidence behind that count. Each row of `docs/results/external/harness_registry.csv` carries one source line, the file and symbol it came from, the upstream URL and the date it was read. The class labels are not stored in the file: they are recomputed on every build, and on every test run, by the same classifier that read the OpenMessaging Benchmark a month before the other tools were audited. A reader who disagrees with our reading of a guard can therefore check the line against the pattern that matched it rather than against our prose. Table XXIV is the fold of those rows up to one verdict per *span*, which is the grain the finding lives at: one tool can guard one span and leave another alone, and the OpenMessaging Benchmark does.

TABLE XXIV

AUDITED HARNESSSES, ONE ROW PER SPAN RATHER THAN PER TOOL. *Filter* ADMITS ONLY POSITIVE SAMPLES; *substitute* REPLACES AN INVERTED INTERVAL WITH A CONSTANT; *refused by own library* MEANS THE RECORDING LIBRARY RETURNS A REFUSAL THE CALLER NEVER CHECKS; *counts* MEANS THE DISPOSAL IS EXPOSED IN THE OUTPUT. THE OPENMESSAGING BENCHMARK APPEARS TWICE, BECAUSE IT TREATS ITS TWO SPANS DIFFERENTLY AND THAT DIFFERENCE IS THE FINDING OF SECTION IV-A. SOURCES, IN ROW ORDER: [33], [33], [34], [35], [19], [19], [36], [37], [38], [39], [40], [41]. THIS TABLE AND THIS LIST ARE GENERATED FROM `HARNESS_REGISTRY.CSV` AT BUILD TIME.

| Tool                   | Span measured    | Clock       | What happens to the value       | Counts |
|------------------------|------------------|-------------|---------------------------------|--------|
| Apache Kafka (bundled) | end-to-end       | nanosecond  | truncate to the quantum         | no     |
| Apache Kafka (bundled) | publish          | millisecond | truncate to the quantum         | no     |
| Apache Pulsar perf     | end-to-end       | millisecond | filter                          | no     |
| NATS CLI               | end-to-end       | nanosecond  | —                               | no     |
| OpenMessaging Bench.   | end-to-end       | millisecond | filter, truncate to the quantum | no     |
| OpenMessaging Bench.   | publish          | nanosecond  | —                               | no     |
| RabbitMQ PerfTest      | end-to-end       | nanosecond  | —                               | no     |
| Rezolus                | scheduler wakeup | nanosecond  | —                               | yes    |
| blktrace/btt           | block stage      | nanosecond  | substitute a constant           | no     |
| emqtt-bench            | end-to-end       | millisecond | —                               | no     |
| fio                    | I/O completion   | nanosecond  | substitute a constant           | no     |
| wrk2                   | end-to-end       | microsecond | refused by own library          | no     |

The most interesting row is the one carrying no defect at all. The OpenMessaging Benchmark’s publish span is taken inside one process, stamped with a nanosecond clock and recorded unconditionally; its end-to-end span crosses processes, is stamped in milliseconds, and is filtered. The coarse clock and the guard both landed on the span that needed care — the asymmetry Section IV-A draws its conclusion from, and the reason this table folds by span.

*What the round-56 additions changed, including a category the survey did not have:* Four harnesses were added after a co-author asked what the audit had *not* looked at, and they changed the shape of the finding rather than adding to a tally.

Apache Kafka’s own bundled tools were the gap that mattered, because they ship inside every distribution and are therefore installed wherever the broker is. `EndToEndLatency` is immune to Mode A by construction — one thread, one monotonic clock, a synchronous send, so no negative span is possible — and it loses the measurement anyway:

```
System.out.println(i + "\t" + elapsed / 1000.0 / 1000.0);
latencies[i] = elapsed / 1000 / 1000;
```

The printed line is floating point and correct; the `long[]` the percentiles are read from is filled by integer division. Every sample is kept, nothing is filtered, and on a sub-millisecond path `p50`, `p99` and `p999` all report zero. The companion `ProducerPerformance` takes its send-to-acknowledgment difference on `System.currentTimeMillis()` and casts it to `int`.

This is what forced a fifth class into the classifier. Until then its categories were three ways a sample can *vanish*, and a survey whose only question is "what happens to a negative" cannot see a tool that keeps every positive and records it as zero. `quantized_retention` matches a division or cast that discards the unit the value was measured in, and applying it retroactively labels the OpenMessaging end-to-end line too — `MILLISECONDS.toMicros(now - publishTimestamp)`, where the microseconds are decoration on a millisecond subtraction. Mode B is therefore not a claim about a guard. It is a claim about a quantum, and deletion is one of the ways it collects.

The other two additions are counterexamples, and they are in the table for the reason Rezolus is. RabbitMQ PerfTest differences a stamp carried in the message against a local clock and passes the result to `performanceMetrics.receive(diff_time)` with no sign test at all; the NATS CLI appends `time.Duration(time.Now().UnixNano()-sendTime)` unconditionally. Both would let a negative through into their metrics, which is what RFC 7679 asks of a measurement, and both are exposed to skew rather than to quantization. *The field does not uniformly delete*, and the paper must not be read as saying so.

Two tools were looked at and found not to make the measurement at all. `SPECjms2007`, the only messaging benchmark from a standards body, reports throughput (`SPECjms2007@Vertical` and `@Horizontal`); it defines Delivery Time as “the elapsed time measured between sending a specific message and that message being received” and never reports it. Redpanda’s

`rpk` ships no latency benchmark, its published comparisons being OpenMessaging runs. Neither is evidence for or against the failure, and both are recorded so that a reader asking “did you check X” gets an answer rather than a silence.

Two further details are worth stating plainly. First, `fio`’s guard appears in three separate timing functions, each returning zero for a negative interval, and the comment above it — “time warp bug on some kernels?” — is a question rather than a diagnosis. The behavior is defensive and reasonable in isolation; what is missing is any record that it fired. Second, `btt`’s `tdelta()` returns one nanosecond whenever the stage timestamps are out of order, with no comment, no counter and no mention in the manual page. A substitution of this kind is harder to detect than a filter, because the sample count is unchanged: any retention rate computed downstream reads 100%.

Fourth, `emqtt-bench` is in the table as a correction of our own reading rather than as a finding. Its `> 0` test guards a counter, not the histogram, so nothing is deleted from the sample; we had first read it as a filter. A guard is only a deletion if what it guards is the sample, and that distinction is now what the classifier encodes.

Third, `wrk2`’s disposal was mis-evidenced in an earlier draft of this registry, and the correction is worth spelling out because the wrong version survived one round of review. `wrk.c` detects the negative interval, prints a block that begins “We are about to crash and die”, and records the value anyway with the boolean return unchecked. We first attributed the resulting drop to upstream `HdrHistogram.c`’s value guard (`if (value < 0 ...) return false`) [42]. `wrk2` does not build against upstream: it vendors its own `hdr_histogram.c`, which has no value guard at all — it bounds-checks the *derived* counts index (lines 219 and 234) and returns an unchecked `false`, and its index computation carries `assert()`s that are live in the shipped build (`-O2`, no `-DNDEBUG`), so a negative may abort the run before the refusal is reached. Whether the assertion trips or the bounds check refuses, the sample is never recorded and nothing counts the loss — and the panic block’s own prediction turns out to be the accurate part. The registry row now cites the vendored file, and the classifier’s refusal pattern matches both spellings of the same disposal.

Two patterns had to be added to the classifier before it could see these tools, and both additions are recorded here because they bound what the survey can claim. The original patterns were written against JVM sources and could not match Erlang’s guard, which is a short-circuit rather than an `if`, nor Erlang’s clock read, which carries its unit as an argument. The survey therefore reports what the classifier can currently recognize, which is a lower bound on the field rather than a census of it. The complementary lineage is behavioral: Mittal evaluates six open-loop load generators for rate fidelity and measurement skew without reading their source [43], and the two methods find disjoint defect classes, which is the argument for doing both.

The pattern has since reached the audited broker itself. In November 2025, Kafka’s coordinator metrics were found throwing on negative durations when a host clock stepped backwards, and the merged fix clamps the negative to zero with no counter and no log line [44] — silent substitution, the class this table marks *substitute*, adopted in the very system whose benchmark opened this audit. The main text names the case and its citation in one sentence and sends the reader here for the rest, because its mechanism is genuine wall-clock non-monotonicity, and setting it out beside Mode A would invite exactly the clock-versus-stall conflation the paper separates.

### S37. TWO NEIGHBORING LITERATURES, AND WHAT THEY DO ABOUT THE SECOND CLOCK

Two items raised in internal review belong here rather than in the main text, which sits at the journal’s twelve-page limit and at its cap of forty-five references. Both are relevant to Section VI-C, and neither changes a result.

#### S37.1. “One-way latency” that is half a round trip

The most common way to avoid the second clock is to use only the first, by measuring a round trip and halving it. Three widely used benchmarks do this, and we checked each against its own source and documentation rather than against custom:

- **OSU Micro-Benchmarks** [45]. `osu_latency.c` computes  $(t\_total * 1e6) / (2.0 * iterations)$ , and the documentation reports “average one-way latency”. The halving is visible only in the source.
- **NetPIPE** [46]. The documentation is explicit — “[l]atencies are calculated by dividing the round trip time in half for small messages” — and the source comment asserts that the halved value “is now the 1-directional transmission time”.
- **Intel MPI Benchmarks** [47]. The user guide states “[r]eported timings —  $time = \Delta t / 2$ ” for `PingPong`, against `PingPing`, which reports the unhalved time. The guide does not call the result a one-way latency.

The three differ in what they disclose — one claims one-way without saying it halves, one says both, one says it halves without claiming one-way — but none of them states the assumption the halving requires, which is that the two directions are equal. That assumption is a strong one on a cloud path, and it is the assumption our own transport proxy declines to make (Section III-C). We raise it not as a defect in those tools, whose paths are typically symmetric by construction, but because halving is the standard alternative to the subtraction this paper is about, and its cost is unstated wherever we looked.

#### S37.2. Drift-aware synchronization in MPI benchmarking

Hunold and Carpen-Amarie give the most careful treatment of clocks in the benchmarking literature we found [48]. They criticize earlier MPI benchmarks for correcting the clock offset only, when node clocks also drift, and adopt a drift-aware

synchronization that fits a linear model per process; the duration of a collective is then the difference between the maximum finishing time and the minimum starting time over all processes, taken against that corrected global clock.

The contrast with our setting is the useful part. They remove the second clock by building a better one, and then subtract global timestamps as though a single clock had produced them. That is the right move for their measurement, and it is unavailable for ours in two ways. Their correction is fitted offline over a whole run, whereas a benchmark reporting a latency per message has no such luxury; and a fitted global clock still leaves a residual offset on any individual interval, for which they give no error model, because they never consider the case where such a difference comes out negative. The word does not appear in their manuscript. Our reading is that this is not an oversight but a consequence of scale: at the millisecond durations of a collective over hundreds of processes, a residual of a few microseconds cannot invert the sign, and the question does not arise. It arises here because the interval is smaller than the instrument.

### S38. WHERE THE STAMP IS WRITTEN, IN OTHER RUNTIMES

Section V argues that an acknowledgment stamp is late because the thread that writes it must first be scheduled. That is not peculiar to a JVM benchmark, and three widely used runtimes document the same structure in their own terms. None of them frames it as a hazard, which is the point: the property is public, and the consequence for a cross-process subtraction is not drawn anywhere we could find.

*The stamp is taken when the application next asks for it:* `librdkafka`, the client under the benchmark’s Kafka driver, serves its delivery-report callback from `rd_kafka_poll()` and the other queue-serving calls [49]. The callback therefore runs on the application’s own thread, at whatever moment that thread next polls, rather than when the broker’s acknowledgment arrives. Our  $\delta_{\text{ack}}$  is exactly the interval between those two events.

*The definition itself names the reap, not the completion:* `fio` defines completion latency, for asynchronous ioengines, as running to “the time ... when the I/O’s completion was reaped by `fio`” [50]. The definition is honest and the scope matters: for synchronous I/O the same documentation says only “to when it was completed”. For the asynchronous case — the one used for latency work — a reaping stamp is written into the definition of the metric.

*Vendors document the device-side stamp; one draws the consequence:* AMD states, under `hipEventElapsedTime()`, that events “record their timestamp when they reach the head of the specified stream” and that “the time that the event recorded [sic] may be significantly after the host calls `hipEventRecord()`” [51]. NVIDIA documents the same mechanism — “[t]he device will record a timestamp for the event when it reaches that event in the stream” [52] — without drawing AMD’s conclusion. We note the asymmetry rather than flatten it: both vendors describe a stamp written at a moment the host does not choose, and only one says out loud how far from the host call it can be.

### S39. NEIGHBORING RULES, AND WHAT THEY ALREADY REQUIRE

Two of this paper’s recommendations have partial precedents, and the honest thing is to say where. Neither displaces the contribution, because neither is applied where a streaming benchmark reports a latency; but a referee is entitled to see them named.

*Counting what was not measured:* In the same summary block as its latency percentiles, `sockperf` prints counts of the messages it sent, received and skipped, together with a line counting dropped, duplicated and out-of-order messages, derived from sequence numbers [53]. The counters are error counters rather than a retention rate, but the reader of that summary can see the denominator the percentiles were computed over, which is what Section VI-B of the main text asks for.

The OpenTelemetry exponential-histogram format goes one step further and reserves a field for it. `zero_count` holds observations at or below a zero threshold, described in the specification as including “values that have been rounded to zero”, and the total `count` is defined to include that bucket [54]. We do not claim it as a general sub-resolution indicator, because it is not one: it captures unrepresentable mass only at the bottom of the scale. What it establishes is narrower and still useful — that a mainstream telemetry format already treats rounded-to-zero observations as data to be carried beside the total rather than dropped, which is precisely what the guard of Section IV of the main text does not do.

*A prior sighting in a benchmark, blamed on clocks.:* Klenik and Pataricza report negative derived durations in a Hyperledger Fabric benchmark, call them a serious violation of event causality, and trace them to a peer clock drifting under a lightweight synchronization service [55]. Their case is genuinely two-clock — the durations oscillate smoothly around zero, a drift signature, the same channel as our Redis –1000  $\mu\text{s}$  finding and not Mode A — and their check is post-hoc data validation with no per-run gate and no campaign rate. It is the nearest prior sighting of the observable inside a benchmark, and the attribution went where the field’s default sends it: to the clock.

*The strongest precedent for our own recommendation, in network measurement:* Our rule says to keep the unusable sample and label it rather than delete it, and one system already does exactly that. TimeWeaver infers one-way delays from passively observed NTP traffic, and where earlier methods discarded a host outright for missing timestamps or negative latencies, it keeps those measurements and assigns them to lower accuracy tiers [56]. That is a fourth disposition beyond the three Section IV of the main text finds in benchmark harnesses — not deletion, not substitution, not passing the value on unmarked, but retention with a quality label — and it is the one we would have asked for. It does not compete with this paper: it is network measurement

rather than a benchmark harness, it derives no retention arithmetic, and it reads no harness source. We record it because a reader entitled to ask whether anyone has done the sensible thing deserves the answer, which is yes, in a neighboring field.

It is a precedent for our *first* rule as well as our third, and we had missed that. Making the case for tiers, the paper states what the filter it replaces cost: of the 8,804 clients the prior method considered, about 3,631 — two in five — “were rejected due to missing timestamps, negative latency values, and other reasons”. That is a published rejection rate, which is what Section VI-B of the main text asks a benchmark to report, arrived at in 2018 and for the same reason: a filter’s cost is not visible in what survives it. Two qualifications, so the precedent is not claimed wider than it is. The denominator is clients rather than samples, and the rate is TimeWeaver’s characterization of the prior method rather than of its own tiering, which it reports instead as counts per tier.

#### S40. WHAT STANDARDIZED BENCHMARKS REQUIRE ABOUT RESOLUTION

Section VI-B of the main text asks that a harness state its timestamp resolution and count what it discards. Standardized benchmarking already contains rules of that form, and one of them is almost exactly the rule we propose. Setting them beside the flagship standardized messaging benchmark is the sharpest way to show the gap, so we do that here rather than assert it.

*A rule of the right form, in embedded benchmarking:* EEMBC’s CoreMark-PRO run rules require that “[e]ach workload must run for at least 1000 times the minimum timer resolution” [57]. That is the form of rule this paper argues for: a floor on the measured interval expressed *relative to the instrument*, not in absolute time. The distinction is easy to lose, and worth keeping — plain CoreMark sets an absolute ten-second floor instead, with no reference to resolution at all, and the two rules are not interchangeable.

*A rule about unusable samples, in power measurement:* SPEC’s Power and Performance Methodology, clause 8.2.2, says the benchmark “should report the number of samples that may have a return value ‘Unknown’” and the number whose uncertainty exceeds the maximum allowed [58]. Two qualifications matter and we state them rather than round them off: the modal verb is *should*, in a methodology document rather than run rules, and the samples in question are unusable readings rather than samples excluded after the fact. Within those limits it is the same instinct — publish the count of what the instrument could not measure.

*Rules about the sign itself, in network measurement:* Three standards already require some part of what the main text asks, and they are the closest precedents we found for treating an impossible value as data rather than as debris. OWAMP requires a packet stamped in the future to be recorded unaltered within its timeout window [59]; ETSI requires removed measurement cycles to be reported [60]; and RFC 7679 treats negative singletons as usable distribution data [61]. None of the three is ours and none is applied where a streaming benchmark reports a latency, which is the gap the main text names rather than fills for the first time.

*And none of it, in standardized messaging:* SPECjms2007 is the flagship standardized benchmark for message-oriented middleware. Its run rules record delivery time as a per-destination histogram whose default granularity is 100 ms and whose default upper bound is 10 s [62], [63]. Searching the run rules, design document and user’s guide for a resolution clause, a minimum measurable interval, or a counter of discarded latency samples returns nothing: the only timing-quality requirement anywhere in them is clause 3.2’s bound of 100 ms on *inter-node clock agreement*, which is a skew limit and not a resolution limit. The reported `deliveryTime` element carries an average, a maximum, a granularity and a ninetieth percentile, and no field for samples outside the histogram’s range.

We are careful about one thing here. The user’s guide does document sample discarding elsewhere — `trimInitialSamples` and `trimFinalSamples`, “this many samples are thrown away” — but those apply to throughput histories rather than to delivery-time histograms, and they are configured constants rather than reported counts. It would be wrong to say the benchmark discards nothing; what it does not do is count the latency samples its own resolution makes unusable.

Two tools reached the same precondition independently, and both disclose rather than delete. `zrk`, a rewrite of `wrk2` begun in July 2026, states that at “the sub-millisecond latencies a fast service actually produces” a millisecond artifact “is frequently larger than the number being measured”, and records the overshoot into the sample rather than discarding it [64]. `wrk2` itself concedes in its own documentation that “measured latencies are only accurate to a  $+/- \sim 1$  msec granularity, due to OS sleep time behavior” [65]. Neither counts a discard, because neither discards: the quantum is disclosed and the sample is kept. That is the contrast Section IV turns on.

The comparison is therefore not that standards bodies have failed to think about this. One of them states our rule in almost our words, for a different domain. The rule simply has not reached the place where brokers are compared on sub-millisecond paths.

*The property those rules refer to is itself a measurement:* A floor expressed relative to the instrument presumes the instrument’s resolution is known, and on a general-purpose platform it frequently is not: the granularity a runtime advertises, the granularity it achieves, and the cost of the call that reads it are three different numbers. `TimerMeter` quantifies exactly those properties for the timers a runtime actually exposes [66], which is the measurement a harness must already have made before a rule of CoreMark-PRO’s form can be applied to it. We name it because the rule of Section VI-B has the same precondition:

a harness cannot state its timestamp resolution honestly without having measured it, and the corpus here is a case where the advertised figure would have been the wrong one to state.

#### S41. THE CLASSICAL STATISTICS OF A DISCARDED ZERO

The main text argues that deleting the samples which compute to zero conditions the reported distribution on being positive, and that the retained fraction is therefore part of the measurement. Two classical sources sit close enough to that argument to be named, and both need care in the naming, so we give them the space here rather than compress them into a clause.

*The baseline the guard invalidates:* The GUM gives the standard model for a quantized reading. Clause F.2.2.1, “The resolution of a digital indication”, states that if the resolution is  $\delta x$  then the stimulus “can lie with equal probability anywhere in the interval  $X - \delta x/2$  to  $X + \delta x/2$ ” and is therefore described by “a rectangular probability distribution ... of width  $\delta x$  with variance  $u^2 = (\delta x)^2/12$ ” [67]. That symmetric model is the departure point for this paper: it holds for *retained* readings, and the positivity guard of Section IV of the main text removes one side of the interval, so neither the rectangular shape nor the  $(\delta x)^2/12$  variance survives the filter. Quantization is not the problem; the asymmetry the guard introduces on top of it is. We cite the clause rather than the formula because the same  $(\delta x)^2/12$  appears in F.2.2.2 for hysteresis, and the form alone does not identify the mechanism.

*The oldest statement that discarding zeros is not free:* Pratt [68] showed that discarding zero differences before ranking violates a natural monotonicity requirement: a sample not judged significantly positive can become significantly positive when every observation is decreased. He calls this an anomaly and gives a procedure that avoids it — rank all observations including the zeros, drop only the zeros’ ranks, and refer the statistic to its null distribution conditional on the number of zeros.

Two qualifications keep the analogy honest. First, Pratt *conditions* on the zero count; he does not treat it as evidence of a shift, and he explicitly declines to claim any optimality for the procedure. Our claim about the retention rate is the weaker and more practical one — that the count must be published so a reader can see what the distribution is conditioned on — and it does not need Pratt’s stronger machinery. Second, the reading that makes the parallel exact is not Pratt’s own framing but one he reports from Meier in a remarks section: that a zero arises because “with only our crude measurement, we do not know” the sign a finer measurement would have resolved. That is precisely the sub-quantum sample of Section IV of the main text, and it is a 1959 statement of it; we attribute it where it belongs rather than to Pratt’s main development.

*A second standard already owns the lemma.:* The arithmetic core of the grid — a rate whose ratio to the sampling tick is  $J/M$  in lowest terms visits exactly  $M$  distinct phases — is standardized in ADC metrology. IEEE Std 1241-2010’s sine-wave histogram test requires the record to hold a number of input cycles “relatively prime” to the number of samples (§6.4.1, Eq. (28)); the same standard’s sine-fit clause states the frequency choice as  $f_i = (J/M) f_s$  and names the practice *coherent sampling* (§5.4.1, Eq. (18)) [69]. Both clauses exist for the same reason we choose incommensurate send rates. (The standard’s notation is  $J/M$  where the main text writes  $p/q$ .) As with the counter literature, we claim the consequence under deletion, not the lemma.

*What the guard deletes here, measured:* The three arguments above are about what deletion does in principle. Figure 8 is what it does to this corpus, in three panels. Panel (a) is the control the main text states in prose: over the same 738,730 joined events on the same clock, the acknowledgment-referenced span falls below zero 62,264 times and the send-referenced span never does, so the negatives are a property of which stamp serves as the origin and not of the delivery being timed. Panel (b) puts a millisecond instrument in front of that population. The difference of two truncated stamps lands on 0 or on 1 according only to where the tick boundaries fall, and a guard that admits a sample only when the difference is strictly positive removes 338,242 of 738,730 events — 45.8%, 95% interval 45.4–46.2 resampling runs rather than events — of which 303,468 computed to exactly zero and 34,774 to less. None of it is counted in what such a harness reports. Panel (c) applies the five dispositions the registry of Section S36 found in shipping software to that one measured population: two of them shrink the sample the statistic is computed from and publish no count of what left; two hold the sample count fixed by reporting a value that was never measured; one keeps the data.

One qualification, because the panel invites the stronger reading. Panel (b) is that rule applied to *our* spans, not a record of the external benchmark deleting our events: it says what a millisecond positivity guard would remove from this population. The per-cell retention the main text quotes is the other measurement — what that harness’s own instrumented runs did report — and the two answer different questions.

#### S42. WHICH CLOCKSOURCE, BOUNDED FROM A MEASUREMENT

*Section VI-D states the verdict in one sentence: a read-cost bound admits only two clocksources, and the corpus closes the channel a second time on headroom. Both halves are derived here — the increment the probe saw, what it excludes, and why the send-referenced span’s floor settles the question independently of which clocksource was in use.*

A reviewer asked which clocksource the cloud instances used, because a virtualized guest need not be given a counter that is coherent across its vCPUs, and if ours were not, that would be a rival to the account in Section V. We did not record the field, and the instances have been reclaimed, so it cannot be read back. Our first answer was that we could not say. That




Fig. 8. **What the instrument deletes, beside what it then reports.** (a) At nanosecond resolution the acknowledgment-referenced span goes below zero 62,264 times in 738,730; the send-referenced span, same events and same clock, never does. (b) A millisecond instrument cannot see (a): it differences two truncated stamps, so a sub-millisecond flight lands on 0 or 1 by tick alignment alone, and a positivity guard then deletes 45.8% of the population uncounted. (c) The five dispositions found in shipping software (Section S36), applied to that same population. Every count is emitted from the committed corpus by `scripts/span_histogram.py`.

answer was wrong, and the correction is worth setting out because the method is the same one the rest of the paper uses: a physical constraint deciding what the record-keeping did not.

The platform probe recorded the smallest non-zero increment observable from `clock_gettime(CLOCK_MONOTONIC)` on the machine that produced the reported runs: 90 ns. An increment is observed by reading the clock twice, so that number is an upper bound on the cost of a single read — and read cost separates the four candidate clocksources by more than an order of magnitude.

*acpi\_pm, excluded by arithmetic:* The ACPI power-management timer counts at `PMTMR_TICKS_PER_SEC = 3,579,545 Hz` (`include/linux/acpi_pmtmr.h`), a period of 279 ns. A clock whose tick is 279 ns cannot report an increment of 90 ns, whatever it costs to read. This exclusion needs no timing figures at all.

*hpet, excluded by cost:* HPET is memory-mapped I/O to an off-die chipset timer. The x86 maintainers, in the commit removing it from the vDSO, describe reads as “exceedingly slow (on the order of several microseconds)”; published measurements of a `clock_gettime` call on HPET sit near  $1.2\mu\text{s}$ . We are careful about the ground here: HPET’s own tick, near 70 ns at 14.318 MHz, is *finer* than the observed increment, so granularity does not exclude it and we do not pretend it does. The exclusion rests on read cost alone.

*What remains, and why it answers the question:* That leaves `kvm-clock` or `tsc`, measured at 33–60 ns and 24–29 ns respectively, both comfortably inside the bound. Each carries the guarantee the reviewer asked about, by a different route.

For `kvm-clock` the route is the vDSO. Without vDSO acceleration the same clock costs about 156 ns per call, which the bound excludes; and `arch/x86/kernel/kvmclock.c` sets the vDSO mode only under a condition:

```
if (!(flags & PVCLOCK_TSC_STABLE_BIT))
    return 0;
kvm_clock.vdso_clock_mode = VDSO_CLOCKMODE_PVCLOCK;
```

`PVCLOCK_TSC_STABLE_BIT` is the flag the KVM guest ABI documents as “time measures taken across multiple cpus are guaranteed to be monotonic” [70]. A `kvm-clock` fast enough to fit the bound is therefore one whose hypervisor asserts



cross-vCPU monotonicity.

For `tsc` the route is selection. `kvm-clock` registers at rating 400 and `tsc` at 300, so on a KVM guest `tsc` is chosen only where `kvmclock_init()` demotes `kvm-clock` to 299 — which it does exactly when `CONSTANT_TSC` and `NONSTOP_TSC` are present and `check_tsc_unstable()` is false. Should warp appear later, `tsc_sync.c` reports “Measured %Ld cycles TSC warp between CPUs, turning off TSC clock” and the source is re-rated away.

*What this does not establish:* It identifies the set of clocksources consistent with the measurement, not which one was in use, and it leans on published read costs for hardware we no longer hold. Those costs vary by roughly a factor of two between independent measurements; the margin here is an order of magnitude, which is why the conclusion survives the spread. It is an inference from a measurement rather than a recorded fact, and Section III-A says so. The derivation is `scripts/clocksource_bound.py`, and its tests pin each exclusion to its own ground so that an exclusion firing for the wrong reason cannot reach the right answer by luck.

#### S43. WHY THE ACKNOWLEDGMENT STAMP IS LATE, AND WHY THE BROKER IS NOT THE REASON

In plain terms: the span that inverts is the one whose reference stamp is read only after a thread has been woken, and the corpus shows twice over that this has nothing to do with which broker is running. Section V states the mechanism; this section gives the source lines, the control that separates the candidate causes, the rivals that were considered and dropped, and the parts we could not test.

##### S43.1. Where each stamp is actually taken

Producer and consumer are separate processes on one host, and both read `CLOCK_REALTIME`. Five stamps enter the spans this paper reports, and they are not taken in comparable places. Three of them are producer-side.

- **The send stamp** is read on the calling thread immediately *before* the client is invoked. In `scripts/redis_producer.py` the worker executes `send_ns = now_ns()` and only then calls `r.xadd(...)`.
- **The Redis acknowledgment stamp** is read on that same thread the moment `r.xadd(...)` returns. `xadd` is synchronous: the thread writes the request and blocks in a socket read until the reply arrives. No second thread is involved anywhere.
- **The Kafka acknowledgment stamp** is read, by default, in the client’s I/O thread when the delivery callback fires. `scripts/kafka_producer.py` also offers `--ack-stamp inline`, which stamps on the calling thread once the send future resolves, matching what `xadd` does; it requires `--max-inflight 1`.

The two clients therefore differ in whether a second thread stands between the reply and the clock read. They do not differ in something more basic: in both, the acknowledgment stamp is read only after a thread that was not running has been made runnable and then scheduled.

*The consumer’s two stamps, and the asymmetry between the clients:* The other two are consumer-side, and until this revision neither this section nor any other said where they are taken. That was a gap in an audit whose whole subject is stamp placement: every span the paper reports ends at one of them.

- **The receive stamp**  $t_{\text{recv}}$  is read when the consumer holds the record. In `scripts/kafka_consumer.py` the client is constructed with a `value_deserializer`, so the payload is parsed inside `poll()` and the parse precedes the stamp. In `scripts/redis_consumer.py` the stamp is read first and `json.loads` runs after it.
- **The output stamp**  $t_{\text{out}}$  is read once the record is in hand. It is the next statement under Kafka and is separated from  $t_{\text{recv}}$  by the payload parse under Redis.

So the consumer’s own handling span,  $t_{\text{out}} - t_{\text{recv}}$ , is 281 ns under Kafka and 19,480 ns under Redis — medians over run medians across 5,913 runs, a factor of 69. It never goes negative on any of the 738,730 events, as a chain cannot.

Three consequences, and we state the direction of each because a disclosure without one is an adjective. *First*, the payload parse falls inside  $D = t_{\text{recv}} - t_{\text{send}}$  for Kafka and outside it for Redis, so the transport proxy and  $D$  carry one client’s parse and not the other’s; against Redis’s median delivery of 800  $\mu\text{s}$  that is 2.4%. *Second*, a longer  $D$  produces fewer negative spans, and the broker carrying the extra parse is the one with the *higher* reported rate, so correcting the asymmetry would widen the gap in Table I rather than close it. *Third*, TTI contains both parses and is unaffected, which is one more reason the equivalence in S48 is also stated on TTI.

We could not fix this in the pipeline where it belongs, because it would require re-running a campaign whose machines are released. What the pipeline now does instead is measure it: `recount_spans.py` carries the span as its fifth column, and a gate fails if the two consumers ever stamp in places that differ again without the number moving with them.

##### S43.2. Why one span cannot invert and the other can

The send stamp is taken before the message leaves the process, so  $t_{\text{send}} \rightarrow \text{emit} \rightarrow \text{deliver} \rightarrow t_{\text{recv}}$  is a chain and its ordering holds by construction, however late the stamping thread was: a late thread makes the span longer, never shorter. That is not an empirical claim about our scheduler, it is a property of the order in which the two operations are written, and it is why the send-referenced span is negative on 0 of 738,730 events under either broker.

The acknowledgment stamp has no such guarantee. The broker’s append precedes both the producer’s receipt of the acknowledgment and the consumer’s receipt of the record, but those are two downstream branches with no happens-before between them (Supplement S35.3). Both branch stamps are read after a wakeup, so the error on their difference is two-sided, and the difference goes negative whenever the acknowledgment-side delay exceeds the true interval plus the receive-side delay. The exposure lies in which operand can be late in the shortening direction, and that is fixed by how the span is constructed, not by what is being measured.

### *S43.3. The second thread is not the mechanism*

The harness was built expecting the thread hand-off to be the cause; the comment at `kafka_producer.py` says that Redis “stamps inline on the calling thread the moment XADD returns, and never pays that wait”. The corpus does not bear that out, and the disagreement is informative.

Two committed results bear on it. First, the stamping campaign (`ec3`) ran Kafka under both settings at matched load, and Table XXI is the outcome: moving from `callback` to `inline` lowers Kafka’s median while Redis does not move, shrinking the between-system gap by about a quarter, and a thirty-run replication reproduces it. The hand-off is therefore real, it is worth some tens of microseconds of median inflation, and a comparison that leaves it in place compares two instruments as well as two brokers.

Second, and against the expectation, removing the second thread does not remove the negative spans. Redis, which never has one, inverts on 8.19% of its 370,836 events against Kafka’s 8.67% of 367,894; by runs affected Redis is the worse of the two (88% of runs against 65%). A thread returning from a blocking socket read must also be made runnable and then scheduled before it can call the clock, and that wait is charged to the measurement exactly as a callback dispatch would be. What the two clients share is the wakeup; the hand-off is an increment on top of it, not the thing itself.

*What we could not test:* The clean form of this control would be the negative-span rate for Kafka under `--ack-stamp inline`, compared with the same runs under `callback`. The stamping campaign retained only its median summary (`docs/results/model/ec3_stamping.csv`); the per-event records that would carry sign-separated counts were not kept, and we do not reconstruct them here. The cross-broker contrast above is the evidence we have, and it is weaker than the within-broker one would have been.

### *S43.4. Two rivals: the scheduler itself, and the hypervisor*

Neither the operating system nor virtualization is the explanation, and it is worth saying why in each case.

The scheduler is not malfunctioning. A base slice with a wakeup-preemption check is a throughput and fairness trade-off, and the arithmetic of Section V-D is the kernel maintainers’ own. A general-purpose scheduler that guaranteed sub-hundred-microsecond wakeup latency to every thread would be a worse general-purpose scheduler, which is why the escapes from it are opt-in: real-time priority, a preemption-free build, or a pinned busy-polling core. The kernel also already publishes the repair — `SO_TIMESTAMPING` returns the time the packet arrived rather than the time a thread got round to asking — and none of the instruments we audited uses it.

Virtualization is not necessary either, and our own numbers point the other way. The workstation testbed runs the brokers in containers with no hypervisor beneath them and the audit rejects 62.4% of its assessed runs, against 51.9% on the cloud instances. The effect is larger where there is no hypervisor at all. Two further observations disagree with a steal-time account: real-time priority is a guest-side control and collapses the rate 39–54× (these two matched pairs; all 8 are in S47, and Section V-B of the main text gives 7–80× across the load sweep), which stolen vCPU time would not yield to; and the 2–4 ms mode sits on the guest kernel’s own base-slice arithmetic rather than on any quantity the hypervisor exposes. Steal time may still contribute on the cloud instances, where the mechanism campaigns were run; what the workstation shows is that it is not required.

*A third rival, inside the interpreter:* The two rivals above are the ones a reader expects. A third is specific to how this harness is built, and the manuscript owes it a paragraph because the mechanism was restated around a thread reaching a CPU.

The stamping threads are CPython (Section III), and both producers are multithreaded: `redis_producer.py` dispatches sends through a thread pool and runs a correction worker beside it. CPython releases the interpreter lock around blocking I/O and takes it back on return, and `now_ns()` is a Python call. So the sequence is not “reply arrives, thread scheduled, clock read” but “reply arrives, thread scheduled, *lock reacquired*, clock read”. The extra wait is bounded by the interpreter’s switch interval, which our campaigns left at the default and none of them recorded; the platform probe now records it, and `interpreter_serialisation()` is part of every future run’s provenance.

Three things follow, and we state them because two of them are uncomfortable. First, the traced estimator cannot see this term: `runqlat` measures `sched_wakeup` to `sched_switch`, and lock acquisition happens after the switch, in userspace. Second, the priority manipulation does not cleanly separate it, because a thread raised to `SCHED_FIFO` also reaches the acquisition queue sooner. Third, magnitude does not separate them either: the default switch interval and the base slice of Section V-D are both of millisecond order, so neither mechanism is excluded by the size of the delay it would produce. Note

what the first point costs us here — the main text’s stall spectrum cannot adjudicate between them, because it is built from the tracepoints that miss one of the two entirely.

What settles it is the direction of the disagreement rather than any of those. If a second serialization sat in series with the run-queue wait, an estimator built from the run-queue wait alone would fall systematically *short* of the observed negative-span rate. Over 3 arms it does not: the ratios are 0.78, 1.06, 1.32, straddling unity, with the largest above it. A term big enough to matter would have to hide inside a spread that already brackets the answer. The interpreter lock is therefore present in principle, bounded in practice, and not the mechanism — and the send-referenced span is immune to it entirely, since a stamp taken before the action bounds its event whatever the interpreter is doing.

#### S43.5. Why averaging does not repair either mode

For Mode B the natural objection is that quantization error falls both sides of the truth, so averaging should recover it. That is exactly right, and it is why the deletion matters: the readings that straddle are the estimator, and HP AN 162-1 makes the point in 1970. But the correspondence stops one step further on, and the paper’s concession to that note should not be read as covering the case here. A counter measures a *constant* interval, and which side of a tick a reading falls on is decided by phase, which is independent of the measurand. Our retention is  $\min(1, T_{\text{true}}/\tau)$ , a function of the *measurand*: the faster the delivery, the likelier it is deleted. The surviving population is therefore selected on the quantity being estimated, which a fixed interval cannot be, and averaging over the survivors does not converge on the truth however many are taken. It also cannot produce a percentile at all, and a latency benchmark reports percentiles.

The consequence is worth stating in its own right. For a sub-quantum path every survivor reads exactly one tick, so the reported median is pinned at  $\tau$  while the truth is  $T_{\text{true}}$ , and the overstatement is  $\tau/T_{\text{true}}$ , the reciprocal of the retention. A tool of this design penalizes the paths that are fastest, and by the largest factor exactly where it deletes the most.

For Mode A averaging is worse than unhelpful. The error is not symmetric noise but a one-sided lateness on one operand, so it does not cancel; and nothing in the path carries what would be needed to remove it afterwards. The reply does not report when it arrived, the thread cannot know how long it was not running, and the only clock reading in existence is the late one. This is not a bias that can be subtracted but information destroyed at the moment of observation, which is why finer clocks, better synchronization and larger samples all leave it untouched.

What does work follows from that. Stamp before the action rather than on resumption, so the reading bounds its event. Where the event is not yours to stamp, attach the stamp to it — a kernel or hardware receive timestamp, or a broker-assigned one — which is the probe-placement argument in Section VI-B. Keep a sub-quantum sample as a left-censored observation, since “ $T_{\text{true}} < \tau$ ” is a fact about the measurand and deleting it discards the censoring indicator along with the value. And treat a negative as a gate rather than a datum: it is not a censored observation but the reference stamp failing, so it belongs in a sign-separated count and in a run-level rejection, never averaged into a distribution.

#### S43.6. The redesign that does not help

A reader who accepts the mechanism usually proposes the same fix: have the consumer acknowledge back to the producer, so that one clock times a round trip and the two-clock problem disappears. It is the right instinct and it does remove skew, but it does not remove this failure, for two separate reasons.

The first is that it measures the wrong quantity. A producer-side round trip is not the staleness of a record at the consumer, and staleness at the consumer is what a streaming pipeline is judged on. Substituting the one for the other answers an easier question than the one asked.

The second is that the stall does not care how many clocks are involved. Every negative in this corpus was produced on a single clock, and the arm in which both processes read that one clock is the arm the audit rejects most, at 62.4%. A round trip still ends with a thread being woken and scheduled before it can read the clock, so it inherits the same late reference stamp the acknowledgment span has. Collapsing two clocks into one removes a term the corpus already shows is not the cause.

#### S43.7. Where the repairs belong

No layer here misbehaves, which is why the fix is not obvious from inside any one of them. The kernel schedules as designed, the clients return as soon as they can, the brokers acknowledge correctly. The benchmark is the only party that assumes something none of them promised: that observing an event tells you when the event happened.

- **Operating system:** nothing is owed. The escape hatches and `SO_TIMESTAMPING` already exist.
- **Kafka:** `record.timestamp()` is a millisecond wire field, so anything built on it inherits a millisecond quantum and must carry its own finer stamp in the payload to escape. Documenting that, or exposing a finer causally attached stamp, is the ask.
- **Redis:** the `XADD` entry identifier embeds a server-clock, millisecond-floored time. One documented sentence saying it is not comparable with a client clock would have prevented the driver defect of Section VI-A outright.
- **Benchmark authors:** stamp before the action; count discards sign-separated; publish retention, timestamp resolution and synchronization state; never difference a server-assigned stamp against a client clock without saying so; dither the send instant; and record the achieved rate.

## S44. THE SCHEDULER CONSTANTS, DERIVED

The main text states the base slice and moves on; this is where it comes from. The constants are *derived* from the published kernel package and the campaign’s own data rather than measured, which is weaker evidence than a measurement and is reported as such.

The core count is recovered from the experiment rather than assumed: each geometry condition loads  $k$  cores and records the achieved utilization, so  $k/\rho$  recovers 8 six times over with a spread of 0.05. The kernel’s own rule then gives the base slice,  $4 \times 0.75 \text{ ms} = 3 \text{ ms}$  — the maintainers’ arithmetic, “0.75 msec \* (1 + ilog(ncpus)) ... 3.00 for 8 cpus and above” [71]. It is specific to this kernel: the constant became 0.70 ms in v6.15, after our 6.8. The build sets `CONFIG_HZ=1000`, a 1 ms tick.

With run-to-parity a woken thread that loses the wakeup-preemption check waits for the incumbent to exhaust that slice, and the expiry is noticed at the tick. That tick is also why the mode is a band and not a spike: the same posting notes a task “can only wait until the next tick to consider that it has reached its deadline, and will run 1ms longer”.

No scheduler tunable is written anywhere in the archived campaign, which is why the derived value is the one that applied. It is strong evidence rather than proof.

## S45. THE METRIC MAP (MOVED FROM THE MAIN TEXT)

This section says which interval each reported quantity actually covers. The drawing is the main text’s Figure 1, which names the four bracketing stamps; what belongs here is the mapping from those stamps onto the metric names, because a reader comparing our numbers against another harness’s needs to know what was subtracted from what.

*Scheduling lag* is  $t_{\text{send}} - t_{\text{sched}}$ . Both stamps are taken inside the producer process, so it is a causal chain and cannot invert. *Acknowledgment lag*,  $A = t_{\text{ack}} - t_{\text{send}}$ , is also producer-internal and also cannot. *Broker transport* is the transport proxy  $S = t_{\text{recv}} - t_{\text{ack}}$ : it subtracts a producer-process stamp from a consumer-process one, which is exactly why it can come out negative when either process is delayed, and it is the span this paper is about. *End-to-end TTI* is  $t_{\text{recv}} - t_{\text{sched}}$ , the sum of the three (Equation 1), and it inverts only if the whole flight does. A fifth stamp,  $t_{\text{out}}$ , is consumer-internal and is not drawn in that figure; S43.1 places it.

## S46. GRID MEMBERSHIP, ARM BY ARM (MOVED FROM THE MAIN TEXT)

The main text’s figure makes the claim about the set; this is the same twelve arms one row at a time, for a reader checking an individual rate. Table XXV is generated from `grid_membership.csv` at build time by the same helper that produces the figure, so the two cannot disagree.

TABLE XXV

**GRID MEMBERSHIP AGAINST A CONTINUUM NULL.**  $D$  IS THE MEAN NORMALIZED DISTANCE TO THE NEAREST GRID VERTEX; UNDER THE NULL ITS EXPECTATION IS THE VALUE IN THE *null* COLUMN. THAT COLUMN WAS, UNTIL THIS REVISION, THE DISTANCE OF  $\theta$  FROM ITS NEAREST VERTEX WITH NO REPLICATE NOISE — THE DISTANCE OF THE EXPECTATION RATHER THAN THE EXPECTATION OF THE DISTANCE, WHICH ARE NOT THE SAME NUMBER AND DIFFERED BY UP TO 0.04 HERE. IT IS NOW THE MEAN OF THE SIMULATED NULL ITSELF, SO THE SENTENCE ABOVE IT IS TRUE.  $p_{\text{Holm}}$  IS A MONTE CARLO  $p$ -VALUE (4,000 DRAWS) AFTER HOLM CORRECTION WITHIN THE FAMILY OF ALL 12 ARMS; THE CORRECTED VALUE IS WHAT DECIDES THE VERDICT. ARMS MARKED *flat (coincident)* ARE THOSE THE MODEL PREDICTS FLAT, WHERE THE TWO HYPOTHESES MAKE THE SAME PREDICTION AND THE TEST HAS NO POWER. THE 700 AND 1250 MSG/S ROWS ARE THE TWO THAT THE SPREAD RULE OF TABLE IX MISSES; THIS TEST RESOLVES BOTH, WHICH IS WHY IT REPLACED THAT RULE.

| rate   | $p/q$ | $n$ | $D$   | null  | $p_{\text{Holm}}$ | verdict           |
|--------|-------|-----|-------|-------|-------------------|-------------------|
| 1250/s | 4/5   | 5   | 0.131 | 0.351 | 0.003             | grid              |
| 1000/s | 1/1   | 5   | 0.003 | 0.479 | 0.003             | grid              |
| 900/s  | 10/9  | 5   | 0.265 | 0.340 | 0.131             | not resolved      |
| 875/s  | 8/7   | 5   | 0.209 | 0.382 | 0.003             | grid              |
| 800/s  | 5/4   | 5   | 0.104 | 0.058 | 1.000             | flat (coincident) |
| 700/s  | 10/7  | 5   | 0.329 | 0.416 | 0.009             | grid              |
| 625/s  | 8/5   | 10  | 0.112 | 0.447 | 0.003             | grid              |
| 600/s  | 5/3   | 6   | 0.034 | 0.469 | 0.003             | grid              |
| 500/s  | 2/1   | 5   | 0.043 | 0.490 | 0.003             | grid              |
| 400/s  | 5/2   | 5   | 0.093 | 0.020 | 1.000             | flat (coincident) |
| 300/s  | 10/3  | 10  | 0.221 | 0.468 | 0.003             | grid              |
| 250/s  | 4/1   | 5   | 0.181 | 0.489 | 0.003             | grid              |

## S47. EVERY REAL-TIME-PRIORITY PAIR, AND THE LADDER THEY MAKE

The main text quotes a range: real-time priority on the stamping threads collapses the negative-span rate 7–80× at fixed utilization. That range is taken over 8 matched pairs from three campaigns, and until this revision only the two of Table XV appeared anywhere — which left the two pairs that anchor the range, including the weakest result in the series, visible nowhere. Both are below.

Table XXVI is generated from docs/results/model/stamping\_priority\*.csv at build time, so the range in the abstract and the rows here cannot disagree. E-A5 is the original manipulation, E-A5b widened the load ladder to 60 and 95%, and E-A7 replicated E-A5. Every pair has disjoint Wilson intervals, and 0 were withheld for a failed manipulation check — the design assumes real-time priority leaves  $\rho$  alone, so  $\rho$  is measured in both arms and a discrepancy above 0.05 withholds the pair rather than reporting it hedged. Naming the threshold matters more than the count it produced: a withholding rule whose criterion is invisible cannot be checked, and this one never fired because it never came close. The widest disagreement any pair showed was 0.002, some 25 times inside the tolerance, so the zero above is a clean manipulation rather than a loose test.

TABLE XXVI

**EVERY MATCHED PAIR.** ORDINARY AND REAL-TIME NEGATIVE-SPAN RATES AT THE SAME ACHIEVED UTILIZATION, AND THE FACTOR BETWEEN THEM. BOTH ARMS' ACHIEVED  $\rho$  IS PRINTED, SO THE CLAIM THAT THE MANIPULATION MOVED OCCUPANCY AND NOT LOAD CAN BE CHECKED PAIR BY PAIR RATHER THAN TAKEN FROM A CAPTION: THE WIDEST DISAGREEMENT ANYWHERE IN THE TABLE IS 0.002, AGAINST THE 0.05 THAT WOULD HAVE WITHHELD THE PAIR. GENERATED AT BUILD TIME FROM THE THREE CAMPAIGN FILES.

| campaign | load | $\rho$ ordinary | $\rho$ real-time | ordinary | real-time | factor |
|----------|------|-----------------|------------------|----------|-----------|--------|
| E-A5b    | 60%  | 0.6055          | 0.6035           | 0.0459   | 0.0017    | 27×    |
| E-A5b    | 70%  | 0.7032          | 0.7025           | 0.1032   | 0.0144    | 7×     |
| E-A5     | 75%  | 0.7531          | 0.7525           | 0.1320   | 0.0034    | 39×    |
| E-A7     | 75%  | 0.7550          | 0.7537           | 0.1504   | 0.0044    | 35×    |
| E-A5b    | 88%  | 0.8806          | 0.8809           | 0.2214   | 0.0034    | 66×    |
| E-A5     | 88%  | 0.8809          | 0.8812           | 0.3049   | 0.0057    | 54×    |
| E-A7     | 88%  | 0.8825          | 0.8825           | 0.2526   | 0.0054    | 47×    |
| E-A5b    | 95%  | 0.9501          | 0.9501           | 0.2938   | 0.0037    | 80×    |




Fig. 9. **The same 8 pairs, as a ladder.** Ordinary and real-time negative-span rates with Wilson 95% intervals, one row per pair, ordered by achieved utilization; the factor is printed at the right. Reading down, the real-time arm barely moves while the ordinary arm climbs with load, which is what makes the factor grow. The growth is a trend and not a law — 60% gives 27× and 70% gives 7× — and the range is reported as a range for that reason.

Figure 9 shows what the range does not: which arm moves. The real-time arm sits between 0.0017 and 0.0144 across the whole load ladder, close to the floor the model names in advance; the ordinary arm rises from 0.046 to 0.30. The collapse is therefore not a proportional reduction that happens to be larger under load — it is the ordinary arm following utilization while the manipulated arm does not, which is the two-state model of Equation 6 with  $p$  moved directly.

Two exhibits moved here from the main text when the manuscript was brought back inside twelve pages, and both are restatements rather than evidence, which is why they were the ones to go. Figure 10 draws the four matched pairs of the main text's mechanism table and the two brokers of its span table: no pair of arms overlaps, which is checkable in those tables and is faster to see here. Table XXVII tabulates the exposure curve whose headline points the main text quotes — the relative error  $A/T_{\text{true}}$  against path length, and beside it the gap a comparison would report between two identical systems whose clients stamp in different places. Neither carries a number that is not already stated where it is argued.




Fig. 10. **Every manipulation separates; the broker does not.** Wilson 95% intervals. Above the rule, the four matched pairs of Table II, utilization held fixed within each: what moves the rate is where the stamping thread sits, not how loaded the machine is. Below it, observed rather than manipulated, the two brokers of Table I; their intervals are narrower than the plotted point.

TABLE XXVII

**WHAT THE DISPLACEMENT COSTS AT LONGER PATHS, AND HOW WIDE THE COST IS.** COMPUTED FROM THE MEASURED ACK LAGS, NOT MODELED. LEFT: THE ERROR ON A SINGLE REPORTED LATENCY,  $A/T_{\text{true}}$ , AT THIS CORPUS'S MEDIAN LAG OF  $725 \mu\text{s}$ . MIDDLE: THE SAME ERROR AT THE TENTH AND NINETIETH PERCENTILES OF THAT LAG ACROSS OUR CONDITIONS,  $500$  AND  $1900 \mu\text{s}$ . THE BAND IS THE COLUMN TO READ. A LAG IS NOT A CONSTANT, AND A READER LOCATING THEIR OWN PATH AGAINST THE POINT ESTIMATE ALONE WOULD PUT A  $10 \text{ ms}$  PATH AT  $7\%$  WHEN A TENTH OF OUR OWN CONDITIONS SIT AT  $19\%$ . RIGHT: THE GAP A COMPARISON WOULD REPORT BETWEEN TWO IDENTICAL SYSTEMS WHOSE CLIENTS DIFFER ONLY IN WHERE THE ACKNOWLEDGMENT IS STAMPED — A CALLBACK THREAD AGAINST AN INLINE STAMP. WHERE THE RIGHT-HAND COLUMN READS “INVERTS”, THE APPARENT GAP HAS CHANGED SIGN; ON EVERY ROW BELOW THOSE NOTHING IS NEGATIVE, SO THE SIGN CHECK OF SECTION III-B FIRES ON NONE OF IT.

| True path<br>$T_{\text{true}}$ | Error on one<br>measurement | p10–p90<br>across conditions | Apparent gap between<br>two identical systems |
|--------------------------------|-----------------------------|------------------------------|-----------------------------------------------|
| 0.25 ms                        | 290%                        | 200–760%                     | inverts                                       |
| 0.5 ms                         | 145%                        | 100–380%                     | inverts                                       |
| 1 ms                           | 72%                         | 50–190%                      | inverts                                       |
| 2 ms                           | 36%                         | 25–95%                       | 67%                                           |
| 5 ms                           | 14%                         | 10–38%                       | 22%                                           |
| 10 ms                          | 7%                          | 5–19%                        | 11%                                           |
| 25 ms                          | 3%                          | 2–8%                         | 4%                                            |
| 50 ms                          | 1%                          | 1–4%                         | 2%                                            |
| 100 ms                         | 1%                          | 0–2%                         | 1%                                            |

The rows added below one millisecond are the regime broker benchmarks actually report in (S52), and they are where an acknowledgment-referenced harness stops measuring the path at all. A send-referenced one is unaffected: it reports the delivery itself, which is why the framework audited in S52.2 needs no correction from this table.

*Which estimator produced the two headline ratios, stated because it decides them:* The main text says the reported span is  $24\%$  of the delivery it stands for, understating it  $4.2\times$ . Both are the *median over conditions of median  $S/\text{median } D$*  — a median of per-condition ratios, computed in `emit_paper_numbers.py` and gated there. The estimator is not a detail. Working from the medians this supplement prints, which is the natural recomputation, a reader who differences them condition by condition gets  $3.5\times$ , and one who divides the pooled medians gets  $2.6\times$ . Three defensible readings, a factor of  $1.6$  between the extremes, and only one of them is the number in the text. This project has been caught by the same distinction once before, on the independence overshoot of Section VI-B, where median-of-ratios and ratio-of-medians differ by  $12.4\times$  against  $21.3\times$ ; there it is stated in the sentence that quotes it, and now it is stated here too.

#### S48. WHAT THE BROKERS ACTUALLY DO (MOVED FROM THE MAIN TEXT)

The main text states two conclusions and points here for the evidence: that the broker comparison is not a purchasing argument, and that one configuration choice, invisible on the standard testbed, decides the outcome. This is the campaign behind both. It sits in the supplement because the paper's contribution is two measurement failures, and what the brokers do is a smaller result than either — smaller, in the end, than the comparison that motivated the work was expected to be.

##### S48.1. Equivalence on gated artifacts

Over the runs the sign check leaves standing, the brokers sit within a millisecond of each other on the transport proxy: a Hodges–Lehmann shift of  $0.408 \text{ ms}$  (90% interval  $0.389\text{--}0.419$ ), with TOST rejecting both one-sided nulls against a  $1 \text{ ms}$

margin at  $p < 0.001$ , holding between 0.408–0.417 ms across 3 concurrency levels.

That span is not a causal chain, so the equivalence is stated on the quantity that is: TTI is equivalent over the same levels against a wider margin (S6). Equivalence is claimed rather than assumed from a failure to reject, which is the reason for the TOST rather than a two-sample test.

#### *S48.2. The condition that reverses the ordering*

One-way delay injected identically at both leaves Kafka tracking it almost additively, while Redis collapses: a median transport of 4.6 s at 5 ms of injected delay, 31.3 s at 20 ms and 102.5 s at 50 ms, over five feeds per arm. That is 900 to 2,050 times the delay applied.

The cause is the consumption pattern rather than the broker. A per-message acknowledgment turns each event into a sequential round trip, so injected delay multiplies once per event, where a prefetching consumer serves from buffer and pays it once per batch.

#### *S48.3. The falsifier, registered in advance*

The prediction was recorded before the run: if the acknowledgment pattern is the cause, then batching the acknowledgments must remove most of the effect without touching the broker, the network or the injected delay. Batching them two hundred at a time cuts the median from 4,138 ms to 103 ms, a factor of 40, replicated four times.

#### *S48.4. Why the standard testbed cannot see it*

Both settings are invisible on a co-located testbed: the round trip they multiply is a few hundred microseconds there, so the difference between paying it once per event and once per batch is below the noise. The choice that decides the outcome under any realistic separation is therefore not visible in the environment most comparisons are run in — which is the same shape of failure as the two the paper is about, an instrument whose configuration determines the result while nothing in the output records it.

### S49. THE STATISTICAL INVENTORY (MOVED FROM THE MAIN TEXT)

Section III-D keeps the choices a reader might contest — Wilson over Wald, Holm within a named family, and why a tail index on interval-censored buckets is not a slope. This is the rest of the inventory, so that every interval in either document has a named method behind it.

Every ratio between two proportions carries a two-proportion  $z$  with pooled variance, and we state whether the intervals are disjoint. Location differences use Hodges–Lehmann shifts with distribution-free intervals and rank-sum tests; equivalence claims use TOST with the margin stated and the interval printed; Holm correction is applied within a named family, and the corrected value is the one the tables display; percentile bootstrap intervals cover statistics with no closed form. The grid-membership inference uses a permutation null, described where it is used. Regression intervals are Student- $t$  at  $n - 2$  degrees of freedom. Tail indices are estimated on the traced histogram by grouped maximum likelihood with a profile-likelihood interval and by an exceedance ratio with a Wilson interval, because the buckets are interval-censored and a slope through survival points is not an estimator; the grouped estimator on log-spaced bins is Virkar and Clauset’s, which is the Hill estimator for binned data, and we use their bootstrap for goodness of fit [72].

All interval arithmetic is recomputed from the committed artifacts at build time by the same code that emits the numbers into the text, so no figure in either document is transcribed.

### S50. THE CONCURRENT NEGATIVE-SPAN REPORT, AND WHERE THE READINGS PART (MOVED FROM THE MAIN TEXT)

Section II-B states the disagreement in three sentences. This is the whole of it, because a dispute with concurrent work should be checkable rather than asserted.

Sharma et al. [24] count negative timing spans in distributed inference systems and propose a `causality_health` check. Injecting skew, they observe no violations up to 3 ms and clear ones by 5 ms, and read that as a skew threshold. Their measurements we do not dispute; the reading we do, on one sentence: “queueing alone cannot produce negative timing spans”.

Under the queue they model — backlog at a service stage — the sentence is true, and Section V refutes that account of our own corpus as well. It is false as written because two different queues are in play and only one of them is theirs. A message waits in a service backlog; the thread that stamps the clock waits in the kernel’s *run queue* for a CPU. The second wait is what displaces a stamp, and it is unaffected by whether any backlog exists: our rates are highest at high utilization with no backlog at all.

The consequence is practical. If backlog cannot invert a span, then eliminating backlog leaves skew as the only explanation, and a millisecond threshold on skew becomes a sufficient check. On a loaded machine it is not: we see negative-span rates near 23% at 88% utilization on a single host — where the inter-host offset is not merely small but undefined, there being one clock — and move that rate fiftyfold with a scheduling parameter, touching no clock.




Fig. 11. **Why a sample disappears, and why the survivors are not a sample.** (a) One delivery of  $T_{\text{true}} = 0.35$  ms at four phases of one tick. Three finish inside it, so both stamps round alike, the difference is exactly zero, and the guard removes them; the fourth crosses the boundary and is recorded as one whole tick — which is why the corpus prints 1.0 and 2.0 ms and nothing between. (b) A delivery survives from phase  $\tau - T_{\text{true}}$  onward — the shaded band — so uniform phases retain  $T_{\text{true}}/\tau$  (Equation 4); a commensurate producer visits only  $q$  and retains a count out of  $q$ , one of the values Equation 5 allows.  $T_{\text{true}}$  here is illustrative and off-vertex by choice: at 0.5 ms the two answers coincide.

Their own formulation is nearer ours than the dichotomy allows. They note that the minimum separation “exhibits variability due to scheduling jitter”, with violation probability rising as  $\epsilon$  exceeds its quantiles. That is the negative-span law of Section III-C with skew written where we write the stall — the same law, attributed to the other term. What a threshold in milliseconds of skew cannot do is transfer to a machine where the stall, not the skew, is the term that grows.

#### S51. THE 1970 COUNTER NOTE, LINE BY LINE (MOVED FROM THE MAIN TEXT)

Figure 11 draws the identity this section traces: one delivery at four phases of a tick, three of them rounding to a difference of zero and deleted, and beneath it the phase diagram that decides how many of a run’s sends survive.

Section II-C concedes the arithmetic of Mode B to Hewlett-Packard’s Application Note 162-1 [73] and states what remains ours. This is the correspondence in full, so the concession can be checked rather than taken on trust.

- **The retention identity.** For an interval of  $Q + F$  clock periods, AN 162-1 gives  $\Pr[R = Q+1] = F$ : the fraction of readings landing on the upper of the two straddling counts is the fractional part itself. That is the retention law of Section IV.
- **The class of a repetition rate.** Its *class* is the denominator of the ratio of repetition rate to clock rate in lowest terms, under the same co-prime condition that fixes our  $q$ , and it determines how many distinct readings the counter can produce.
- **The ceiling on averaging.** The gain in resolution available from averaging  $N$  readings is bounded by a factor  $1/q$  and not by  $1/\sqrt{N}$ , which is the quantization ceiling of Section IV-B. AN 162-1 names  $q = 1$  as the corner where averaging cannot help at all — the case a paced producer on a round interval walks straight into.
- **The symptom.** It tells the operator what to look for: a counter reading that appears to hang on a round number while the input is known to vary.
- **The cure.** Phase jitter on the repetition rate, so the samples stop landing on the same points of the clock’s cycle. We arrived at it independently and recommend it in Section VI-B.

The one thing the note does not contain is the failure this paper reports, because its instrument keeps both readings. Retention is the estimator there; deleting the population that carries the fractional part is what converts a solved metrology problem back into an open one.

*When dither works, which is a question with an answer:* Our remedy is to dither the send instant, and a reader from signal processing will ask under what conditions dither actually recovers the underlying quantity. It is a fair question and the



literature has answered it. For quantized Gaussian measurements subtractive dither helps when the ratio of the noise’s standard deviation to the quantization interval is roughly *below* one third; above that it costs more than it buys [74]. The condition is one-sided. Their second threshold does have a lower bound, but it decides which *estimator* wins inside that regime rather than whether dither helps at all, and we do not lean on it. We name the result rather than apply it, because our dither is not that dither. Theirs adds noise to the *value* being quantized; ours randomizes the *phase* of the sampling instant against the tick, which is RFC 3432’s construction [75] and is what breaks the commensurability of Section IV-B. The two coincide only in the uniform-phase limit that Equation 4 already assumes. The neighboring result is worth the reader’s attention anyway: it is the closest thing to a proof that the recommendation has a domain of validity rather than being folklore.

## S52. TWO LITERATURES THE PAPER STANDS AGAINST (MOVED FROM THE MAIN TEXT)

Section II-B and Section II-C state what this paper takes from each of these and what it adds. This is the survey behind those sentences.

### S52.1. *Production tracing reached the conclusion without the mechanism*

The observable is familiar outside benchmarking. Distributed tracing systems ship clock-skew adjusters, which “modif[y] start time and log timestamps for spans that appear to be ‘off’ with respect to the parent span” [76]. An issue titled *Clock Skew Adjuster considered harmful* objected that the result is “wrong data and really hard to diagnose” [77], and Jaeger has defaulted the adjustment off since 2020.

A 2026 preprint reaches Villain’s conclusion again on current hardware, pairing an edge inference runtime’s own timing against a logic-analyzer reference and finding that deployment interference corrupts the timing infrastructure as well as the timing it reports [78]. It reports no negative spans, no quantized deletion and no law relating either to the interval measured; what it confirms is the premise, fourteen years after Villain and in another domain.

That is our conclusion, reached by practitioners, from the symptom alone. What the argument lacked was a mechanism and a magnitude: if the displacement is a late stamp rather than a skewed clock, then an adjuster is not correcting error but moving evidence, and how much evidence it moves is a measurable quantity nobody had measured. Section V measures it.

### S52.2. *A framework that does not have the problem*

Section VI-B claims the rules above are practical rather than aspirational, and the strongest evidence for that is not ours. In March 2026 Paul et al. published mq-bench, a framework for exactly the comparisons this paper is about, and evaluated eight brokers with it [79]. Its measurement design makes five of the choices we recommend, and argues for none of them:

- **Native resolution.** “Each message includes a 24-byte binary header containing a 64-bit send timestamp in UNIX nanoseconds.” There is no millisecond quantum, so the deletion law of Section IV has nothing to bind on.
- **A span that is a causal chain.** It computes  $t_{\text{recv}} - t_{\text{send}}$ , which is the span the main text’s span table shows never inverts, rather than the acknowledgment-referenced proxy that does.
- **One clock.** “Clock synchronization between publisher and subscriber processes is ensured by running both on the same workload generator machine.”
- **No guard.** We looked for a positivity filter, a clamp or a discard rule and found none.
- **A published loss fraction.** Its reliability experiment injects TCP resets and reports what did not arrive: “all brokers exhibit approximately 6.3–6.6% message loss” at QoS 0, or 1,150–1,200 of 18,200 messages, against 0% at QoS 1 and 2.

mq-bench then reports medians as low as 0.21 ms — squarely inside the range where both failures reported here bite — and needs no remedy, because it never acquired either defect.

The last of those bullets is the one we did not expect to find. Our rule asks for the retained fraction to be published beside the latency, and here it is, in a framework that never argues for the practice: the loss is induced rather than spontaneous, but the reporting is the point. Their first two experiments run at QoS 0, which is at-most-once and has no redelivery, so the headline latencies are drawn from a configuration that can silently drop — and the third experiment is what tells a reader how much. That is the shape the rule asks for, arrived at independently.

One thing it does not do is say why its span is safe. A reader cannot tell from the paper whether the send-referenced difference was chosen because it is a causal chain or because it was the convenient one to instrument, and that is exactly what the rule “name the span you are subtracting” asks an author to make explicit. The choice is right either way; the record of why is what would let the next framework inherit it.

### S52.3. *How large the literature is that misses this*

A 2025 preprint synthesizes 42 peer-reviewed Kafka studies published between 2015 and 2025 and reports evaluation rigor, configuration disclosure and reproducibility inconsistent across them [5]. It finds neither of the failures reported here. The size matters for the same reason the audit of Section IV-D does: the instruments are few and shared, so a defect in one is a defect in a decade of comparisons rather than in one project.

The adjacent literatures are alive to benchmarking pitfalls without reaching this one. Fruth et al. catalogue the perils of database benchmarking [80], Zhang et al. attribute tail latency to its sources through precise load testing [81], and the scheduling-latency literature has compared measurement approaches across kernels for over a decade [82]. Each takes the instrument’s own reading as given. That is not a criticism of any of them — it is the assumption this paper is about, and its being shared is the reason the omission survives.

*Three 2026 data points, two of them inside the regime:* The main text concedes that most published comparisons report a median above the quantum, where the deletion law does not bind. That concession stands, and it is worth recording that it is not universal. A 2026 practitioner comparison of NATS, Redis and Kafka gives Kafka “sub-10ms latency at p99” and gives the other two no percentile at all: Redis has “sub-millisecond response times” and NATS “sub-millisecond latency”, with “microsecond-level message delivery” [83]. That is the sharper exhibit, and not because the numbers are small. A ranking that names a percentile for one system and not for the other two cannot be read at all in this regime: sub-millisecond *somewhere* in the distribution is consistent with a median on the quantum and with a median well above it, and those two have retained fractions that differ by orders of magnitude. The comparison reports no retained fraction, no rejection count, no timestamp resolution and no send rate, so nothing in it distinguishes the two cases. It is the clearest current instance of a published ranking produced inside the regime this paper is about.

A second 2026 comparison closes that gap from the other side. It ranks Kafka, Redis Streams and NATS on end-to-end p99 and gives Redis Streams 0.8 ms — a percentile, named, and below the tick — against 3.2 and 12.5 ms [84]. The measurement is across a three-node cluster, so two clocks, and the method is one line about the node shape: no tool, no timestamp source, no synchronization statement, no resolution, no discard count. Unlike the ranking above, this one *can* be placed against the quantum, and it lands under it. We draw no conclusion about the number, which may be perfectly good; the point is that nothing published beside it would let a reader tell, and on a millisecond-resolution cross-node stamp most of that distribution would compute to zero or to a negative a positivity guard would drop.

Against that, the rules of Section VI-B are being adopted independently, and by a benchmark rather than by a metrics agent. A 2026 voice-agent latency methodology records both endpoints *on one clock* — a dual-channel recording, chosen because “a platform measures from where it stands, and the caller is not standing there” — publishes its discard counts per platform and per reason so that “the denominator is auditable”, and declines to claim differences below its detector’s resolution [85]. That is the one-clock rule, the retention rule and the resolution rule, arrived at in another domain by people who had not read this paper. We cite it as corroboration that the rules cost little, not as evidence for any claim of ours.

The load-generator half has an older precedent, and a closer one. Section III-A says the achieved rate is recorded per run because the self-validation SPEC and TPC ask for applies to the instrument as well as to the system under test. Klenik and Kocsis did exactly that in 2021, porting TPC-C to Hyperledger Fabric [86]: they instrument their own workers for what they call the scheduling precision reserve — the gap between when a transaction is picked and when it must be submitted — publish it against terminal count, and report that it “can drop below zero in the case of hundreds of terminals”. What they then do with that negative is the part worth copying. They do not clamp it and they do not drop it; they weigh it against the timescale of the thing being measured, observing that the violation “never exceeds half a second” where TPC-C’s constraints “are in the order of magnitude of seconds”, and conclude it is tolerable *here*. That is this paper’s own question — is the instrument’s timescale smaller than the flight? — asked about a load generator, answered in the open, and four years earlier. They publish their invalidated fraction as well.

*The sharpest exhibit for the gap is a tutorial on exactly this subject:* If the omission were confined to benchmarks under deadline it would be a smaller claim. It is not. A 2026 tutorial on statistical evaluation for computer-systems papers devotes a section to *latency-specific pitfalls*, opens it with “latency data is the most common metric in systems papers and the most consistently mis-reported”, and names three traps: the mean as a summary, coordinated omission, and warmup effects [87]. The instrument’s own clock is not among them. Over thirty-one pages the words *timestamp*, *resolution*, *quantization* and *retention* do not occur; *clock* occurs once, about non-determinism under seeding. Its pre-submission checklist asks for “median + tail percentiles + CDF; warmup discarded” and for no denominator, no resolution and no sign check.

The industrial half of that exhibit is a vendor’s own fairness guide. A May 2026 Kafka benchmarking methodology, written expressly to say how to run a comparison that is fair, covers workload profile, hardware normalization, the durability contract and failure scenarios, and says nothing about discarded samples, negative values, timestamp resolution or the send rate’s relation to the clock tick [88]. Its entire treatment of the subject is the phrase “with outlier handling described” — the unfalsifiable gesture the rules of Section VI-B exist to replace with a number. A tutorial and a vendor guide, four months apart, omitting the same thing is a stronger statement about the field than either alone.

A third document closes the set, and it is the one that should have caught this. In July 2026 a broker-monitoring vendor published a methodology guide whose central section is *The Seven Performance Benchmarking Errors* [89] — not advice on running a benchmark, but an enumeration of the ways one goes wrong. The seven are co-locating the load generator with the broker, skipping JVM warmup, measuring only throughput, not running long enough, unrepresentative message sizes, triggering producer flow control, and not matching production configuration. Every one is about experimental design; none reaches the instrument. The words *clock*, *timestamp*, *resolution* and *negative* do not occur on the page. We note without irony that its first

error is co-locating the load generator, while Section VI-A finds that a co-located testbed *hides* the condition deciding the outcome: the two are different concerns, resource contention against exposure, and the guide is right about its own.

We record all three without complaint about their authors, who are doing something else and doing it well. The point is narrower and harder to argue with than any count of benchmarks: a document written in 2026 to enumerate the ways latency measurement goes wrong does not contain the ways this paper reports, which is what it means for a gap to be a gap.

#### S52.4. Where scheduling delay comes from, and what the queueing account gets right

A thread that is runnable does not always run. Work-conservation violations — a runnable thread left waiting while a core sits idle — are documented for CFS-era schedulers [23]; ours is an EEVDF-era kernel, and we make no claim that those particular defects are present.

Queueing gives the leading-order account of waiting, and it is right about the thing that matters here: utilization alone does not fix a waiting time, because pooling and geometry matter at fixed  $\rho$ . This is why the geometry contrast of Section V refutes a single-parameter law rather than queueing itself — a distinction we drew only after a referee pressed on it, since multi-server queueing is geometry-dependent at fixed  $\rho$  whether or not the scheduler conserves work.

Chandrasekar and Kramberger [90] apply exactly such a single-parameter M/G/1 framing to benchmark bias. We adopt it as a leading-order account and refute it on the load axis. On a second axis they reach half of our mechanism concurrently and independently: their client’s own interpreter lock “artificially inflates” the latencies it reports, charging the instrument’s own scheduling to the server under test. That is the inflation half. What a positive number cannot show — the negative span, and the sign channel that makes the displacement legible — is what remains ours.

Tail behavior under load [21] is the phenomenon our stall distribution samples. That work also shows real-time priority collapsing a tail that renicing leaves alone, applied to the system under test; we apply the same lever to the instrument, which is the manipulation of Section V.

#### S53. THE TWO FLOORED CLOCKS BEHIND THE $-1000\mu\text{s}$ SIGNATURE (MOVED FROM THE MAIN TEXT)

Section IV-D states the signature and what it rules out. This is why the two drivers differ, which is a property of the harness rather than of either broker.

The Redis driver takes its publish timestamp from `entry.getID().getTime()` in `RedisBenchmarkConsumer.java:72` — the stream-entry identifier the *Redis server* assigns on `XADD` [19]. The Kafka driver uses a producer-set stamp. So the Redis end-to-end span subtracts a consumer-side wall clock from a server-side one, across two hosts, with both floored to the millisecond; the Kafka span floors two stamps whose difference is taken inside one JVM.

Two consequences follow, and together they are what makes the sign channel legible.

First, the arithmetic admits exactly one negative value. Two clocks floored to the same quantum, offset by less than one tick, can disagree by one tick and by no other amount, so the only negative a floored cross-host difference can produce is  $-1000\mu\text{s}$ . The corpus contains 41,403 negatives and every one of them is that value.

Second, the Kafka corpus’s 10,913,263 discarded samples contain no negative at all, because a difference taken inside one process has no second clock to disagree with. The same guard therefore hides two different failures — a resolution failure under Kafka and a clock failure under Redis — and an unsigned discard counter could not tell them apart.

It also means the two drivers do not share a measurand: Kafka’s span is client-to-client on one clock, Redis’s server-to-client across two. A comparison of the two numbers as though they measured the same interval is a further error the harness invites and does not flag.

#### S54. THE PERMUTATION NULL, CONSTRUCTED (MOVED FROM THE MAIN TEXT)

Section IV-C names the test and reports its verdicts. This is how the null is built, which matters because the null is the whole content of the claim: a continuum hypothesis has to be turned into a distribution before anything can reject it.

For each arm, let  $D$  be the mean distance from its replicates to the nearest vertex of the  $q$ -grid, normalized by the cell half-width. Under the continuum null, retention is a continuous function of rate, so a replicate’s position within its cell carries no information and the positions are exchangeable and uniform on the cell. The null distribution of  $D$  is therefore obtained by permuting replicate positions within the arm:  $10^4$  permutations, which fixes the smallest attainable  $p$  at  $2.5 \times 10^{-4}$  and is why no arm reports a  $p$  below that value however far it sits from the diagonal.

Two properties of this construction are worth stating because they bound what the test can say. It is exact under the null rather than asymptotic, which matters at  $n = 5$ . And it has no power at all where the grid and continuum predictions coincide, which is not a weakness to be apologized for but the reason the two arms at those rates are reported as untestable rather than as evidence — a test that separated them everywhere would be measuring something other than what it claims.

#### S55. THE OVERNIGHT CAMPAIGN, PREDICTION BY PREDICTION (MOVED FROM THE MAIN TEXT)

Section IV-B reports the outcome in a sentence. This is the tally, because a pre-registration is worth what its failures are worth and three of these failed.

Sixty-three cells ran at  $n \geq 5$  with six predictions and their falsifiers registered in advance. Every cell completed validly. One prediction was confirmed, three falsifiers fired, one was not evaluable and one split.

*Duration invariance, which killed the drift account:* If retention were set by an accumulating drift, longer runs would sit further from the grid than shorter ones. Intermediate counts over one, three and ten minutes are 1, 1 and 0, with the vertices pinned throughout. Nothing accumulates. What remains is per-send jitter, which is the mechanism the retention law of Section IV assumes and not one we chose after seeing the data.

*The linear extrapolation that failed:* One registered prediction assumed retention would extrapolate linearly in rate across the incommensurate arms. At 1053 and 1219 msg/s the measured values are 47.2 and 48.2% — flat where the prediction wanted a slope. The grid law does not predict a trend in rate, only a position against the tick, so the failure is of the extrapolation rather than of the law; we record it because it was registered and it did not come true.

## REFERENCES

- [1] Apache Kafka, “KIP-526: Reduce producer metadata lookups for large number of topics,” Apache Software Foundation, Kafka Improvement Proposal, 2020, documents the metadata fetch a producer performs before its first send to an uncached topic.
- [2] StatsBomb, “Statsbomb open data,” *GitHub Repository*, 2023. [Online]. Available: <https://github.com/statsbomb/open-data>
- [3] H. Liu, W. Hopkins, A. M. Gomez, and J. S. Molinuevo, “Inter-operator reliability of live football match statistics from opta sportsdata,” *International Journal of Performance Analysis in Sport*, vol. 13, no. 3, pp. 803–821, 2013.
- [4] L. Pappalardo, P. Cintia, A. Rossi, E. Massucco, P. Ferragina, D. Pedreschi, and F. Giannotti, “A public data set of spatio-temporal match events in soccer competitions,” *Scientific Data*, vol. 6, no. 1, p. 236, 2019.
- [5] M. Mohammad, “Analysis of design patterns and benchmark practices in Apache Kafka event-streaming systems,” *arXiv preprint arXiv:2512.16146*, 2025.
- [6] T. Downs, “Grow buffer if histogram can’t fit (pull request #398),” OpenMessaging Benchmark, commit 4eb2327c, Dec. 2023, fixes issue #369: truncated histogram serialisation silently discarded most latency samples. <https://github.com/openmessaging/benchmark/pull/398>; accessed 19 August 2026.
- [7] J. Vanlightly, “Kafka versus Redpanda performance — do the claims add up?” <https://jack-vanlightly.com/blog/2023/5/15/kafka-vs-redpanda-performance-do-the-claims-add-up>, May 2023, a second, independent silent-loss defect in the same harness.
- [8] T. Mytkowicz, A. Diwan, M. Hauswirth, and P. F. Sweeney, “Producing wrong data without doing anything obviously wrong!” in *Proc. 14th Int. Conf. Architectural Support for Programming Languages and Operating Systems (ASPLOS)*. ACM, 2009, pp. 265–276.
- [9] A. Georges, D. Buytaert, and L. Eeckhout, “Statistically rigorous Java performance evaluation,” in *Proc. 22nd ACM SIGPLAN Conf. Object-Oriented Programming, Systems, Languages and Applications (OOPSLA)*. ACM, 2007, pp. 57–76.
- [10] E. Barrett, C. F. Bolz-Tereick, R. Killick, S. Mount, and L. Tratt, “Virtual machine warmup blows hot and cold,” *Proceedings of the ACM on Programming Languages*, vol. 1, no. OOPSLA, pp. 52:1–52:27, 2017.
- [11] A. Maricq, D. Duplyakin, I. Jimenez, C. Maltzahn, R. Stutsman, and R. Ricci, “Taming performance variability,” in *Proceedings of the 13th USENIX Symposium on Operating Systems Design and Implementation (OSDI)*. USENIX Association, 2018, pp. 409–425.
- [12] T. Kalibera and R. Jones, “Rigorous benchmarking in reasonable time,” in *Proceedings of the 2013 International Symposium on Memory Management (ISMM)*. ACM, 2013, pp. 63–74.
- [13] E. van der Kouwe, G. Heiser, D. Andriesse, H. Bos, and C. Giuffrida, “SoK: Benchmarking flaws in systems security,” in *Proc. 4th IEEE EuroS&P*. IEEE, 2019, pp. 310–325.
- [14] T. Hoefler and R. Belli, “Scientific benchmarking of parallel computing systems: Twelve ways to tell the masses when reporting performance results,” in *Proc. Int. Conf. High Performance Computing, Networking, Storage and Analysis (SC)*. ACM, 2015, pp. 73:1–73:12.
- [15] H. Weyl, “Über die gleichverteilung von zahlen mod. eins,” *Mathematische Annalen*, vol. 77, pp. 313–352, 1916.
- [16] V. T. Sós, “On the distribution mod 1 of the sequence  $n\alpha$ ,” *Annales Universitatis Scientiarum Budapestinensis, Sectio Mathematica*, vol. 1, pp. 127–134, 1958.
- [17] L. Schuchman, “Dither signals and their effect on quantization noise,” *IEEE Transactions on Communication Technology*, vol. 12, no. 4, pp. 162–165, 1964.
- [18] S. McCanne and C. Torek, “A randomized sampling clock for CPU utilization estimation and code profiling,” in *Proc. USENIX Winter Technical Conf.*, 1993, pp. 387–394.
- [19] OpenMessaging Project, Linux Foundation, “The OpenMessaging benchmark framework,” 2018, available at [openmessaging.cloud/docs/benchmarks/](https://openmessaging.cloud/docs/benchmarks/); accessed 19 August 2026.
- [20] J. Ousterhout, “Always measure one level deeper,” *Communications of the ACM*, vol. 61, no. 7, pp. 74–83, 2018.
- [21] J. Li, N. K. Sharma, D. R. K. Ports, and S. D. Gribble, “Tales of the tail: Hardware, OS, and application-level sources of tail latency,” in *Proc. ACM SoCC*. ACM, 2014.
- [22] J. Dean and L. A. Barroso, “The tail at scale,” *Communications of the ACM*, vol. 56, no. 2, pp. 74–80, 2013.
- [23] J.-P. Lozi, B. Lepers, J. Funston, F. Gaud, V. Quéma, and A. Fedorova, “The Linux scheduler: a decade of wasted cores,” in *Proc. 11th European Conf. Computer Systems (EuroSys)*. ACM, 2016, pp. 1–16.
- [24] A. Sharma, D. Shah, D. Larivière, and H. ElBakoury, “Time, causality, and observability failures in distributed AI inference systems,” *arXiv preprint arXiv:2604.21361*, Apr. 2026, open Compute Project, Unified Intelligent Infrastructure workstream.
- [25] L. Kleinrock, *Queueing Systems: Volume I - Theory*. Wiley-Interscience, 1975.
- [26] P. B. Danzig and S. Melvin, “High resolution timing with low resolution clocks and a microsecond resolution timer for sun workstations,” *ACM SIGOPS Operating Systems Review*, vol. 24, no. 1, pp. 23–26, Jan. 1990.
- [27] S. Herrleben, M. Leidinger, V. Lesch, T. Prantl, J. Grohmann, C. Krupitzer, and S. Kounev, “ComBench: A benchmarking framework for publish/subscribe communication protocols under network limitations,” in *Performance Evaluation Methodologies and Tools (VALUETOOLS 2021)*. Springer, 2021.
- [28] G. Tene, “How NOT to measure latency,” 2015, talk, Strange Loop / QCon; coined “coordinated omission”.
- [29] —, “HdrHistogram: A high dynamic range histogram,” 2015, used by the OpenMessaging Benchmark; available at [hdrhistogram.org](https://hdrhistogram.org).
- [30] R. A. Wannamaker, S. P. Lipshitz, J. Vanderkooy, and J. N. Wright, “A theory of nonsubtractive dither,” *IEEE Transactions on Signal Processing*, vol. 48, no. 2, pp. 499–516, 2000.
- [31] S. Yang, J. Jeong, B. Scholz, and B. Burgstaller, “Cloudprofiler: TSC-based inter-node profiling and high-throughput data ingestion for cloud streaming workloads,” *arXiv preprint arXiv:2205.09325*, 2022.
- [32] F. N. Bostanci, H. Luo, A. Olgun, M. Makeenkova, G. F. de Oliveira, A. G. Yaglikci, and O. Mutlu, “Cleaning up the mess: Re-evaluating the real-system modeling accuracy of Ramulator 2.0,” *arXiv preprint arXiv:2510.15744v4*, May 2026, shows a MICRO best-paper runner-up with all three artifact badges, including Reproducible, reported incorrect simulator results through configuration errors and could not rebuild its own key results; argues for mechanisms to correct results and artifacts after publication. Read 2026-09-03.
- [33] Apache Software Foundation, “Apache Kafka tools — EndToEndLatency.java and ProducerPerformance.java,” Source repository, 2026, <https://github.com/apache/kafka>; the percentile array is filled by integer division, `latencies[i] = elapsed / 1000 / 1000`, while each sample prints at full precision. Read 2026-08-31.
- [34] Apache Pulsar contributors, “PerformanceConsumer.java,” Source repository, 2026, <https://github.com/apache/pulsar>. Read 2026-08-21.

- [35] Synadia, “NATS cli — cli/latency\_command.go,” Source repository, 2026, <https://github.com/nats-io/natscli>; the wall-clock difference is appended unconditionally. Read 2026-08-31.
- [36] Broadcom, “RabbitMQ PerfTest — Consumer.java,” Source repository, 2026, <https://github.com/rabbitmq/rabbitmq-perf-test>; the cross-process difference is passed to the metrics unfiltered. Read 2026-08-31.
- [37] IOP Systems, “Rezulus: systems performance telemetry — scheduler\_discarded\_samples,” Source repository, 2026, <https://github.com/iopsystems/rezulus>; counts samples discarded for out-of-order timestamps. Read 2026-08-20.
- [38] A. D. Brunelle, “blktrace/btt — btt/inlines.h,” Source repository, 2026, `tdelta()` returns one nanosecond when the stage timestamps are out of order: `return (from < to) ? (to - from) : 1;`. Read 2026-08-20.
- [39] EMQ Technologies, “emqtt-bench: MQTT benchmark tool — src/emqtt\_bench.erl,” Source repository, 2026, <https://github.com/emqx/emqtt-bench>; the guard is on the counter, not the sample. Read 2026-08-21.
- [40] J. Axboe, “fio: Flexible I/O tester — gettime.c,” Source repository, 2026, <https://github.com/axboe/fio>; the guard is in three timing functions. Read 2026-08-20.
- [41] G. Tene, “wrk2 — src/wrk.c,” Source repository, 2026, <https://github.com/giltene/wrk2>; the negative is detected, printed, and recorded unguarded; the vendored `hdr_histogram.c` bounds-checks the derived index behind live assertions. Read 2026-08-21.
- [42] HdrHistogram contributors, “HdrHistogram\_c — src/hdr\_histogram.c,” Source repository, 2026, [https://github.com/HdrHistogram/HdrHistogram\\_c](https://github.com/HdrHistogram/HdrHistogram_c); upstream’s `hdr_record_values` refuses a negative value outright — the guard `wrk2`’s vendored copy lacks. Read 2026-08-21.
- [43] Y. Mittal, “An empirical study of open-loop load generators for microservices and web workloads,” Master’s thesis, University of Illinois Urbana-Champaign, 2025, <https://hdl.handle.net/2142/129222>; behavioural evaluation of six open-loop generators. Read 2026-08-21.
- [44] Apache Kafka contributors, “KAFKA-19888: Clamp negative values in coordinator histograms,” Issue tracker and pull request #20986, 2025, <https://issues.apache.org/jira/browse/KAFKA-19888>; merged 2025-11-26, shipped in 4.2.0, backported to 4.0.2/4.1.2. Read 2026-08-21.
- [45] Network-Based Computing Laboratory, Ohio State University, “OSU micro-benchmarks 7.5 — osu\_latency,” <https://mvapich.cse.ohio-state.edu/benchmarks/>, 2025, `c/mpi/pt2pt/standard/osu_latency.c` divides the round trip by two; the documentation reports “average one-way latency”. Read 2026-08-20.
- [46] D. Turner and X. Chen, “NetPIPE: A network protocol independent performance evaluator,” <https://netpipe.cs.ksu.edu/>, 2025, “Latencies are calculated by dividing the round trip time in half for small messages”. Read 2026-08-20.
- [47] Intel Corporation, “Intel MPI benchmarks — PingPong,” Intel MPI Library User Guide, 2021, “Reported timings —  $\text{time} = \Delta t/2$ ”; the companion `PingPing` reports the unhalved time. Read 2026-08-20.
- [48] S. Hunold and A. Carpen-Amarié, “Reproducible MPI benchmarking is still not as easy as you think,” *IEEE Transactions on Parallel and Distributed Systems*, vol. 27, no. 12, pp. 3617–3630, 2016.
- [49] Confluent, “librdkafka introduction — delivery reports,” <https://github.com/confluentinc/librdkafka>, 2026, the `delivery-report` callback `dr_msg_cb` is served by `rd_kafka_poll()` and other queue-serving calls, so it runs on the application’s thread rather than asynchronously. Read 2026-08-20.
- [50] J. Axboe, “fio HOWTO — interpreting the output,” <https://fio.readthedocs.io/>, 2026, for asynchronous ioengines completion latency runs “to when the I/O’s completion was reaped by fio”. Read 2026-08-20.
- [51] Advanced Micro Devices, “HIP runtime API: Event management,” <https://rocm.docs.amd.com/projects/HIP/en/latest/>, 2026, under `hipEventElapsedTime()`: “the time that the event recorded may be significantly after the host calls `hipEventRecord()`”. Read 2026-08-20.
- [52] NVIDIA Corporation, “CUDA C++ best practices guide, using CUDA GPU timers,” <https://docs.nvidia.com/cuda/cuda-c-best-practices-guide/>, 2026, section 9.1.2: “The device will record a timestamp for the event when it reaches that event in the stream.” Read 2026-08-20.
- [53] Mellanox Technologies, “sockperf: network benchmarking utility,” <https://github.com/Mellanox/sockperf>, 2026, the run summary prints `SentMessages`, `ReceivedMessages` and `SkippedMessages` beside the latency percentiles, and a dropped/duplicated/out-of-order line derived from sequence numbers. Read 2026-08-20.
- [54] OpenTelemetry Authors, “OpenTelemetry metrics data model — exponential histogram: Zero count and zero threshold,” <https://opentelemetry.io/docs/specs/otel/metrics/data-model/>, 2026, `zero_count` holds values at or below a zero threshold, including “values that have been rounded to zero”; `count` is defined to include it. Read 2026-08-20.
- [55] A. Klenik and A. Pataricza, “Adding semantics to measurements: Ontology-guided, systematic performance analysis,” *Acta Cybernetica*, 2022, arXiv:2112.11270; negative derived durations in a Hyperledger Fabric benchmark, traced to peer clock drift.
- [56] R. Durairajan, S. K. Mani, P. Barford, R. Nowak, and J. Sommers, “TimeWeaver: Opportunistic one way delay measurement via NTP,” in *Proc. 30th International Teletraffic Congress (ITC 30)*, 2018, pp. 185–193, retains samples that earlier methods discarded, including negative latencies, by assigning them to lower accuracy tiers.
- [57] EEMBC, “CoreMark-PRO run rules,” <https://github.com/eembc/coremark-pro>, 2026, “Each workload must run for at least 1000 times the minimum timer resolution.” Plain CoreMark instead sets an absolute ten-second floor. Read 2026-08-20.
- [58] Standard Performance Evaluation Corporation, “SPEC power and performance benchmark methodology, version 2.3,” [https://www.spec.org/power/docs/SPEC-Power\\_and\\_Performance\\_Methodology.pdf](https://www.spec.org/power/docs/SPEC-Power_and_Performance_Methodology.pdf), 2025, clause 8.2.2, Power Reporting: the benchmark “should report the number of samples that may have a return value ‘Unknown’” and those exceeding the maximum allowed uncertainty. Read 2026-08-20.
- [59] S. Shalunov, B. Teitelbaum, A. Karp, J. W. Boote, and M. J. Zekauskas, “A one-way active measurement protocol (OWAMP),” Internet Engineering Task Force, RFC 4656, Sep. 2006.
- [60] ETSI, “Speech and multimedia transmission quality (STQ); QoS aspects for popular services in mobile networks; part 4: Requirements for quality of service measurement equipment,” European Telecommunications Standards Institute, Technical Specification TS 102 250-4 V2.3.1, Nov. 2019, clause 5.1, General requirement for data logging.
- [61] G. Almes, S. Kalidindi, M. Zekauskas, and A. Morton, “A one-way delay metric for IPPM,” Internet Engineering Task Force, RFC 7679, Jan. 2016, obsoletes RFC 2679. Section 3.5 keeps negative values as distribution data rather than discarding them.
- [62] Standard Performance Evaluation Corporation, “SPECjms2007 run and reporting rules, version 1.0,” <https://www.spec.org/jms2007/docs/RunRules.html>, 2014, clause 3.6.2 records delivery time as a histogram of default granularity 100 ms; the only timing-quality requirement is clause 3.2’s 100 ms bound on inter-node clock agreement. Read 2026-08-20.
- [63] K. Sachs, S. Kounev, J. Bacon, and A. P. Buchmann, “Performance evaluation of message-oriented middleware using the SPECjms2007 benchmark,” *Performance Evaluation*, vol. 66, no. 8, pp. 410–434, 2009.
- [64] zoxy-io, “zrk: a Zig rewrite of wrk2,” <https://github.com/zoxy-io/zrk>, 2026, “At the sub-millisecond latencies a fast service actually produces, that’s not a rounding error — it’s frequently larger than the number being measured”; the overshoot is recorded rather than discarded. Read 2026-08-21.
- [65] G. Tene, “wrk2: a constant-throughput, correct-latency variant of wrk,” <https://github.com/giltene/wrk2>, 2019, “measured latencies are only accurate to a  $\pm 1$  msec granularity, due to OS sleep time behavior” — disclosed, not discarded. Read 2026-08-21.
- [66] M. Kuperberg, M. Krogmann, and R. H. Reussner, “TimerMeter: Quantifying properties of software timers for system analysis,” in *Proc. 6th Int. Conf. Quantitative Evaluation of Systems (QEST)*, 2009, pp. 85–94.
- [67] Joint Committee for Guides in Metrology, “Evaluation of measurement data — guide to the expression of uncertainty in measurement (JCGM 100:2008),” [https://www.bipm.org/documents/20126/2071204/JCGM\\_100\\_2008\\_E.pdf](https://www.bipm.org/documents/20126/2071204/JCGM_100_2008_E.pdf), 2008, clause F.2.2.1, “The resolution of a digital indication”. Read 2026-08-20.
- [68] J. W. Pratt, “Remarks on zeros and ties in the Wilcoxon signed rank procedures,” *Journal of the American Statistical Association*, vol. 54, no. 287, pp. 655–667, 1959.
- [69] IEEE, “IEEE standard for terminology and test methods for analog-to-digital converters,” IEEE Std 1241-2010, 2011, §6.4.1, Eq. (28): the histogram test’s relatively-prime record condition; §5.4.1, Eq. (18):  $f_i = (J/M)f_s$ , named coherent sampling.

- [70] Linux Kernel Documentation, “KVM-specific MSRs: MSR\_KVM\_SYSTEM\_TIME\_NEW,” <https://docs.kernel.org/virt/kvm/x86/msr.html>, 2026, flag bit 0, CPUID 0x40000001 bit 24. Read 2026-08-21.
- [71] Z. Zhou, “sched: Reduce the default slice to avoid tasks getting an extra tick,” Linux kernel mailing list, commit 2ae891b82695, 2025, reviewed-by V. Guittot; reduces the constant to 0.70 in v6.15.
- [72] Y. Virkar and A. Clauset, “Power-law distributions in binned empirical data,” *The Annals of Applied Statistics*, vol. 8, no. 1, pp. 89–119, 2014.
- [73] Hewlett-Packard, “Time interval averaging,” Hewlett-Packard Company, Application Note 162-1, 1970, part no. 02-5952-0766; undated; the year is its *HP Journal* citation.
- [74] J. Rapp, R. M. A. Dawson, and V. K. Goyal, “Estimation from quantized Gaussian measurements: When and how to use dither,” *IEEE Transactions on Signal Processing*, vol. 67, no. 13, pp. 3424–3438, 2019.
- [75] V. Raisanen, G. Grotefeld, and A. Morton, “Network performance measurement with periodic streams,” Internet Engineering Task Force, RFC 3432, Nov. 2002.
- [76] Jaeger contributors, “model/adjuster/clockskew.go,” <https://github.com/jaegertracing/jaeger>, 2026, at v1.57.0; adjusters run in the query service, and the default has been off since v1.20.0. Read 2026-08-21.
- [77] —, “Clock skew adjuster considered harmful (issue #1459),” Issue tracker, 2019, <https://github.com/jaegertracing/jaeger/issues/1459>. Read 2026-08-21.
- [78] A. Swami and N. Chougule, “Architecture dependent temporal observability under deployment interference in edge inference systems,” *arXiv preprint arXiv:2605.17701*, 2026.
- [79] T. C. Paul, P. Lertpongrijikorn, H. D. Nguyen, and M. Amini Salehi, “Benchmarking message brokers for IoT edge computing: A comprehensive performance study,” *arXiv preprint arXiv:2603.21600*, 2026, introduces mq-bench: nanosecond send stamps, one host, no positivity guard. Read 2026-08-25.
- [80] M. Fruth, S. Scherzinger, W. Mauerer, and R. Ramsauer, “Tell-tale tail latencies: Pitfalls and perils in database benchmarking,” in *Performance Evaluation and Benchmarking (TPCTC)*. Springer, 2021, pp. 119–134.
- [81] Y. Zhang, D. Meisner, J. Mars, and L. Tang, “Treadmill: Attributing the source of tail latency through precise load testing and statistical inference,” in *Proc. 43rd ACM/IEEE Int. Symp. Computer Architecture (ISCA)*, 2016.
- [82] F. Cerqueira and B. B. Brandenburg, “A comparison of scheduling latency in Linux, PREEMPT\_RT, and LITMUS^RT,” in *Proc. 9th Annual Workshop on Operating Systems Platforms for Embedded Real-Time Applications (OSPERT)*, 2013, pp. 19–29, footnote 7 bounds worst-case scheduling latency below by the quantum length under a quantum-driven scheduler.
- [83] Index.dev, “NATS vs Redis vs Kafka: message broker comparison,” Practitioner comparison, 2026, <https://www.index.dev/skill-vs-skill/nats-vs-redis-vs-kafka>; gives Kafka “sub-10ms latency at p99” and gives Redis and NATS no percentile at all, only “sub-millisecond”. No retained fraction, rejection count, timestamp resolution or send rate. Re-read 2026-09-03: an earlier note here quoted a Redis p99 of 0.8 ms against Kafka’s 12.5 ms, which is not on the page and has been withdrawn. Traced 2026-09-04: those figures belong to `devto2026streaming` below, which a search had returned in the same result set.
- [84] Y. Gao, “Real-time event streaming: Kafka vs Redis Streams vs NATS in 2026,” Practitioner comparison, 2026, [https://dev.to/young\\_gao/real-time-event-streaming-kafka-vs-redis-streams-vs-nats-in-2026-3401](https://dev.to/young_gao/real-time-event-streaming-kafka-vs-redis-streams-vs-nats-in-2026-3401); ranks the three on “End-to-end latency (p99)” and gives Redis Streams 0.8 ms, NATS JetStream 3.2 ms and Kafka 12.5 ms, with a summary table reading “<1ms / 1-5ms / 5-20ms”. Method given in full as “Tested on 3-node cluster, 8 vCPU, 32GB RAM each” and “benchmarks based on production deployments”; no tool, timestamp source, synchronization statement, resolution or discard count. Read 2026-09-04, and the source of the figures withdrawn from `indexdev2026brokers` above.
- [85] Openbenchmarks, “How voice agent latency is measured,” Methodology page, 2026, <https://openbenchmarks.com/voice-agent-latency/how-voice-agent-latency-is-measured>; both endpoints on one clock, discard counts published per platform and per reason, and differences below the detector’s resolution not claimed. Read 2026-08-31.
- [86] A. Klenik and I. Kocsis, “Porting a benchmark with a classic workload to blockchain: TPC-C on Hyperledger Fabric,” in *arXiv preprint arXiv:2112.11277*, 2021, instruments the load generator itself: the “scheduling precision reserve” is the gap between when a transaction is picked and when it must be submitted, published as boxplots against terminal count. It “can drop below zero in the case of hundreds of terminals”, and the authors weigh that against the workload’s own timescale — the violation “never exceeds half a second” where TPC-C’s constraints “are in the order of magnitude of seconds”. The invalidated fraction is published too. Read 2026-09-04.
- [87] B. Krishnamachari, “How to do statistical evaluations in ECE/CS papers: A practical playbook for defensible results,” *arXiv preprint arXiv:2605.00428*, 2026, section 14, “Latency-Specific Pitfalls”, names three: the mean as a summary, coordinated omission, and warmup effects; section 18, “Outliers, failed runs, and exclusion rules”, is the nearest it comes to a discard rule. Over 31 pages the words timestamp, resolution, quantization and retention do not occur. Read 2026-09-03.
- [88] AutoMQ, “Kafka benchmark methodology: run fair comparisons,” Vendor methodology guide, May 2026, <https://www.automq.com/blog/kafka-benchmark-methodology-run-fair-comparisons>; covers workload profile, hardware normalization, durability contract and failure scenarios. Its whole treatment of what the instrument discards is the phrase “with outlier handling described”. Read 2026-09-03.
- [89] meshIQ, “ActiveMQ performance benchmarking: the complete methodology guide,” Practitioner guide, 2026, <https://www.meshiq.com/blog/activemq-performance-benchmarking-methodology/>, 21 July 2026. “The Seven Performance Benchmarking Errors” are co-locating the load generator with the broker, skipping JVM warmup, measuring only throughput, not running long enough, non-representative message sizes, triggering producer flow control, and not matching production configuration. Verified on two independent reads that *clock*, *timestamp*, *resolution* and *negative* do not occur on the page. Read 2026-09-04.
- [90] A. Chandrasekar and J. Kramberger, “Identifying and mitigating systemic measurement bias in production LLM inference benchmarks,” *arXiv preprint arXiv:2605.24217v2*, 2026.